FORM N: DETAILED SPECIFICATIONS 24003

SUPPLY AND INSTALLATION OF FLAT DECK FUELING TRUCK SERVICE BODY

INSTRUCTIONS FOR COMPLETION OF SPECIFICATIONS

- 1.1 All items in these specifications should be answered indicating compliance or non-compliance.
- 1.2 **Bidder shall state "yes" for compliance or state "deviation"**, or give a reply where requested to do so. Deviations and/or equivalents shall be clearly stated and fully detailed. Deviations and/or equivalents will be considered subject to evaluation. In every instance where a brand name or design specifications is used, the City will also consider deviations and/or equivalents.
- 1.3 Lengthy explanations of deviations may be included in a separate document and must reference the appropriate Detailed Specification.
- 1.4 Each Proponent is required to fill in every blank. Failure to do so may be used as a basis for rejection of bid.
- 1.5 It will be the responsibility of the Proponent to inform the City of any errors or omissions in these Detailed Specifications, for under this Contract, the Contractor shall be held responsible to ensure that the manufacturer will be responsible for the design, performance, reliability and satisfactory operational function of the unit.

2.0 DESCRIPTION OF EQUIPMENT

- 2.1 These specifications describe the supply and installation of a <u>Supply and Installation of Flat</u> <u>Deck Fueling Truck Service Body</u> and other equipment and features as specified herein.
- 2.2 The <u>Supply and Installation of Flat Deck Fueling Truck Service Body</u> shall be a new 2024 model year or newer.
- 2.3 The **Supply and Installation of Flat Deck Fueling Truck Service Body** and all other items/components shall be the manufacturer's latest model. The equipment shall be furnished complete and ready for operation. Any parts or accessories not specifically mentioned, but which are required to complete and place the equipment and associated attachments in successful operation shall be furnished as though specifically mentioned in these specifications. The equipment and associated attachments, and all parts thereof, shall conform in strength and quality of material and workmanship, to the best standards and engineering practice of the industry.
- 2.4 The ratings specified herein merely state the minimum values acceptable to the City, not implying that those values are sufficient for the design of the particular equipment being bid.

3.0 OTHER SPECIFICATIONS AND STANDARDS

- 3.1 All applicable SAE standards form an integral part of these specifications and shall have precedence in any conflict concerning minimum acceptable standards.
- 3.2 <u>Where applicable</u>, the <u>Supply and Installation of Flat Deck Fueling Truck Service Body</u> shall comply with the applicable regulations:

Standard - Specification/Regulation	Internet URL
Transport Canada, National Safety Mark, NSM:	http://www.tc.gc.ca/eng/acts-regulations/acts-road.htm
Manitoba Safety and Health Regulation, Parts 12, 16, 22:	http://web2.gov.mb.ca/laws/regs/current/217.06.pdf
Canadian Motor Vehicle Safety Standards C.M.V.S.S.:	<u>http://laws-</u> lois.justice.gc.ca/eng/regulations/C.R.C., c. 1038/sect ion-sched3.html

Standard - Specification/Regulation

Internet URL

Manitoba Highway Traffic Act regulations and requirements including, but not limited to, a Manitoba Government Inspection with Safety Sticker:

Canadian Standards Association CSA:

Under Writers of Canada U/L:

Society of Automotive Engineers SAE:

City of Winnipeg Lighting Visibility Standard:

Manitoba Building Code:

http://web2.gov.mb.ca/laws/regs/index.php?act=h60

http://www.csagroup.org

http://www.ulc.ca

http://www.sae.org

http://winnipeg.ca/matmgt/pdfs/PublicWorksEquipLighting Visibility.pdf

https://web2.gov.mb.ca/laws/regs/current/_pdfregs.php?reg=31/2011

- 3.3 <u>Where applicable</u>, the completed unit shall include a Manitoba Government Inspection with Safety Sticker.
- 3.4 <u>Where applicable</u>, the manufacturer/installer shall be a certified vehicle completer and must affix their National Safety Mark (NSM) certification sticker on each unit.

State NSM number:

4.0 <u>FUEL</u>

4.1 <u>Where applicable</u>, the equipment shall be fully fuelled upon delivery (no exceptions).

5.0 <u>REFERENCES</u>

5.1 If available, please provide five (5) references where this equipment is used in a working environment where climatic conditions are similar to the City of Winnipeg.

6.0 MAKE & MODEL

6.1 State year, make and model being bid:

Model Y	/ear:
Make:	
Model:	

7.0 PERFORMANCE RELIABILITY

7.1 The responsibility for the design of the **Service Bodies** its performance and reliability shall rest upon the Contractor.

- 7.2 The term "repeated failures" as used herein is defined to mean that the same component, subassembly, or assembly develops repeated defects, breakdowns and/or malfunctions rendering the vehicle inoperative, or requiring repeated shop correction, service and/or replacement during the warranty period applicable for said component, subassembly, of assembly. Minor items or ordinary service adjustments are not included, or considered under the scope of "repeated failures", as well as other factors, such as operational damage due to accidents, misuse or lack of proper maintenance, service and lubrication attention by not following the manufacturer's preventative maintenance schedule.
- 7.3 Where the <u>Service Bodies</u> develops "repeated failures" in service, the Contractor shall make any necessary engineering changes, repairs, alterations or modifications in order to guarantee reliability of performance.
- 7.4 The equipment shall be capable of consistent top performance in City of Winnipeg Environment. Note: The City of Winnipeg has four seasons with ambient temperatures ranging from approximately 90°F (32°C) to -40°F (-40°C).

8.0 SERVICE FACILITY

8.1 For the purpose of warranty repairs, the Bidder shall have an authorized service facility. The facility, or a portion thereof, shall be dedicated to the service and maintenance of the type equipment being offered. Bidders shall provide a description of the service facility including, but not limited to, number of qualified service staff, years of service experience, and general service capabilities within three (3) Business Days upon request of the Contract Administrator.

9.0 QUALIFICATIONS OF MANUFACTURER & CONTRACTOR

- 9.1 The manufacturer of the <u>Service Bodies</u> shall have five (5) years continuous experience manufacturing <u>Service Bodies</u>.
- 9.2 The manufacturer shall have in effect a documented quality control program ensuring that the quality of materials and workmanship, including welding, conforms to the best standards and engineering practice of the industry.
- 9.3 The Contractor shall have five (5) years continuous experience servicing, repairing and maintaining <u>Service Bodies</u> of the type being offered.

Representative Picture Typical Completed Flat Deck Fueling Truck Service Body on Truck Chassis, Pictured below – Passenger's Side View (R1).



10.0 SPECIFICATIONS

Scope

10.1 Supply and Delivery of <u>Flat Deck Fueling Truck Service Body</u> complete with steel deck which will be mounted on a City owned cab and chassis.

The **<u>Flat Deck Fueling Truck Service Body</u>** shall be capable of consistent top performance for loading and hauling varying payloads year-round in conditions normal to the City of Winnipeg.

Body and accessories to be mounted by a CMVSS certified installer in accordance with CMVSS regulations as well as the chassis and body manufacturers recommendations.

Note:

The City of Winnipeg has four seasons with ambient temperatures ranging from approximately $90^{\circ}F(32^{\circ}C)$ to $-40^{\circ}F(-40^{\circ}C)$

Make and Model – Service Bod

	Make	State: make:
10.2	Model	State: model:
10.3	Model Year	State: model year:
	Body Weights	
10.4	Body Weight – Service Body	State: estimated weight of service body
10.5	the completed unit	ertified weigh scale ticket upon delivery of nt and rear axle weights including two (2) ull of fuel.
	Manitoba Inspection (MGI)	
10.6	 The Contactor shall provide com completed unit. 	npleted/valid MGI upon delivery of the

• MGI documentation shall be valid upon release in accordance with an approximate 12-month period application or effectiveness.

Installation

Flat Deck Fueling Truck Service Body will be installed on the following

10.7

City owned cab & chassis vehicle:

	ty Winnipeg tment/Customer	Vehicle Type/Style	Quantity	Description	New Vehicle Unit Number (WFMA)
PW-PA	RKS-SOUTH	2024 Ford F-550	1	19,500 lbs. GVWR Diesel, 4WD Extended Cab. Cab; 60 (Cab to Axle Length CA), 7.3 L, V8 Gasoline engine TorqShift® 10-Spd. Automatic Horizontal discharge exhaust, Ford Oxford White Code Z1	2303330
10.8	<u>Availability</u>			e cab chassis will be available during the cond quarter of 2024	9
10.9	Pick-Up		 The Contractor shall be responsible for picking-up the chassis cab vehicles from the City upon commencement of the Contract 		
			a A	The vehicles will be available for pick-up at the Winnipeg Fleet Management Agency, 185 Tecumseh St., Winnipeg, Manitoba	
			a	Pick-up times will be between 8:00 am and 2:00 pm on any Monday to Friday Business Day	
			a	The Contractor shall be responsible for any related fuel and Insurance costs to and from their facility	
				te: The vehicles will be fully fuelled at time of pick-up by the Contractor	

10.10 Drawings

Drawings – Contractor shall supply

- The Contractor shall supply multi-view CAD drawings to the Contract Administrator upon Award of Contract
- Drawings will be reviewed and approved as part of the Pre-Production planning stages
- Contractor to provide a weight analysis after pre-production meetings
- Drawings are to include all dimensions, materials, and specifications as required
- Drawings are to be revised as requested by the City
- Multiple drawing iterations may be required
- Construction of the service body shall not commence until approval is granted
- Note: Drawings can be supply as hard copies, PDF's or electronically

Steel/Galvanized Flat Deck Fueling Truck Service Body

10.11 Material Fabricate steel/galvanized flat deck capable of support two (2) transfer tanks, tires, tool compartments and miscellaneous shop tools for mobile repairs Any other material used in the fabrication should be corrosion-resistant; i.e. 10 gauge 5052-H32 marine grade alumimum is acceptable • The mill certification for the all materials grades should be available upon request; Steel, galvanized, 5052-H32 alumimum marine grade shall be provided or available to the inspector upon request or Contract Administrator. Double sided construction • Internally reinforced compartment doors 10.12 Left in natural unpainted service body **Compartment Interiors** finish 10.13 **Compartment Layout** • one (1) front vertical storage compartment which is situated behind front cab and is the entire width of the flat deck and one shelf position





Air compressor in front vertical compartment and accessible

Each side of vehicle to have:

• one (1) horizontal storage compartment behind front cab and mounted under the flat deck

approximately in the middle of the compartment to accommodate air

compressor

• one (1) rear storage horizontal compartment mounted under flat deck behind the wheel well

Picture showing lower storage compartments Mounted under the flat deck



General Dimensions


For the purpose of these specifications:

- L Length along or parallel to chassis longitudinal axis.
- H Height, vertical.
- D Depth on horizontal plane across vehicle

Note: Unless otherwise specified, all dimensions are in inches and are the nominal sizes.

- Left and right is always based on perspective when sitting in the vehicle, so:
- Driver side is the left L1
- > Passenger side is on the right R1.
- The designations for the <u>Driver's side</u> may be referred to as <u>L1</u> within the documentation.
- The designations for the <u>Passenger's side</u> may be referred to as <u>R1</u> within this documentation.

10.14	Body Flat Deck Height	Driver's Side – L1	
	Ū	Sate:	
		Passenger's Side – R1	
		Sate:	
		State: Body Height:	
10.15	Body Length	Approximately 132" inches (work platform included) State: Body Length:	
10.16	Body Width	Approximately 90" – 96" inches State: Body Width:	



Flat Deck Fueling Truck Service Body Compartment Layout, Driver's Side (L1)

The present configuration of the flat deck fueling truck service body compartments. (Driver's Side – L1)

COMPARTMENT SIZES – Approximate Dimesnions			
1 32" height x 20 width Approximate Width of flat deck			
2 18" height x 30" length Approximate		18" D	
3	18" height x 24" length Approximate	18" D	

10.17 Front Vertical Compartment #1 (Behind truck cab)

Compartment #1

- Compartment # 1
- Approximately 32" inches height x 20" inches width x with of flat deck
- One shelf, approximate in the middle height location of compartment
- Accommodate compressor
- 250 lb. minimum load capacity

State:

Compartment Size: _

Compartment #2

- Compartment # 2
- "Weather guard" Alumimum underbed toolboxes (Model 631-0-02 Under Bed Box, Alumimum, Compact, 5.4 cu ft) or equivalent style and functionality
- Approximately 13.5" inches height x 30" inches width x 18" inches depth
- 250 lb. minimum load capacity

State:


Compartment Size:

10.18 Horizontal Compartment #2 (Front horizontal storage compartment behind truck cab) Mounted under flat deck 10.19

Compartment #3

- Compartment # 3
- Rear Horizontal Compartment #3 • "Weather guard" Alumimum underbed (Back horizontal storage compartment Behind wheel well) Mounted under flat deck
 - toolboxes (Model 627-0-02 Under Bed Box, Alumimum, Compact, 4.3 cu ft or equivalent style and functionality
 - Approximately 23" inches height x 9/-3/4" inches width x 18" inches depth
 - 250 lb. minimum load capacity

Flat Deck Fueling Truck Service Body Compartment Layout, Passenger's Side (R1)



Front horizontal storage compartment

The present configuration of the flat deck fueling truck service body compartments. (Passenger's Side - R1)

COMPARTMENT SIZES – Approximate Dimesnions			
1 32" height x 20" width Approximate Width of flat deck			
2	18" D		
3	18" height x 24" length Approximate	18" D	

10.20 Front Vertical Compartment #1 (Behind truck cab) • Compartment # 1

Compartment #1

- Approximately 32" inches height x 19.5" inches width x with of flat deck
- One shelf, approximate in the middle height location of compartment
- Accommodate compressor
- 250 lb. minimum load capacity

State:

Compartment Size: ___

Horizontal

Compartment #2

(Front horizontal storage

Mounted under flat deck

compartment behind truck cab)

10.21

Compartment #2

- Compartment # 2
- "Weather guard" Alumimum underbed toolboxes (Model 631-0-02 Under Bed Box, Alumimum, Compact, 5.4 cu ft) or equivalent style and functionality
- Approximately 13.5" inches height x 30" inches width x 18" inches depth
- 250 lb. minimum load capacity

State:

Compartment Size:

Compartment #3

- Compartment # 3
- "Weather guard" Alumimum underbed toolboxes (Model 627-0-02 Under Bed Box, Alumimum, Compact, 4.3 cu ft or equivalent style and functionality
- Approximately 23" inches height x 9/-3/4" inches width x 18" inches depth
- 250 lb. minimum load capacity
- Installation of a Pack Rat Drawer Unit or equivalent to be access from Driver's side of the Cab, (L1).

Final size to be determine a preproduction meeting and finalized by Contract Administrator.

Representative Picture of Pack Rat
Drawer System for installation in
extended cab area.This image shown for illustration
purposes only and may not be an
exact representation of the final
product but should be a similar
configuration and style functionality.

Fuel Tanks – Slip/Transfer Tanks

10.24 Slip Tanks

Slip Tank – Flat Deck Installation

- Installation meets Canadian General Standards Board updated the CAN/CGSB-43.146 Standard
- Required Installation of one (1) slip Tank Diesel - 545 Liters minimum
- Required Installation of one (1) slip Tank Gas- 290 Liters minimum

- 10.22 Rear Horizontal Compartment #3 (Back horizontal storage compartment Behind wheel well) Mounted under flat deck
- 10.23 Extended Cab Area



10.25 12 Volt Fuel Transfer Pump


12V Fuel Transfer Pump with fuel meter installed for each slip tank. One for Desiel tank and one for gas tank. Transfer pump must have minimum:

- Transfer pump equipment to be mounted and accessible on Passenger side of vehicle (R1)
- Flowrate: Up to 15 GPM (57 LPM)
- Duty Cycle: 30 mins. On / 30 mins. Off

12 Volt Fuel Transfer Pump Required for each slip tank.




- 10.26 Heavy Duty Spring Retractable Bonding Reel
- Installation of Heavy-Duty Spring Retractable Bonding Reel on back of front vertical storage compartment; passenger side (R1).
- Model Number; Reelcraft G3050, serial Number 20200102 or equivalent make and model with same functionality and safety requirements.



10.27 Slip tanks mounted on flat deck behind front vertical storage compartment.





Pictures showing mounting of the transfer/slip tanks in the bed of the flat deck.

10.28 Placards

Gasoline and diesel require placards, with UN number, be visible on both sides of flat deck truck and on transfer tanks.



10.29 Industrial 100-Foot Air Hose Reel


10.30 Air Compressor

- Installation of industrial 100-foot retractable hose reel mounted on Driver's side (L1) on vertical storage compartment and easy associable.
 - Connect to air compressor in front vertical storage compartment.
 - Minimum 1.5 HP, 3.0 CFM, 120 volts plug connection, quick couplers and able to have fitted permanent connections.
 - Able to run in cold weather, and cold weather start-ups.
 - Oil free for less maintenance

10.31 Spare Tire Storage

- Three tire storage poles situated in the bed on the flat deck area
- Vertical pole diameter approximately 2-3/8" x 26" height
- Two (2) locations on the Drivers side location on the flat deck (L1)
- One (1) location on Passenger side location on the flat deck (R1)

Exact mounting location to be determined at pre-production meeting



Grab Handles

10.32 Safety Grab Access Handle

- 2.0" diameter grab safety handle for access to rear flat deck platform
- Located for ergonomic access to rear flat deck platform
- Qty one (1)
- Approximately, 2.0" diameter tubing x 3' feet tall.
- Slip resistant
- Bolt-on construction
- Primed and painted safety yellow

Design, mounting location and installation to be determined at a preproduction meeting



Planks - Black Polyboard Mandatory 10.33

- 2" x 6" Composite planks Sides and tailboard of flat deck
- Black in color on all sides
- Bolted in gussets
 <u>Wood material substitute not accepted</u>

Deck

Area

10.35

10.36

Flat Deck Fueling Truck Service Body Tailgate, Rear Compartment, Main Deck and Under Compartment

Main Deck Assembly

Pullout Deck Working Surface

- - Minimum 3/16" in. all steel galvanized checker plate
 - Approximately 28" inches, centered in the rear and located under flat deck.
 - Hinged cover which folds down to gain access to pull out work surface
 - Length of pull out deck 4' feet
 - 3/4" plywood top, interchangeable.





- 10.37 Under Deck Pull out Compartment Tailgate
- 3/16 in. aluminum construction
- Fold-down type with heavy duty hinges
- Chrome or stainless-steel paddle style door handle and latch
- Lubrication access points on hinge mechanism
- Hinge assembly and hinge pin is aluminum and has enough clearance that it will not seize up over time
- The end of the hinge is open and can be sprayed with lubricant if desired
- Rain lip or drip molding to prevent water from entering into the storage compartment
- Rain lip shall protrude to prevent water penetration, but shall not interfere with functionality



• 10 lbs. ABC fire extinguisher mounted on the flat deck behind front vertical compartment on Passenger side (R1)



Rear Bumper and Hitch

Fire Extinguisher

10.39 Rear Bumper

10.38

- Heavy duty step type bumper
- Tubular steel construction
- Galvanized
- Tapered at outer ends
- 12 in. steel grip strut surface
- Approximately 16 in. step height from ground
- 10.40 Auxiliary Step (Passenger Side (R1))
- Aluminum grip strut
 - Located on Passenger side an integrated into rear bumper



Exact mounting location and size to be determined at pre-production meeting

10.41 Dock Bumpers

- Rear mounted
- One (1) on each side of unit on the rear bumper
- Vertically mounted to a heavy-duty rear bumper frame to the rear of unit

Exact mounting location to be determined at pre-production meeting



Dock Bumpers

10.42 Rear Hitch

Hitch integrated into the rear bumper design, tow capacity 6000 lbs.

- 10.43 Eye Bolt or welded shackle (Required for Trailer Safety Chains)
- One (1) each side of hitch
- Eye bolt or welded shackle on bumper or equivalent style and functionality requirement for tower safety chains



Eye Bolts/ Weld on Shackles

Running Boards

10.44	Construction	Custom made: Extending entire length of underside of
		front and rear doors, each side. • AGS 6061 aluminum grip strut, 9-1/2"
		inches x 2.0" inches x 0.08" inches
		 Inside kick plate shall consist of 1/8" inches aluminum checker plate
		 Support brackets shall consist of 1-1/2"
		inches x 1-1/2" inches x 1/8" inches RC aluminum square tubing with 1/4"
		inches aluminum support plates
10.45	Mounting	Cab steps to be mounted using the existing holes in the frame and body
		where applicable
		 Use 3/8-16 nut inserts to secure the mounting brackets to the body



Running Boards

10.46	<u>Rear Fenders</u> Rear Fenders	 Heavy Duty rear poly half-moon fenders complete with steel mounting hardware or Aluminium wheel well covers
10.47	Trailer Equipment Trailer Connector	SAE J560 certified 7-Way Flat trailer receptacle mounted and installed in rear hitch plate complete with all necessary wiring
		Note: The cab and chassis will be supplied (unattached) with Ford OEM Trailer Plug Socket and Electric Trailer Brake Controller
		Installation to be determined at pre- production meeting

	<u> Standards – Flat Deck Service Body (Where Applicable)</u>				
10.48	Service Body/Truck Chassis	properly support	ust be attached to the truck chassis and ted. i.e. bolted and automotive grade U-bolts service body to truck chassis main frame		
		accordance with	service body and any equipment shall be in the chassis manufacturer's guidelines for ncluding, but not limited to, guidelines for tire clearances.		
		Note: in some cases, the following must be conducted in accordance with service body manufacturers specifications for installation.			
		installer in accor	sories to be mounted by a CMVSS certified rdance with CMVSS regulations as well as the ly manufacturers recommendations.		
		EXAMPLE: Ford & Ram Specific Requirements – The under structure of the service body must be attached to the truck frame using a minimum of four points. The front two mounts closest to the cab of the truck must be spring mounted.			
		Exception for Aerial/Crane Device equipped Service Bodies: If an aerial/crane device is involved, the body is to be spring mounted at the opposite end of the device at the two-service body under structure to truck frame attachment points.			
		 Doors s assemb Master l advertis 	Lock Rod System, if equipped, functions as ed, if not, adjust components e adjustments are made, perform a water		
10.49	Compartment	Floor Lining	Both horizontal compartments and front passenger side compartments shall be lined with Dri-Dek material or equivalent material having same material specifications		
10.50	Isolators		 All interfaces between aluminium and steel are to be separated by an approximately		
10.51	Drain Holes		All body compartments to include a ½ in. drain hole complete with plug		

10.52	Doors Design and Weather Stripping	Automotive door design with neoprene seals or equivalent seals having same specifications to minimize moisture and dust intrusion. Automotive grade weather tripping.	
10.53	Doors	 Each vertical compartment door is hinged vertically and equipped with a vinyl cover door chain to limit the door's opening range. The door swings open to a 90° angle. 	
10.54	Door Latches	Flush mounted with locks for all compartment doorsIt is required that all locks be keyed in the	
10.55	Cabinet Locks	 same manner. Service Body cabinets to be keyed to the same key for all cabinets. 	
10.56	Compartment Door Handles	 Tri-Mark door handles, Chrome plated or stainless-steel paddle style handles or equivalent model having same specifications 	
10.57	Door Hinges and Latches	Chromed or stainless steel with adjustable striker plates	
10.58	Compartment Door Openings	Sealed using automotive type bulb gasket door seal	
10.59	Front Vertical storage compartment Light (LED) System	 Front vertical storage compartment to be Illuminated with integrated high performance and long-life LED lighting. Actuated when the doors are opened 	
10.60	Wheel Well Area	 Shall incorporate a Fibreglass or rubber fender flare Wheel Well papels are removable 	

• Wheel Well panels are removable


	of Winnipeg o. 140-2024 Fleet 20200131	Form N: Detailed	l Specifications Page 21 of 37
10.61	Mud Flaps	 No name, fabric reinforced, black rubber mud flaps installed fore and aft of rear tires 1/2 in. diameter steel bar anti-sail brackets 	
10.62	Wheel Well Area	 Shall incorporate a fibreglass or rubber fender flare Wheel Well panels are removable 	
	Rear Bumper and Receiver –	Truck Chassis/Flat Deck Fueling Truck Servic	<u>e Body</u>
	Back-Up Alarm		
10.63	Back-Up Alarm	• SWS model 99202 or Whelen, Grote equivalent model having same specifications and functionality	
		 Mounted between frame rails at rear of vehicle Protected from damage and road spray/damage 	
	Rear View Camera		
10.64	Rear View Camera	 The cab and chassis will be supplied (unattached) with a rear-view camera Rear-view camera prep kit to include camera, screen (or displayed in rear view mirror) mounting hardware and OEM wiring harness To be installed by body supplier The installation of the rear-view camera is carried out by a professional installer in order to guarantee an unobstructed view during the process of reversing 	
	Picture showing location of m camera on back rear of flat de		


()

.

	Conspicuity Tape		
10.65	Conspicuity Tape	Truck-Lite 98127 or equal, affixed or equivalent model having same specifications	
	Inverter		
10.66	Inverter	 CSA approved 110 Volt, 3000 Watts minimum Make: Xantrex Model: XPower 3000 Inverter or equivalent rated unit model having same specifications or functionality Part Number: 813-3000-UL 	
		State: Make: Model:	
10.67	Deep Cycle Battery	 Group 31, approximately 900 CCA or equivalent Model AGM Battery/Deep Cycle Mounted in the same location as invertor 	

- in a reinforced compartment
 Battery Operating temperature range-40°F / -40°C to 140°F / +60°C
- Battery Cold Start Performance S.A.E J537





ODP-AGM31 LEFT POSITIVE STUD TERMINALS





Invertor and deep cycle AGM battery to be install/mounted in front top vertical storage compartment


10.68	Installation	 All exposed inverter terminals shall be: Coated with a dielectric grease Completely covered with or rubber fittings The battery lid cover supplied to provide protection for the terminals, ensuring their shielding. 	
10.69	Location	Invertor and deep cycle AGM battery to be install/mounted in front top vertical storage compartment.	
		Location to be confirmed at pre- production meeting.	
10.70	Wiring	 Invertor wired through ignition at the dash. Ensure to mounted inverter manufacturer remote switch Labeled Inverter to be complete with suitable solenoid and battery isolator The wiring should have the capability to carry approximately 14 volts of alternator charging voltage from the engine compartment (when engine running) to the deep cycle battery connected to the invertor. 	
10.71	Installation	 No exposed invertor terminals Terminals coated with a dielectric grease Completely coved with adhesive-sealant- lined shrink tubing must be used to guarantee joint integrity, waterproofing and strain relief or rubber fittings 	

10.72 Receptacle



- Two (2) required
- Duplex receptacle
- Mounted at front of service body, passenger and driver side (Passenger 's Side – R1) (Driver's Side – L1)
- Forward facing
- Mounted as high as practicable so as not to interfere with interior shelf positioning
- Two (2) required
- Duplex receptacle
- Mounted at inside front vertical compartment; Passenger and Driver's side.





- The Duplex receptacle shall be minimum 20 Amp, GFI, CSA approved
- Weatherproof type with hinged covers with <u>automatic cover closure/spring</u> closure mechanism built in to the housing cover.


Location to be confirmed at preproduction meeting.

Lighting

- 10.73 LED Lighting
- 10.74 L.E.D. Beacon Amber
- All safety waring lights shall be Class 2 or equivalent specification
- Whelen, SWS or Grote Series Amber LED Mini Light Bar or equivalent specifications and functionality
- Mounted to on the front vertical compartment (behind front truck cab)



- Protected by branch guard heavy duty construction
- Mini Light Bra shall be wired "Hot" (i.e. able to use without the key on) wired through a single OEM dash mounted switch or on the control panel enclosure. labelled "Light Bar" with a permanent type engraved style label
- Mounting of labels with 3M VHB Tape or equivalent
- Switch shall be capable of amber mode



Lighting – Where applicable/requirement in accordance with application.

10.75	Amber Strobe Lights	• Fou
	(Warning)	• Whe

- Four (4) total
- Whelen 5GA00FAR, or equivalent SWS or Grote Series LED lighting
- Mounting garments flush with service body
- Two (2) located outside of 3-Light cluster, rear facing in rear kick plate
- Two (2) located in the front grille
- Amber Strobes shall be wired "Hot" (i.e. able to use without the key on) wired through a single OEM dash mounted switch or on the control panel enclosure. labelled "Strobes" with a permanent type engraved style label
- Two (2) strobe lights in front Grille, (location to be confirmed at preproduction meeting and signed off by contract administrator).



• Two (2) amber strobe lights in lower flat deck back location of service body



Locations to be confirmed/finalized at pre-production meeting

10.76 Traffic Advisors

- SWS 67301, Whelen or Grote equivalent in functionality
- 1-piece aluminium with 1-1/2 square frame
- Aluminium front and rear panels
- Approximate size 44 in. H x 22 in. W x 3-3/8 in. D
- 10 dual optic, LED modules with half sun shade
- Six (6) flash patterns
- 20 ft. of cable per half
- In-cab controller SWS 77501 with 10A auxiliary port
- Traffic Arrows shall be wired "Hot" (i.e. able to use without the key on), wired through a single OEM dash mounted switch or on the control panel enclosure, labelled "Traffic Advisors" with a permanent type, engraved style label



10.77	Light Switch Configuration(s)	 Amber strobes (rear ovals) controlled with one switch 	
		 L.E.D. Beacon controlled with one switch capable of amber mode 	
		 Traffic Advisor – separate controller 	
10.78	Combination Turn/Stop and	• Top Mounted - One (1) per side	
	Taillights	 Bottom Mounted - One (1) per side 	
		 P/N Truck-Lite 44302R with P/N 44710 mounting grommets 	
10.79	Back-Up Lights	One (1) per side	
		 P/N Truck-Lite 44206C with P/N 44710 	<u></u>
		mounting grommets or equivalent with same functionality	
10.80	3-Light Cluster	• Three (3)	
		 P/N Truck-Lite10250R with P/N 10403 	
		mounting grommets or equivalent with same functionality	
		 Located to protect from damage 	

10.81	Clearance Lights	 Grote 49333 and 49332 with mounting grommets Or Truck-Lite 33050R and 33050Y with 3370 mounting grommets Whelen or Grote LED clearance lighting with same functionality may be substituted 	
10.82	Harness	Note: The clearance light on the service body must remain within the boundaries of the body itself. Truck-Lite 50 Series or equivalent harness system, properly routed, internally grounded and secured	
10.83	Rear Light Mounting Location (Rea	r Sill)	
	 Rear-Corner Clearance Lights, qty two (2), one per side Combination Turn/Stop and Taillights, qty two (2), one per side Back-Up Lights, qty two (2), one per side 		
	The lights shall be situated so that no debris or door opening contacts/obstructs		

Location of Lights to be confirmed at pre-production meeting

- 10.84 Rear Light Mounting Location (Top-Rear of Body)
 - Combination Turn/Stop and Taillights, qty two (2), one per side
 - Amber Strobe Lights, qty two (2), one per side
 - 3-Light Cluster, qty three (3)

Location of Lights to be confirmed at pre-production meeting

10.85 Clearance Light Mounting Locations:

the lights.

- Front qty two (2), located one on each bottom corner of body
- Sides qty two (2) per side, located on front and rear bottom corners
- Rear qty two (2), located one on each bottom or top corner

Location of Lights to be confirmed at pre-production meeting

	Welding Stand	ards_		
10.86	Welds		Continuous welds	
10.87	Standard	steel) and	V47.1-30, ertification of companies for fusion welding of W59, Welded steel construction).	
		Certification, CSA W59.2 - 20	<u>ole:</u> ion Welding of Aluminium Company 18 – Welded Aluminium Construction merican Welding Society (AWS)	
10.88	Weld Quality Ins	spection	 Straight and uniform Consistent thickness No spatter drops No slag, cracking or holes No dips or craters in the bead No holes, breaks or cracks in the bead/fillet Not Acceptable – cause for rejection. Lack of uniformity and straightness Visible spatter Cracking, undercutting or breaks in the bead 	
10.89	Weld Spatter		 Bead width inconsistent All weld spatter must be removed prior to final finish 	
	<u>Finish</u>			
10.90	Steel		Match chassis cab colour: Ford Oxford White Z1	
10.91	Aluminum Com	ponents	 Unfinished Material Grade corrosion-resistant 5052- H32 marine grade aluminum Mill certificates for the material utilized in the construction of the specific tender must be made accessible upon inquiny. 	
10.92	Galvanized		 must be made accessible upon inquiry All galvanized parts which move must be smoothed, cleaning or conditioning after the galvanizing process to ensure function and appearance requirements are met which may include removal of sharp edges, lumps and repaired 	
10.93	Deck		 Deck surface properly cleaned and coated with: Rust-Oleum AS5400 Anti-Slip Floor Covering or equivalent performance product Color Black 	

10.94	Preparation	All steel components unless otherwise noted in these specifications shall be sandblasted, properly cleaned, primed and finished with the Endura, DuPont or Tristar paint process in order to prevent rust formation	
10.95	Primer	Required: Epoxy or Polyurethane primer	
		Endura EP321 Intermix Epoxy Primer	
		or DuPont polyurethane	
		or Tristar Coatings Inc. Epoxy Primer	
		Two (2) coats – Dry Film Thickness 3.0 – 4.0 mils	
10.96	Paint	Required: Polyurethane Colour: 2023 Ford Oxford White Code Z1	
		Endura EX-2C	
		or DuPont Polyurethane	
		or Tristar Coatings Inc. Polyurethane	
		Two (2) coats: 3 - 5 mils Wet Film Thickness with a total combined overall average Dry Film Thickness of 4 – 6 mils	
	<u>Clearance</u>		
10.97	Clearance	Clearance between aluminium service body and the back of the truck cab shall be a minimum of 3" inches in accordance with the Cab & Chassis Incomplete Vehicle Manual.	
10.98	Tire Clearance	Aluminium service body shall provide for an approximate 4" inch clearance with rear springs fully loaded.	
	Installation		
10.99	Not-Permitted	Drilling on chassis frame flangesWelding on the chassis frame	
10.100	Installation Guide	-	
		be provided to the Contract Administrator for validation during the construction	
		phase. These instructions/guidelines pertain to the proper	
		installation/mounting of the body or equipment, following the chassis	
		manufacturer's guidelines for body mounting	
10.101	Holes	 When necessary and permitted in accordance with manufacturers 	
		specifications and regulations holes in the frame shall be drilled, remade and deburged to fit balts	
		deburred to fit bolts<u>Bolt holes shall not have excessive play</u>	
		 Holes required to run wires through shall be drilled and deburred (not punched), 	
		grommeted and sealed as required when permitted.	

10.102	Isolators	 All interfaces between aluminum and steel are to be separated by an approximate 1/16" inch thick rubber or neoprene sheet. Shall be bolted through with non-ferrous stainless-steel bolts and non-conductive
10.103	Mounting Brackets	bushings. • Shall be bolted to the frame using Grade-8 fasteners
10.104	Bolt Requirements	gh the entire ress concentration s the available bolt
40.405	Figure 3	Figure 1 ISO Class 8.8 bolts should not be confused with SAE Grade 8 bolts. ISO Class 10.9 bolts are equivalent to SAE Grade 8 bolts (6 radial embossed on the bolt head – Figure 2). ISO Class 8.8 bolts are equivalent to SAE Grade 5 bolts (3 radial embossed on the bolt head). Figure 3 shows an ISO Class 10.9 bolt head and a Nylock nut securing a separate bolt. Notice that both the bolt head and nut are installed with hardened washers and there are more than two threads protruding from the nut.
10.105	Mounting Standards	 Mounting of the body shall be in accordance with the chassis

accordance with the chassis manufacture's guidelines for body mounting, including but not limited to guidelines for tire and suspension clearance and fuel filler installation.

10.106	Mountings Standards	 If applicable the aluminum side packs shall be mounted to the steel deck using cadmium plated carriage bolts and fender washers Bearing plates shall be used in high stress areas. 	
10.107	Mounting Standards	 Any holes required in the fame if permitted must be drilled, reamed and deburred to fit the bolts. 	
10.108	Mounting Standards	 All non-continuous body seams (joints) shall be caulked with an automotive grade elastomeric sealant 	
10.109	Bolted Connections to Chassis Frame	• Mounting to the chassis frame is permitted however the bolt/nut assembly must have no gap or skewed connections are allowed; bolt/nut connection must be perpendicular to the clamping surface.	

• Not Recommended, However, if hole is to be drill to accommodate bolt/nut assembly, ensure hole is drilled far enough away from any seams, splices or overlays in the chassis frame to ensure bolted and nut/washer connection will be flat, ensure total contact with chassis frame.



The assembly of bolt and nut through the chassis frame must adhere to certain guidelines. In the event that the hole is situated on a curved surface or where a transition occurs in the frame, it is not recommended to utilize it as a mounting location.

However, if the hole location is to be utilized as a mounting location, the following protocol must be observed: A levelling washer must be employed to ensure that the bolt clamping force is fully applied and perpendicular to the frame, with no gaps permitted.

The helt/put

The bolt/nut assembly, located on the seam, is deemed unacceptable.

Lighting and Electrical Standards

10.110	Conformance: • LED Lighting – Class 2		
	• CED Lighting – Class 2 • C.M.V.S.S.	-	
	 Manitoba Highway Traffic Act. 		
	City of Winnipeg Lighting Visibility Standard		
	http://winnipeg.ca/matmgt/pdfs/PublicWorksEquipLighting	Visibility.pdf	
10.111	Lighting:		
	Supplier installed	-	
	• LED – Class 2		
	Stop / turn / tail lightsClearance lights		
	Back-up lights		
	3-Light cluster		
10.112	Visibility:		
	 Taillights, back-up lights and warning lights to be fully vision 		
	lowered to horizontal positionNo clearance light shall protrude beyond the service bo		
		-)	
10.113	Licence plates:		
	 The front license plate holder is securely installed and comes with the necessary mounting screws for the license plate. 		
	 The back-license plate holder is securely installed and it 	nust have an LED	
	light to illuminate it and should be positioned on the left		
10 111	the vehicle, ensuring it is not obstructed.		
10.114	 License Plate Light (Rear Location) Complete with license plate bracket 		
	 P/N Truck-Lite 36140 (Light) 		
	P/N Truck-Lite 36710 (Bracket)		
10.115	Identification:		
10.115	 All dash mounted warning lights and switches to be idea 	ntified with	
	permanent, engraved type labels		
	Mounting of labels with 3M VHB Tape or equivalent. To ensure adhesion to		
	interior surfaces 3M Adhesion Promoter 06396 is a convenient liquid primer for enhancing the adhesion of 3M™ Acrylic Foam Tapes in automotive		
	applications. This adhesion promoter works with most LSE plastics used for		
	interior and exterior automotive trim and parts		
	 No labels to be located on upper surface of dash 		
		ble form of	
	permanently engraved labeled switches.		





Not Acceptable – Not Permanently Label Picture above shows example of permanent engraved label switches.

10.116 LED Strobe Lights:

- Shall be wired "Hot" (I.e. able to be used without the key on)
- All LED strobe lights shall be wired through the ignition, wired through a single OEM dash mounted switch or on the control panel enclosure, labelled "Strobes" with a permanent type, engraved style label
- 10.117 Connection System:
 - Weather Pack Sealed Connection System or equivalent system having same industry specifications.
 - Genuine OEM connectors, terminals, and wire seals are used to guarantee quality and 100% fitment.
 - ("J-Box" and shrink tube acceptable)



- 10.118 Grommets:
 - Rubber grommets should be employed for the purpose of passing or running wiring through apertures in the panels' chassis, unless explicitly specified otherwise.



- 10.119 Harnesses:
 - Harness system, properly routed and secured.
 - All harnesses shall be internally grounded, no exceptions
 - Colour coded or numbered
- 10.120 Junction box:
 - Complete with necessary compression fittings, required for all vehicle lighting harness connections
 - Securely located inside rear of truck frame
 - Waterproof
 - Readily accessible for servicing
 - Protected from road spray
- 10.121 All Plug-In Connectors:
 - All plug-in connectors shall be coated with Truck-Lite NYK Corrosion Preventive Compound prior to assembly
- 10.122 Compartment Lights:
 - LED continuous "rope" style lighting in all service body compartments, properly secured to prevent damage

10.123 Wiring:

- All wiring to be colour coded, loomed and properly secured.
- Genuine OEM connectors, terminals, and wire seals are used to guarantee quality and 100% fitment
- All LED strobe lights shall be wired through the ignition, wired through a single OEM dash mounted switch or on the control panel enclosure, labelled "Strobes" with a permanent type, engraved style label

10.124 Electrical Connectors:

• All electrical connectors to be crimped, soldered and then sealed using adhesive-sealant-lined shrink tubing must be used to guarantee joint integrity, waterproofing and strain relief or rubber fittings



- Pictures above showing acceptable crimping and sealant using adhesivesealant-lined shrink tubing must be used to guarantee joint integrity, waterproofing
- 10.125 Joining of Wires:
 - All joining of wires to be soldered and adhesive-sealant-lined shrink tubing must be used to guarantee joint integrity, waterproofing and strain relief

Note: Crimp on electrical connectors for joining wires are not acceptable

- 10.126 Wiring Routing:
 - Any holes required to run wires through shall be drilled and deburred (not punched), grommeted and sealed

^{11.0} **WARRANTY**:

11.1 All warranty information shall be detailed and *include all exclusions*.

The Contractor shall provide all published warranty information upon delivery of the equipment.

Bidder shall state all warranty information.

11.2 The warranty for the **Flat Deck Service Body and all accompany components** shall cover the complete equipment, and all parts thereof against any defects of workmanship, construction and materials.

Any equipment that has become defective during said warranty period and has not proven to have been caused by negligence on the part of the user shall be repaired or replaced at no cost to the City.

The warranty shall be effective from the date the equipment is put into service by the City of Winnipeg

11.3	Factory Warranty – Flat Deck Body	State: Terms:	
11.4	Invertor	State: Terms:	
11.5	Compressor	State: Terms:	
11.6	Slip Tanks	State: Terms:	
11.7	Electrical	State: Terms:	
11.8	Battery	State: Terms:	
11.9	Paint	State: Terms:	

12.0 **DELIVERY:**

12.1 Delivery Point:

The complete unit shall be serviced, ready for operation and delivered F.O.B. with the freight prepaid, including invoice and N.V.I.S. (if applicable) to the WFMA 185 Tecumseh Street, Winnipeg MB.

12.2 **Delivery Time:**

Equipment shall be delivered between 8:00 am and 2:00 pm on Business Days.

State: earliest delivery time from date of award:

12.3 Delivery Contact:

The Contractor shall contact the Contract Administrator prior to delivery of the equipment.

12.4 **P.D.I**:

A pre-delivery inspection shall be performed by the Contractor on the equipment. Proof upon inspection including completed check list

13.0 **MANUALS**:

13.1 <u>Manuals:</u>

The following manuals shall be supplied with the equipment when delivered:

Operator – Two (2) Copies

- One (1) copy shall be sent to the Equipment Operator Training Branch
- One (1) copy to be left with the equipment

Parts and Service

• One (1) complete set including preventative maintenance schedules

Note: CD or USB flash drive is preferred where available.

14.0 **PARTS/LABOUR PRICING:**

- 14.1 Bidder to provide City of Winnipeg Parts Discount % Pricing from retail parts pricing. **State percentage discount**
- 14.2 Bidder to provide City of Winnipeg Labor Discount % Pricing from Retail shop labor rate. **State percentage discount**

15.0 FIRST SERVICE PREVENTATIVE MAINTENANCE KIT:

- 15.1 If applicable, in order to assure minimum downtime of the Equipment in future service, the Contractor must provide one (1) complete replacement set of new OEM filters for each unit purchased. The set of required filters shall include (if applicable to the equipment type) air, fuel, oil, transmission, cab and hydraulic, or otherwise all known necessary common replacement filters required for the first preventative maintenance servicing and first transmission service.
- 15.2 The Contractor must provide a list of factory recommended lubricants to be used with the equipment, as well as a complete cross reference guide for all warranty approved lubricants and filters that can be used during Preventative Maintenance servicing.