


**1 SITE PLAN**  
L1 SCALE - 1 : 200



LEGEND	
	NEW ASPHALT PATH OVER THE EXISTING GRAVEL PATH PER 1/L4 AND SCD-646, 250 m2
	ASPHALT PAVING PER SCD-646, 216 m2
	APPROX EXTENT OF NEW SOD PER CW 3510 & CW 3540, APPROX 672 m2
	MIN 300mm DEEP SAFETY SURFACE (ENGINEERED WOOD FIBER) C/W DRAINAGE SYSTEM PER 2/L4 AND MANUFACTURER SPECIFICATION AND SCD-661, 298 m2
	CONCRETE CURB PER 3/L4 AND SCD-643, 55.0m
	PLAYGROUND ROLLED ASPHALT ACCESSIBLE ENTRANCE PER 4/L4
	SUBSURFACE DRAINAGE COLLECTOR PIPES PER SCD-650 AND SCD-661
	HDPE OUTLET PIPE TIE IN TO EX CB PER SCD-665
	EXISTING PVS LDS LINE
	EXISTING CATCH BASIN
	(10) TACHE BENCH PER SCD-121A
	(1) TACHE ACCESSIBLE PICNIC TABLE PER SCD-122A
	(1) TACHE PICNIC TABLE PER SCD-122
	(1) WASTE RECEPTACLE PER NOTE # 9
	FUTURE TREES, N.I.C.
	EXISTING TREES TO REMAIN AND BE PROTECTED PER 7/L4

**GENERAL NOTES**

- ALL EXISTING STRUCTURES, TREES, SHRUBS, SIDEWALKS, CURBS, SOD, UTILITIES AND PAVING TO BE PROTECTED (UNLESS OTHERWISE NOTED) DURING CONSTRUCTION TO CITY OF WINNIPEG STANDARDS. CONTRACTOR TO MAKE GOOD ALL DAMAGED AREA DURING CONSTRUCTION BOTH ON AND OFF SITE TO CITY OF WINNIPEG STANDARDS AT THE CONTRACTORS COSTS.
- CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.
- CONTRACTOR TO CONFIRM ALL EXISTING GRADES, LAYOUT, DIMENSIONS AND MATERIALS ON SITE AND REPORT ANY DISCREPANCIES TO THE CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION.
- ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH THE MOST RECENT VERSIONS OF CITY OF WINNIPEG SPECIFICATIONS. ALSO REFER TO L4 FOR ADDITIONAL DETAILS AND SPECIFICATIONS.

- ALL LAYOUT TO BE CONFIRM ON SITE AND APPROVED BY CONTRACT ADMINISTRATOR PRIOR TO ANY CONSTRUCTION OR REMOVAL.
- SUB-GRADE, SUB BASE & BASE COURSE CONSTRUCTION AS PER CW 3110
- GEOTEXTILE FABRIC AS PER CW 3130
- TOPSOIL & SOD AS PER CW 3540 AND CW 3510
- WASTE RECEPTACLE TO BE 6" IN-GROUND ALFA MAXI 30, SANDSTONE COLOUR CONTAINER, GREEN COLOURED LID, .915 MM (36") DIAMETER X 2440 MM (96") HEIGHT, WITH STANDARD MAXI LID. FOR INFORMATION CONTACT: EQUINOX INDUSTRIES TEL: 1-800-665-7487

REV	YY / MM / DD	DESCRIPTION	BY
g	2024-04-10	ISSUED FOR CONSTRUCTION	NH
f	2024-02-13	RE-ISSUED FOR 100% REVIEW	NH
e	2024-01-08	ISSUED FOR 100% REVIEW	NH
d	2023-08-04	ISSUED FOR 90% REVIEW	NH
c	2023-05-05	ISSUED FOR 66% REVIEW	NH
b	2023-02-27	ISSUED FOR 33% REVIEW	NH
a	2021-04-27	ISSUED FOR REVIEW	NH

A. SECTION LETTER OR DETAIL NUMBER.  
B. DRAWING WHERE SECTION OR DETAIL IS DRAWN.  
OR  
DRAWING WHERE SECTION OR DETAIL IS INDICATED.  
--- SECTION OR DETAIL SHOWN ON SAME DRAWING.

CLIENT

**SCATLIFF + MILLER + MURRAY**  
visionary urban design + landscapes

PROJECT <b>AMBER GATES PLAYGROUND AND SEATING</b>			
TITLE <b>SITE PLAN</b>			
DESIGN	DRAWN	DATE - Y / M / D	SCALE
NH	NH	2023/02/27 (REV)	1:200
CHECKED	APPROVED	PROJECT NO.	DRAWING NO.
AJ	BS	18-3167-003	L1