



| EXISTING     | LEGEND - PLAN    | PROPOSED      |
|--------------|------------------|---------------|
| 150 WM       | WATERMAIN        | <u>150 WM</u> |
| <del>-</del> | HYDRANT          | +             |
| $\otimes$    | VALVE            | $\otimes$     |
| 250_CS       | COMBINED SEWER   | 250_CS        |
| 0            | MAINTENANCE HOLE |               |
|              | CATCH BASIN      |               |
| $\Box$       | CURB INLET       | ▼             |
|              | POWER            |               |
|              | SIDEWALK         |               |



Certificate of Authorization Stantec Consulting Ltd.

No. 1301

## **WARNING**

IF POWER EQUIPMENT OR EXPLOSIVES ARE TO BE USED FOR EXCAVATION ON THIS PROJECT THE CONTRACTOR MUST:

1) NOTIFY THE GAS COMPANY OF THE PROPOSED LOCATION OF EXCAVATION.

2) TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY INSTALLATIONS.

SEE PROVINCIAL REGULATION 140/92 FOR DETAILS

## **METRIC**

WHOLE NUMBERS INDICATE MILLIMETRES DECIMALIZED NUMBERS INDICATE METRES

2024-02-28 111220782



Stantec Consulting Ltd. Suite 500, 311 Portage Avenue Winnipeg MB Canada R3B 2B9 Tel. 204.489.5900 Fax. 204.453.9012 www.stantec.com

## Notes

- 1. CONTRACTOR TO VERIFY LOCATION, INVERTS AND TYPE OF ALL EXISTING BURIED UTILITIES PRIOR TO CONSTRUCTION AND NOTIFY ENGINEER OF ANY DISCREPANCIES.
- 2. ALL MATERIALS AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATION.
- ALL WATER SERVICES TO HAVE A MINIMUM OF 2.5m COVER AND TO BE INSTALLED USING TRENCHLESS METHODS WHERE POSSIBLE.
- 4. ALL TRENCH BACKFILL FOR WATER, SEWER AND PVC CONDUIT INSTALLATIONS SHALL BE CLASS B SAND BEDDING WITH CLASS 2 BACKFILL WHEN WITHIN 1.0m OR UNDER NEW OR PROPOSED PAVEMENT AREAS AND CLASS 4 BACKFILL IN LANDSCAPED AREAS.

Client/Project

CITY OF WINNIPEG - PARKS DEPARTMENT GIIZHIGOOWEYAABIWE PARK PARK REDEVELOPMENT

Figure No.

C-101

DRINKING FOUNTAIN/BOTTLE FILL STATION 242 LIZZIE STREET - WINNIPEG MB