DRAWING INDEX

SHEET NUMBER	CITY OF WINNIPEG DRAWING NUMBER	DRAWING TITLE
1	D–16868	COVER PAGE
2	D–16869	DRAWING INDEX, DESIGN NOTES, LEGEND, & ABBREVIATIONS
3	D–16870	GORDON AVENUE – BRAZIER STREET TO 100M E OF BRAZIER STREET
4	D–16871	GORDON AVENUE – 100M E OF BRAZIER STREET TO 175M E OF BRAZIER STREET
5	D–16872	GORDON AVENUE – 175M E OF BRAZIER STREET TO 275M E OF BRAZIER STREET
6	D–16873	GORDON AVENUE – 275M E OF BRAZIER STREET TO STADACONA STREET
7	D–16874	KILDONAN DRIVE – HENDERSON HIGHWAY TO KILDONAN DRIVE SOUTH
8	D–16875	KILDONAN DRIVE – KILDONAN DRIVE SOUTH TO CANTERBURY PLACE
9	D–16876	KINGSFORD AVENUE – DeFEHR STREET TO 100M E OF DeFEHR STREET
10	D–16877	KINGSFORD AVENUE – 100M E OF DeFEHR STREET TO 195M E OF DeFEHR STREET
11	D–16878	KINGSFORD AVENUE – 195M E OF DeFEHR STREET TO 295M E OF DeFEHR STREET
12	D–16879	KINGSFORD AVENUE – 295M E OF DeFEHR STREET TO 400M E OF DeFEHR STREET
13	D–16880	KINGSFORD AVENUE – 400M E OF DeFEHR STREET TO 500M E OF DeFEHR STREET

ABBREVIATIONS

WWS	WASTE WATER SEWER
CS	COMBINED SEWER
LDS	LAND DRAINAGE SEWER
℄	PROPERTY LINE
℄	CENTER LINE
G.I.S.	GEOGRAPHIC INFORMATION SYSTEM
B.M.	BENCH MARK
TH	TEST HOLE
ELEV	ELEVATION
INV	INVERT
MIN	MINIMUM
MAX	MAXIMUM
SL	STREET LIGHTING
TS	TRAFFIC SIGNALS
ABAND	ABANDONED
BLDG	BUILDING
HSE	HOUSE
CRN	CORNER
OPP	OPPOSITE
C/S OR S/C	CURB STOP
MTS	MANITOBA TELEPHONE SYSTEM
R.O.W.	RIGHT–OF–WAY
WM	WATERMAIN
CULV	CULVERT
MH	MANHOLE
CB	CATCH BASIN
CI	CURB INLET
VERT.	VERTICAL
HORZ.	HORIZONTAL
I.B.	IRON BAR
FIBRE	FIBRE OPTIC
TYP	TYPICAL
X–ING	CROSSING
HYD	HYDRANT
EXIST	EXISTING
N	NORTH
E	EAST
S	SOUTH
W	WEST
W/	WITH
C/W	CONSTRUCTED WITH
CONC	CONCRETE
AC	ASBESTOS CEMENT
VC OR CLAY	VITRIFIED CLAY
CI	CAST IRON
DI	DUCTILE IRON
PVC	POLYVINYL CHLORIDE
HDPE	HIGH DENSITY POLYETHYLENE
PCCP	PRESTRESSED CONCRETE CYLINDER PIPE

LEGEND

PLAN VIEW

DESCRIPTION	ABANDONED	EXISTING	PROPOSED
WATER PIPE			
FIRE HYDRANT			
VALVE			
CURB STOP			
REDUCER			
COUPLING OR SLIDDER			
CROSS			
BEND – 11.25°, 22.5°, 45°, 90°			
TEE			
VERTICAL BEND			
ANODE			
REPAIR MARKER			
PLUG			
SEWER PIPE			
MANHOLE			
CATCH BASIN			
CURB INLET			
JUNCTION			
℄ DITCH			
CULVERT			
SURVEY BAR			
SURVEY MONUMENT			
TREE – DECIDUOUS			
TREE – CONIFEROUS			
HYDRO			
HYDRO POLE			
LAMP STANDARD			
HYDRO POLE W/STREET LIGHTING			
POLE			
GUY ANCHOR			
M.T.S. POLE			
PEDESTAL OR BOX			
CABINET			
M.T.S., SHAW, OR VIDEON			
TRAFFIC SIGNALS			
TRAFFIC LIGHT STANDARD			
GAS			
STEAM			
FIBRE OPTIC			
FENCE			
EDGE OF PAVEMENT OR GUTTER			
EDGE UNPAVED OR GRAVEL ROAD			
℄			
PROJECTED ℄			
LOT LINE			
SIDEWALK – PATHWAY			
EASEMENT			
EDGE OF BUILDING			
MAILBOX			
PARKING METER			
TEST HOLE			
TREE LINE OR BUSH			

PROFILE

DESCRIPTION	ABANDONED	EXISTING	PROPOSED
WATER PIPE			
HYDRANT TOP			
VALVE			
TEE OR CROSS			
COUPLING OR BEND			
REDUCER			
END OF PIPE			
SEWER PIPE			
UNPAVED GROUND SURFACE			
PAVED GROUND SURFACE – ℄ PIPE			
GUTTER (NORTH AND WEST)			
GUTTER (SOUTH AND EAST)			
℄ DITCH (NORTH AND WEST)			
℄ DITCH (SOUTH AND EAST)			
STRUCTURE			
MANHOLE OR CATCH BASIN			

HATCH PATTERNS

EXISTING	PROPOSED	DESCRIPTION
		EARTH OR GROUND ABOVE PIPE
		SAND OR OTHER FINE MATERIAL
		CONCRETE
		WASHED STONE OR GRANULAR MATERIAL
		INTERLOCKING STONE
		METAL
		GRAVEL OR STONE

CONSTRUCTION NOTES

1. EXPOSE EXISTING WATERMAIN & CONFIRM INVERTS PRIOR TO CONSTRUCTION.
2. LOCATION OF ALL SERVICES TO BE CONFIRMED IN THE FIELD.
3. INSTALL WATERMAIN BY TRENCHLESS METHODS.
4. TRENCHES AND EXCAVATIONS WITHIN 1 METRE OF A PAVED AREA INCLUDING SIDEWALKS SHALL BE CLASS 3 BACKFILL.
5. ALL MATERIALS SHALL CONFORM TO THE CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS.
6. MINIMUM COVER TO TOP OF WATERMAIN SHALL BE 2.4 m.
7. REPLACE ALL EXISTING LEAD SERVICES FROM PROPOSED WATERMAIN TO ℄.
8. NOTIFY ALL AFFECTED RESIDENTS AND BUSINESSES 24 HOURS IN ADVANCE OF ANY WATER SHUTDOWNS OR DISRUPTION OF SERVICE.

LOCATION APPROVED
UNDERGROUND STRUCTURES

SUPV. U/G STRUCTURES COMMITTEE _____ DATE _____

NOTE:

LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

B.M.
ELEV.

NO.	REVISIONS	DATE	BY

DESIGNED BY	JB	CHECKED BY	SC
DRAWN BY	AOM	APPROVED BY	SC
SCALE: HORIZONTAL	1:250	RELEASED FOR CONSTRUCTION	
VERTICAL	1:50		
DATE	2024 04 09	DATE	Digitally signed by Stacy Cournoyer, P. Eng. 2024-04-24

PLOT DATE: 2024 04 09

ENGINEER'S SEAL
PROVINCE OF MANITOBA
S.R.J. COURNOYER
Member 22699
2024-04-24
REGISTERED PROFESSIONAL ENGINEER
Digitally signed by Stacy Cournoyer, P. Eng.

CONSULTANT DRAWING NUMBER
–

BID OPPORTUNITY: 70–2024
CONTRACT NUMBER: 5

Winnipeg

THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT
ENGINEERING DIVISION

2024 WATER MAIN RENEWALS
CONTRACT #5

INDEX PAGE

SHEET 2 OF 13
CITY DRAWING NUMBER
D–16869

FILE PATH: R:\DRAWINGS\WATER\RENEWAL\2024 RENEWALS\Cont 5\Construction Dwgs\
FILE NAME: INDEX – CONTRACT 5.dwg