



ADDENDUM 2 BID OPPORTUNITY NO. 74-2005

NEWPCC SECONDARY EFFLUENT UV DISINFECTION FACILITY

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: March 22, 2005
BY: T Roziere
TELEPHONE NO. (204) 986-4623

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20050301

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 9 of Form A: Bid may render your Bid non-responsive.

PART B – BIDDING PROCEDURES

B2 Submission Deadline Revise B2.1 to read:

B2.1 The Submission Deadline is 12:00 noon Winnipeg time, March 30, 2005

PART E – SPECIFICATIONS

E1.2 The following Drawings are affected by this Addendum. Detailed descriptions of the changes are included subsequently in this document under the heading "DRAWINGS"

<u>Drawing No.</u>	<u>Drawing</u>	<u>Description of Change</u>
66303D-CA1.01	Architectural – Landscape Plan	Clarification
CA1.01-SK1	Typical Planting Detail	Supplemental Information re: Dwg CA1.01 Rev 0
66303D-CP1.01	Process – Standard Details	Clarification

Section 01500 Clause 2.1 Clarification:

The City will supply the water used for construction purposes including the initial water used for the watertightness testing. Water used for retesting shall be supplied at the Contractor's expense at the City standard rates. The Contractor shall be responsible for conveying the water (hook-ups, pipes, maintenance, etc.) to the construction site from the City source.

Section 03300 Clause 3.15 Clarification:

The City will supply the water used for construction purposes including the initial water used for the watertightness testing. Water used for retesting shall be supplied at the Contractor's expense at the City standard rates. The Contractor shall be responsible for conveying the water (hook-ups, pipes, maintenance, etc.) to the construction site from the City source.

Section 04200 Clause 2.2.2.1 Revise to Read:

.1 Metric Modular Face Brick, 90 x 57 x 190

DRAWINGS

Drawing 66303D-CA1.01 Rev 0 Clarification

This Drawing shows five unreferenced plants (symbol: circle divided into 8 segments) in the planting cluster to the south-east of the UV Building. These shall be labelled "Goldflame Spires: 30 inch diameter"

Drawing CA1.01-SK1 Rev 0 Add

Refer to this sketch "Typical Planting Detail" in conjunction with Drawing 663030D-CA1.01

Drawing CP1.01 Rev 0 Clarification

Standard Detail STD 620: Weir plates shall be of sufficient length to fully span the width of UV reactor channels