

Air Handling Unit Schedule											
Tag	Service	Make	Model	Airflow (LPS)	ESP (Pa)	Gas Heating (kW)		Motor (kW)	Unit MCA	Voltage	Comments
						Input	Output				
AH-4	Gym / Weights	ICE	HTDM-200, DX-10	1,230	250	118	94	3	19	575 / 3	Integral condensing unit
AH-6	Club Rooms	McQuay	CAH006GDAC	1,275	250	-	-	5	-	575 / 3	Vertical stacked configuration
AH-7	Spectators	McQuay	CAH006GDAC	1,420	250	-	-	5	-	575 / 3	Vertical stacked configuration
AH-8	Main Floor	McQuay	CAH003GDAC	710	250	-	-	3	-	575 / 3	Vertical stacked configuration
AH-9	Bowling Area	ICE	HTDM-400, DX-6	1,510	250	147	118	3	16	575 / 3	Integral condensing unit
AH-10	Library	Aaon	RM-010-4-0-AA02-339	2,600	188	53	43	5	24	575 / 3	Supply with factory roof curb
AH-11	Main Lobby	Aaon	RM-A16-4-0-AA02-349	3,400	188	79	64	5	29	575 / 3	Supply with factory roof curb
AH-12	Running Track	Aaon	RM-010-4-0-AA02-339	12,000	188	159	127	15	109	575 / 3	Supply with factory roof curb