



**KILDARE LAND DRAINAGE FLOOD PUMPING STATION
MECHANICAL AND ELECTRICAL WORKS**

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: September 7, 2007
BY: Rudy Derksen, P.Eng.
TELEPHONE NO. (204) 896-1209

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20060821

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART D – SUPPLEMENTARY CONDITIONS

Delete: Clause D18.1 (a) shall be deleted.

“(a) Deliver pump discharge pipes; One thousand dollars (\$1,000.00);”

PART E – SPECIFICATIONS

Add: Section 15100, Item 2.1.6

"To anchor the 3.0m long sleeves/pump discharge pipes to the concrete, provide 6 horizontal rows of 13mm (1/2") diameter by 100mm long 304 stainless steel "Nelson" studs or equal, welded equally spaced around the circumference of the sleeve/pump discharge pipes. Each row at 500mm spacing shall have 8 studs for a total of 48. Variations of this anchoring design that are equal in quality will be considered."