

ADDENDUM NO. 1 BID OPPORTUNITY NO. 74-2007

**2007 WATERMAIN RENEWALS - CONTRACT 1, LOGAN AVENUE FROM
BLAKE STREET TO ELECTA STREET**

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: February 23, 2007
BY: Stacy Cournoyer, P. Eng.
TELEPHONE NO. (204) 986-2142

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: 20040128

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid Submission non-responsive.

PART A – BID SUBMISSION

Replace 74-2007_Bid_Submission with 74-2007_Addendum_1-Bid_Submission.

PART D – SUPPLEMENTAL CONDITIONS

Revise D15.1 (c) to read: Commence work for Phase 2 specified in D14.1(b) starting at limit of work at Quelch Street and work east to limit of work at 1343 Logan Avenue.

PART E – SPECIFICATIONS

Revise E3 to read:

E3. TEMPORARY SURFACE RESTORATIONS

E3.1 Further to clause 3.3 of CW 1130, excavations within the pavement and sidewalk on Logan Avenue at the intersections of Blake Street, Cecil Street, Quelch Street and Vine Street shall be left in a temporarily restored condition as follows:

E3.1.1 Temporarily restore disturbed surfaces as follows:

- (a) Asphalt and concrete pavements: minimum 50 millimetre thick layer of Type II Asphaltic concrete pavement as specified in CW 3410.
- (b) Sidewalks: minimum 50 millimetre thick layer of cold mix asphalt or cement-stabilized fill.

E3.1.2 Maintain temporary surface restoration until permanent surface restoration is completed or Contractor for Bid Opportunity 151-2007 takes control of site.

E3.1.3 If temporarily restored surfaces are not maintained within 24 hours of being notified to do so by the Contract Administrator, the work may be directed to be done by City forces and the cost deducted from future payments to the Contractor.

E3.2 Excavations within pavement and sidewalk on Logan Avenue from Blake Street to the west side of the CPR tracks and excluding intersections stated in E3.1 shall not be restored. Backfill excavations to match existing grade.

- E3.3 Excavations within pavements and sidewalks on the east side of the CPR tracks to the Electa Street shall be permanently restored in accordance with CW 2110.
- E3.4 Measurement and Payment
 - E3.4.1 Costs for temporary surface restoration and maintenance will be included with the watermain installation.
 - E3.4.2 Cost of removal of pavement and sidewalk from Blake Street to CPR tracks will be included with the watermain installation.