



P.D. DRAWER 330 - DUNKIRK, MD 20754 USA TOLL FREE: (800) 368-2573 (USA & CANADA) TEL (301) 855-8300 - FAX (410) 257-7579 WEB SITE: HTTP://WWW.YICTORSTANLEY.COM









AVAILABLE OPTIONS:

POWDER COATING

10 STANDARD COLORS, CUSTOM COLORS (INCLUDING THE RAL RANGE)

SLAT TYPES

WOODS: PHILIPPINE MAHDGANY AND IPE

2nd SITE SYSTEMS (R) RENFORCED RECYCLED PLASTIC SLATS

COLORS: GRAY, MAPLE, CHERRY, AND WALNUT

(NOT AVAILABE 8-FOOT LENGTHS)

LENGTHS

STANDARD 4'

STANDARD 6' LENGTH SHOWN

STANDARD 8'

## NOTES:

- 1. DUCTILE IRON CASTINGS COME WITH A TEN YEAR WARRANTY AGAINST BREAKAGE.
- 2. DRAWING NOT TO SCALE. DO NOT SCALE DRAWINGS.
- 3. ALL FABRICATED METAL COMPONENTS ARE STEEL SHOTBLASTED, ETCHED, PHOSPHATIZED, PREHEATED, AND ELECTROSTATICALLY POWDER-COATED WITH T.G.I.C. POLYESTER POWDER COATINGS. PRODUCTS ARE FULLY CLEANED AND PRETREATED, PREHEATED AND COATED WHILE HOT TO FILL CREVICES AND BUILD COATING FILM. COATED PARTS ARE THEN FULLY CURED TO COATING MANUFACTURER'S SPECIFICATIONS. THE THICKNESS OF THE RESULTING FINISH AVERAGES 8-10 MILS (200-250 MICRONS).
- 4. IT IS NOT RECOMMENDED TO LOCATE ANCHOR BOLTS UNTIL BENCH IS IN PLACE. THIS VICTOR STANLEY, INC. PRODUCT MUST BE PERMANENTLY AFFIXED TO THE GROUND. CONSULT YOUR LOCAL CODES FOR REGULATIONS.
- 5. ANCHOR BOLTS NOT PROVIDED BY VICTOR STANLEY, INC.
- 6. FOR HIGH SALT ABUSIVE CLIMATES, HOT DIP GALVANIZING BEFORE POWDER COLATING IS AVAILABLE. SEE WRITTEN SPECIFICATIONS FOR DETAILS.
- 7. ALL SPECIFICATIONS ARE SUBJECT TO CHANGE. CONTACT MANUFACTURER FOR DETAILS.
- 8. THIS PRODUCT IS SHIPPED PARTIALLY UNASSEMBLED.



STANDARD BACKLESS BENCH WITH DUCTILE IRDN END FRAMES

SHOWN: STANDARD 6-FOOT LENGTH

COPYRIGHT 2007 VICTOR STANLEY, INC. ALL RIGHTS RESERVED