



# 277-2009 ADDENDUM 1

## BAYVIEW AND HATCHER PARK SITE WORKS

### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY**

ISSUED: May 20, 2009  
BY: Aaron Hirota  
TELEPHONE NO. (204) 956-0396

**THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS**

Template Version: A20070419

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.**

---

### **PART A – BID SUBMISSION**

Replace: 277-2009 Bid Submission with 277-2009 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): Replace entire form.

### **PART E – SPECIFICATIONS**

Revise: E2.2 to read: All trees will have a tree protective zone (TPZ) at the dripline of the crown, which will remain free of digging, trenching, grade changes, stock piling of materials and soil compaction, throughout the duration of the Contract. Protective snow fencing around these areas is required. The TPZ shall be considered to be the ground surface directly beneath the tips of its outermost branches.

Revise: E2.4 to read: Excavation shall be performed in a manner that minimizes damage to the existing root systems. Where possible, excavation shall be carried out such that the edge of the excavation shall be a minimum of 3m from the closest edge of the trunk. Where roots must be cut to facilitate excavation, they shall be pruned neatly at the face of excavation by an arborist licensed to practice in the Province of Manitoba. They must be properly trimmed with sharp tools to prevent crushing or being pulled up by construction equipment. No paint is required. All exposed roots must be mulched until the excavated area is filled with clean earth to avoid exposure to sunlight and desiccation.

Revise: E2.5 to read: No operation of equipment will occur within the TPZ unless authorized by the City Forester or designate. Equipment shall not be parked, repaired, refuelled; construction materials shall not be stored, and earth materials shall not be stockpiled within the TPZ. The Contractor shall ensure that the operations do not cause flooding or sediment deposition on areas where trees are located.

Revise: E2.9 to read: Auguring under existing trees will be the only acceptable method of underground installations. Any other excavations must be approved by the Urban Forestry Branch.

Delete: E19.2.1 (a)

Delete: E19.4.2

Delete: E19.4.3

Delete: E19.4.6

Add: E19.4.9                    Any Site damage caused by materials stockpiled on site shall be repaired by the Contractor at their own cost to the satisfaction of the Contract Administrator.

Delete: E19.5.1

Delete: E19.6.1

Delete: E19.6.2

Revise: E20.16 to read:        The Contractor is advised that all excavations, removals, disposal, rough grading, compaction and related Work for construction of concrete sidewalk, crushed limestone pathway, and planting areas shall be incidental to the unit prices bid for each item as listed in the schedule of prices.

Delete: E26

Delete: E28.21

Delete: E28.32 (g)

Delete: E28.33

Delete: E28.37 (b)

Revise: E29.4.2 to read:        Spraying Deciduous Trees

Revise: E29.4.2 (a) to read:    Because of the specialized nature of such operations, this should be done by a qualified licensed local arborist.

Delete: E29.4.2 (b)

Delete: E29.4.6 (a)(vii)

## **DRAWINGS**

Replace: 277-2009 \_Drawing\_L1.2 with 277-2009 \_Addendum\_1 Drawing L1.2