



335-2009 ADDENDUM 1

DESIGN AND CONSTRUCTION – REPLACEMENT OF INDOOR HOCKEY RINK BOARD SYSTEM AT TERRY SAWCHUK MEMORIAL ARENA

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE REQUEST FOR PROPOSAL

ISSUED: May 15, 2009
BY: Coleen Groening
TELEPHONE NO. (204) 986-2491

THIS ADDENDUM SHALL BE INCORPORATED INTO THE REQUEST FOR PROPOSAL AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: Ar20070420

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Request for Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Proposal may render your Proposal non-responsive.

PART E – SPECIFICATIONS

- Revise:** E3.4.1 (e) to read: The access gates (3'-0" wide standard) and player gates (2'-6" wide) shall be left or right swing. The gate panel framing shall be the same construction as standard panels.
- Revise:** E3.4.1 (t) to read: The existing concrete substrate floor surfaces in the player, penalty and timekeeper's boxes shall be covered with 100% solid recycled rubber flooring, ½" thick, smooth face style, 4 foot lengths and black in colour. Rubber flooring shall be vulcanized, non-absorbent, slip resistant and easily cleaned. Construction of elevated flooring will not be required.
- Add:** E3.4.1 (x) to read: **Raised Coaches Walkway:** In the players area an optional two-tier framework can be fabricated for a coach's walkway behind the benches. The coach's walkway will be elevated 7" above standard floor height and will be 18" deep.