



577-2009 ADDENDUM 5

SOUTHWEST RAPID TRANSIT CORRIDOR - STAGE 1: TRANSITWAY TUNNEL AT CN RIVERS SUBDIVISION MILEAGE 1.38 & ASSOCIATED WORKS

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: November 10, 2009
BY: Dave Krahn, P.Eng.
TELEPHONE NO. (204) 453-2301

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A2007/0419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART D – SUPPLEMENTAL CONDITIONS

- Revise: D16.4(a) to read: The commencement date shall start no earlier than July 2, 2010 and shall end no later than November 30, 2010.
- Revise: D16.6(a) to read: The commencement date shall start no earlier than August 1, 2011 and shall end no later than November 15, 2011.
- Revise: D20.1(a) to read: Critical Stage 1 Tunnel Works: The completion of Stage 1 Works sufficient, as described herein, for the commencement of Stage 2 - Track Detour by September 15, 2010. Refer to Section D16.4.
- Revise: D20.1(b) to read: Critical Stage 2 Tunnel Works: The completion of Stage 2 Works sufficient, as described herein, for the commencement of Stage 3 - CN Track Relocation by September 15, 2011. Refer to Section D16.6.
- Revise: D21.1 to read: The Contractor shall achieve Substantial Performance by September 15, 2011.
- Revise: D22.1 to read: The Contractor shall achieve Total Performance by September 30, 2011.

PART E – SPECIFICATIONS

- Revise: E6.3.2(a) to read: The Contractor shall be responsible to develop suitable Site access in accordance with this Section and Section E10 Encroachment on Private Property. This includes but is not limited to, temporary removal and reinstallation of chain link fencing, any landscaping and grading repairs, etc. necessary to restore any Site and construction access areas to their pre-existing condition.
- Add: E10.3 The Contractor will be permitted access by CN to the site from Nassau St. N.
 - (a) The Work to be done by the Contractor under this Section shall be in accordance with the Standard Construction Specification E6 Site Development and Restoration and CN Construction and Safety Requirements.
- Add: E10.4 Measurement and Payment
 - (a) The Access permitted by CN and associated Works will not be measured. No additional payment will be made for this item of Work.

- Add: E25.2.19(a)(viii) Bakor Blueskin WP200
- Add: E25.2.19(a)(ix) Bakor 790-11 Hot applied rubberized asphalt waterproofing membrane complete with appropriate primer and reinforcing.
- Revise: E25.2.19(b)(i) to read: Besides as specified in the Contract Drawings, approved products are Volclay Waterstop RX 101T by Engineered Site Products Ltd. and Vinylex Type BS9532 as supplied by Brock White.
- Add: E25.4.12(j) Surface preparation shall be in accordance with the manufacturer's directions. Manufacturer's directions will supersede those given above where they are different.
- Revise: E26.2.4(a) to read: Wall Drain shall be Miradrain 6000 by Mirafi, Nilex DN50, Aquadrain 15X, Bakor DB 6000 Drain Board, Soprema sopradrain eco-vent, or equal as accepted by the Contract Administrator. Mastic adhesive shall be as recommended by the wall drain manufacturer.

DRAWINGS

Replace:

- 577-2009_Drawing_U237-09-04A-R1 with 577-2009_Addendum_4_Drawing_U237-09-04A-R2
- 577-2009_Drawing_U237-09-22-R1 with 577-2009_Addendum_4_Drawing_U237-09-22-R2
- 577-2009_Drawing_U237-09-35-R1 with 577-2009_Addendum_4_Drawing_U237-09-35-R2
- 577-2009_Drawing_U237-09-69-R0 with 577-2009_Addendum_4_Drawing_U237-09-69-R1
- 577-2009_Drawing_U237-09-71-R0 with 577-2009_Addendum_4_Drawing_U237-09-71-R1