


NOTES:

11. PROVIDE ONE(1) SINGLE POLE TOGGLE SWITCH CONTROL FOR EACH TYPE 'MH04' LUMINAIRE WITHIN MAIN ELECTRICAL ROOM ADJACENT PANEL FEEDING SAME.
12. PROVIDE SEPARATE PRICE FOR THE FOLLOWING FOR FUTURE SIGNAGE AT CORNER OF CHURCH & ARLINGTON:
 - a) 15A/IP CIRCUIT BREAKER IN PANEL B.
 - b) POWER: 2 #3 RW90 IN 27mm PVC C. U/G TO W.P. JUNCTION BOX.
 - c) DATA: ONE (1) 27mm PVC C. U/G TO W.P. JUNCTION BOX C/W PULL WIRE.

CONFIRM LOCATIONS WITH CONTRACT ADMINISTRATOR. THIS ITEM SHALL BE INCLUDED IN SEPARATE PRICE #2.
13. DEMOLISH EXISTING LIGHTING STANDARD C/W ALL ASSOCIATED OVERHEAD WIRING BACK TO SOURCE. OVERHEAD WIRING REQUIRING RELOCATION DUE TO DEMOLISH STANDARD SHALL BE RE-FED C/W DIRECT BURIED MULTI-CONDUCTOR CABLE. COORDINATE REQUIREMENTS ON SITE.

DEMOLITION NOTES:

- D1. DISCONNECT AND REMOVE EXISTING 120/240V/1 ϕ /3W/200A PANELBOARD WITHIN SHED C/W EXTERIOR METER SOCKET C/W ASSOCIATED WIRING AND CONDUIT C/W SERVICE ENTRY MAST. EXISTING CIRCUITING SHALL BE MAINTAINED. PROVIDE NEW PANEL-D TO REPLACE SAME. PROVIDE NEW BREAKERS TO REPLACE EXISTING CIRCUITRY AS REQUIRED. CONFIRM REQUIREMENTS ON SITE PRIOR TO TENDER CLOSING.
- D2. DISCONNECT AND REMOVE EXISTING POLE MOUNTED LUMINAIRE, POLE AND OVERHEAD WIRING TO SOURCE. CIRCUIT FEEDING SAME SHALL BECOME SPARE. COORDINATE REMOVAL OF POLES WITH MANOTIBA HYDRO.

5878  MCW / AGE Consulting Professional Engineers 210-1821 Wellington Avenue Winnipeg, Manitoba, R3H 0G4 Phone - (204) 779-7900 Fax - (204) 779-1119 E-Mail: mcw_wpg@mcw.com	PROJECT:		SINCLAIR COMMUNITY CENTRE ADDITION & RENOVATIONS	REF. DWG. NO. E1.1
	DESCRIPTION:		SITE PLAN	DWG. NO. RE-2
	DATE: 2010-03-31	DRAWN BY: PCS	SCALE: N.T.S.	ISSUED WITH: ADD#01E