



### 333-2014 ADDENDUM 4

#### Contract 1 – Site Preparation Works – South End Water Pollution Control Centre (SEWPCC) Upgrading/Expansion Project

### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY**

ISSUED: July 31, 2014  
BY: Roy Houston, P.Eng.  
TELEPHONE NO. (204) 896-1209

**THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS**

Template Version: A20131129

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.**

### **PART A – BID SUBMISSION**

Replace: 333-2014 Addendum 3 - Bid Submission with 333-2014 Addendum 4 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

- Form B(R4): Added - Items A.3 ii), A.15. ii), and A.18 ii).
- Form B(R4): Revised Quantities - Items B.3, B.5 i), B.5 ii), B.6, B.8, B.9
- Form B(R4): Revised Quantities - Items C.1, C.2, C.3 i), C.4, C.5

Page numbering on some forms may be changed as a result.

### **PART E – SPECIFICATIONS**

Revise: NMS Division 01  
Section 01 11 00  
Clause 1.2. B.7.h  
to read:

Darco alarm panel for high and low level volume alert c/w tree kit and float switch in underground tank. Alarm panel to be installed in trailer at kitchen counter, location to be determined on site.

- Add: E.8.7: The Contractor shall provide maintenance of the shoring systems for the duration of the Contract and up to one month following completion of the Work within this Contract to facilitate transfer of the maintenance of shoring systems to the Contractor of a subsequent SEWPCC project contract.
- Add: E.8.8: Removal of shoring is excluded from the scope of the Work. Removal of shoring will be performed by others in a subsequent SEWPCC project contract.
- Add: E.8.9: Contractor shall coordinate shoring design with the Structural Designers to ensure that the location of shoring elements such as rakers do not adversely interfere with building construction in future contracts.

Add: E.9.10:

The Contractor shall be responsible for supplying and placing any granular working base deemed by the Contractor as necessary to facilitate access to their work required within the excavations. This includes any granular working base deemed necessary for the bottom of excavations or excavation ramps. The Contractor shall submit their plans for placement of granular base within the excavations with the Contract Administrator for approval prior to placement, in accordance with the submittal requirements of this Contract. The cost for any granular base for inside excavations or on excavation ramps shall be incidental to the cost of excavation work. No additional payment shall be made for granular material supplied and placed on excavation ramps or at bottom of excavations.