



255-2017 ADDENDUM 2

SUPPLY, DELIVERY, AND INITIAL START-UP INSPECTION OF PUMPING EQUIPMENT FOR COMMUNITY ROW WASTEWATER PUMPING STATION

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: April 06, 2017
BY: Brian Cleven, P. Eng.
TELEPHONE NO. (204) 786-8080

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART E – SPECIFICATIONS

- Add Clause D10.4.1: The Contractor shall provide fork lift(s), crane(s), and labour as required to off-load the goods at the delivery location. The City of Winnipeg does not have equipment or personnel at this location to assist with off loading of goods. A City of Winnipeg employee will direct the Contractor where to place the goods inside the building. The Contractor is fully responsible for any damage that may occur to the goods during shipment or off-loading at the delivery location.
- Revise Clause E5.3.3(b) to read: Provide a cast **or fabricated** 90° suction elbow with hand hole and cover plate fastened with bolts, to permit access to the suction side of the impeller for cleaning and inspection.
- Replace Clause E5.3.6 (e) to read: Cast impeller surface to be free from casting blemishes and finished to 250 RMS or better.
- Replace Clause E7.5 to read: Check valve to be rapid closure rubber flapper (RF) type with a 45° seating face suitable for vertical installation.
- Revise Clause E7.11 to read: The exterior and interior of the valve shall be coated with an **AWWA C-550** approved fusion bonded epoxy coating.