



**CONSTRUCTION NOTES**

- MILL EXISTING ASPHALT AND CONSTRUCT NEW ASPHALT OVERLAY (+/- 50mm)
- RENEW EXISTING CONCRETE LIP CURB AND GUTTER
- REMOVE EXISTING SIDEWALK AND CONSTRUCT NEW 100mm CONCRETE SIDEWALK (SD-228A)
- REMOVE EXISTING ASPHALT PAVEMENT AND RE-GRADE BASE COURSE MATERIAL AS REQUIRED
- REMOVE EXISTING LIP CURB AND GUTTER AND CONSTRUCT MODIFIED BARRIER CURB AND GUTTER (SD-200)
- CONSTRUCT NEW CURB RAMP (SD-229E)
- SUPPLY AND INSTALL NEW SIDEWALK BLOCKS
- INSTALL LIFTER RING AND MATCH TO GRADE (AP-010)
- INSTALL NEW MANHOLE FRAME AND SOLID COVER (AP-006, AP-007)
- INSTALL NEW MOUNTABLE CURB FRAME AND COVER (AP-015, AP-016)
- RE-GRADE EXISTING INTERLOCKING PAVING STONES
- REMOVE EXISTING CURB AND GUTTER
- INSTALL NEW 1200mm CATCH BASIN WITH FRAME (AP-006) AND GRATED COVER (AP-008) AND CONNECT TO EXISTING MAN-HOLE WITH 3.8m - 250mm PVC PIPE AS PER CW 2130

**GENERAL NOTES**

- PAVEMENT DIMENSIONS ARE TO BACK OF CURB
- ALL CURB RADII UNDER 15.0m SHALL BE MODIFIED
- CURB REPLACEMENT AS DIRECTED BY CONTRACT ADMINISTRATOR
- INSTALL DETECTABLE WARNING TILES AS DIRECTED BY CONTRACT ADMINISTRATOR (CW 3326)
- PAVEMENT REPAIRS SHOWN ARE ONLY A REPRESENTATIVE SAMPLE OF THE TENDERED QUANTITIES
- ASPHALT TIE-INS ON APPROACHES TO BE DETERMINED IN THE FIELD BY THE CONTRACT ADMINISTRATOR
- ADJUST WATER VALVES, HYDRANT ASSEMBLIES AND WATER SERVICE SHUT-OFF VALVES TO GRADE IF REQUIRED
- CONTRACTOR TO CONFIRM THE LOCATION OF ALL UTILITIES / SERVICES IN THE FIELD PRIOR TO CONSTRUCTION

FOR TENDER PURPOSES ONLY  
NOT FOR CONSTRUCTION

**METRIC**  
WHOLE NUMBERS INDICATE MILLIMETERS  
DECIMALIZED NUMBERS INDICATE METERS

TENDOR NO. 1-2023

EXISTING	LEGEND - PLAN	PROPOSED	EXISTING	LEGEND - PLAN	PROPOSED	EXISTING	LEGEND - PROFILE	PROPOSED
⊕	HYDRANT	⬆	---	LDS/WWS	---	☒	UTILITY BOX	---
⊗	VALVE	⬆	---	WATERMAIN	---	☒	CONCRETE	---
⊙	CURB STOP	●	---	GAS	---	☒	CONCRETE SIDEWALK	---
○	MANHOLE	●	---	TRAFFIC SIGNALS	---	☒	ASPHALT	---
□	CATCH BASIN	■	---	HYDRO/STREET LIGHT	---	☒	GRANULAR	---
△	CURB INLET	▲	---	MTS/SHAW	---	☒	PAVING STONE	---
○	HYDRO POLE	▲	---	CURB RENEWAL	---	☒	LEGEND - PLAN	PROPOSED
○	LIGHT STANDARD	●	---	PROPERTY LINE	---	☒	LEGEND - PROFILE	PROPOSED
○	TRAFFIC SIGNAL POLE	●	---	RAMP CURB	---	☒	WEST GUTTER	---
⊕	SURVEY BAR	⬆	---	ELEVATIONS	(31.000)	☒	CENTER LINE	---
⊕	GEODETIC BENCH MARK	⬆	---	TREE	---	☒	EAST GUTTER	---

NO.	REVISIONS	DATE	BY
3.	ADDENDUM 1	23/03/14	M.F.
2.	ISSUED FOR TENDER	23/03/07	M.F.
1.	SUBMIT FOR PLAN APPROVAL	23/01/31	T.G.

B.M. IB NW CORNER OF GROVERDALE & LARKSPUR ELEV. 234.396		ENGINEERING DIVISION TECHNOLOGY SERVICES BRANCH 106 - 1155 PACIFIC AVE	
DESIGNED BY	T.G.	CHECKED BY	A.P. & R.W.
DRAWN BY	T.G.	APPROVED BY	R.W.
HOR. SCALE: 1 : 250		VERTICAL: 1 : 10	
DATE: 2023/03/13			

**THE CITY OF WINNIPEG**  
PUBLIC WORKS DEPARTMENT

**2023 LOCAL STREET RENEWAL PROGRAM**  
GROVERDALE AVENUE  
FROM GARDEN GROVE DRIVE TO BURDICK PLACE  
ASPHALT PAVEMENT RESURFACING AND ASSOCIATED WORKS  
FROM STA. 3+00 TO STA. 3+54

CITY DRAWING NUMBER SE-23-57  
SHEET 25 OF 26  
**3**