



278-2023 ADDENDUM 4

CHERITON TOT LOT PLAYGROUND RENEWAL

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: May 16, 2023
BY: Ramy Penner
TELEPHONE NO. 204 451-4608

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

FORM B: PRICES

Replace: 278-2023 Addendum 2 - Form B(R2): Prices with 278-2023 Addendum 4 - Form B(R3): Prices. The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

Form B(R3): Revise No. 14 - Supply and Install (4') Chain Link Fence with Baffle Gate.

Page numbering on some forms may be changed as a result.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, **May 23**, 2023

PART E – SPECIFICATIONS

Revise: E 1.4 to read:

<u>Specification No.</u>	<u>Specification Title</u>
CW-1110	General Instructions
CW-1130	Site Requirements
CW-3110	Sub-Grade, Sub-Base and Base Course Construction
CW-3130	Supply and Installation of Geotextile Fabrics
CW-3170	Earthwork and Grading
CW-3510	Sodding
CW-3520	Seeding
CW-3540	Topsoil and Finish Grading for Establishment of Turf Areas
CW-3550	Chain Link Fencing

<u>Drawing No.</u>	<u>Drawing Name/Title</u>
C.65 – B	Existing Conditions and Removals
C.65 – C	Materials Plan
C.65 – D	Layout Plan A
C.65 – E	Layout Plan B
C.65 – F	Details
C.65 - G	Details B

C.65-H-CAD	CAD File
SCD-105-B1	Heavy Duty Square Post Bollards
SCD-105-G1	Heavy Duty Square Post and Chain Fencing for Vehicle Access
SCD-119	Waste Receptacle Side Opening Metal Slat Type
SCD-121-A	Tache Bench Composite with Arms
SCD-153	English Park Sign w/ Address
SCD-633	Chain Link Fence Entrance Baffle Gate Detail
SCD-646	Parkway Path Crushed Limestone
SCD-650	Engineered Wood Fibre Safety Surfacing
SCD-651-A	Double Tier Timber Edging
SCD-660	Painted Sandbox on Granular Pad

Revise: E17.2.1 to read: Square Post Bollards

Delete: E17.3.1(a)

Add: E22

E22. CHAIN LINK FENCING

E22.1 Description

E22.1.1 The Work to be done by the Contractor under this specification shall include the furnishing of all superintendence, overhead labour, materials, equipment, tools, supplies and all other things necessary for and incidental to the satisfactory performance and completion of all Work as shown on the Drawings and as hereinafter specified, including, but not necessarily confined to the following:

- (a) Supply and Installation of chain link fencing.
- (b) Supply and Installation of chain link vehicle access gate.

E22.1.2 This specification supplements and amends C.W. 3550 - Chain Link Fencing.

E22.2 Materials

E22.2.1 All materials, supplied under this specification shall be of a type approved by the Contract Administrator, and shall be subject to inspection and testing by the Contract Administrator.

E22.2.2 Chain link fencing and gate as specified in CW 3550 and on Drawings.

E22.2.3 Fencing and gate height shall be 1.22m (4'), with knuckled top and bottom fabric.

E22.3 Construction Methods

E22.3.1 As per CW 3550 and the Drawings.

E22.3.2 Fencing is to be installed minimum 610 mm in from the edge of the lane.

E22.3.3 Baffle gate is to be installed as per CW 3550, SCD-633 and the Drawings.

E22.4 Method of Measurement and Basis of Payment

E22.4.1 Method of Measurement shall be as follows:

- (a) Chain link fencing will be measured on a lineal meter basis for the following items:
 - (i) "Supply and Install 4' tall chain link fence" on Form B: Prices.

E22.4.2 Basis of Payment shall be as follows:

- (a) Chain link fencing and gate will be paid for at the Contract Unit Prices. The amount to be paid for shall be the total number of units, as indicated on Form B: Prices. This price shall be full payment for

supplying all labour, equipment and materials, and performing all operations herein described and all other items incidental to the Work and as accepted by the Contract Administrator.

DRAWINGS

Replace: 278-2023 _Drawing_C.65-C with 278-2023_ Drawing_C.65-C-R1

Note: Wood fence and gate to be chain link.

Add: 278-2023_SCD-663-R1

Delete: 278-2023_Drawing_C.65-F