


- GENERAL NOTES:**
1. All field dimensions shall be checked and verified by the General Contractor prior to starting construction.
 2. General Contractor shall confirm the location of all subgrade services prior to starting any excavation.
 3. Excavate all topsoil, loose or swelling soils under to the new construction to the Contract Administrator's satisfaction.
 4. Excavate soil below all new concrete surfaces and replace with a minimum 8 inches of compacted granular fill. Granular fill to be compacted to 98% modified proctor density.
 5. All construction joint locations shall be approved by the Engineer.

- CONCRETE**
1. All concrete shall be 25 MPa, with 5% air entrainment. Apply a steel trowel finish to all surfaces.
 2. General Contractor shall order slump, cylinder and air testing for each concrete pour. Cost for concrete testing shall be paid by the City of Winnipeg, Building Services Division.

STRUCTURAL PLAN VIEW
 SCALE: 1/8" = 1' - 0"

NO.	DESCRIPTION	DATE	BY
REVISIONS / ISSUE			
THE CITY OF WINNIPEG  PUBLIC WORKS DEPARTMENT BUILDING SERVICES DIVISION 100 MAIN STREET, MAIN FLOOR WPG, MB. R3C 1A4			
PROJECT: REPLACEMENT OF WADING POOL BASIN BROADWAY NEIGHBORHOOD CENTRE 185 YOUNG STREET, WINNIPEG, MANITOBA BID OPPORTUNITY NO. 212-2005			
SHEET TITLE: STRUCTURAL PLAN VIEW			
ENG. STAMP	PROJECT NO.	DRAWN BY: L.M.C.	CHECKED BY:
APPROVED BY:			
SCALE: AS NOTED		DATE: APRIL, 2005	
DWG. NO. L2		REV.	