




PARTIAL SIXTH FLOOR PLAN - DEMO MECHANICAL
SCALE: 1/8"=1'-0"



PARTIAL SIXTH FLOOR PLAN - NEW MECHANICAL
SCALE: 1/8"=1'-0"



PARTIAL ROOF PLAN - DEMO MECHANICAL
SCALE: 1/8"=1'-0"



PARTIAL ROOF PLAN - NEW MECHANICAL
SCALE: 1/8"=1'-0"

EXISTING DRAWING NOTES: ##

- EXISTING MAIN AIR CONDITIONING UNIT# RC5, 15 TONS, AIR COOLED.
- EXISTING BACK-UP AIR CONDITIONING UNIT# RC6, 13 TONS, WATER COOLED.
- EXISTING AUXILIARY AIR CONDITIONING UNIT# RC7, 5TON, AIR COOLED.
- EXISTING CONDENSING UNIT ON ROOF SERVING UNIT# RC5.
- EXISTING CONDENSING UNIT ON ROOF SERVING UNIT# RC7.
- EXISTING TEMPERATURE SENSOR SUSPENDED ABOVE RETURN AIR (TYPICAL).
- COLD WATER SUPPLY AND RETURN (DRAIN) LINES BELOW RAISED FLOOR TO EXISTING UNIT# RC6.
- EXISTING REFRIGERANT LINES UP TO CONDENSING UNIT ON ROOF (TYPICAL).
- EXISTING REFRIGERANT LINES DOWN TO AIR CONDITIONING UNIT ON 6TH FLOOR.
- EXISTING CONDENSATE DRAIN LINE BELOW RAISED FLOOR.

SEQUENCE OF WORK: A

- REMOVE EXISTING CONDENSING UNIT# RC7-CU AND ALL ASSOCIATED PIPING.
- HOIST NEW CONDENSING UNIT TO ROOF AND MOUNT AS PER DETAIL MD-1 AND MD-2 IN THE MECHANICAL SPEC. CONNECT TO ELECTRICAL, RUN NEW REFRIGERANT LINES DOWN TO 6TH FLOOR. PREPARE ALL ELECTRICAL AND MECHANICAL CONNECTIONS SUCH THAT NEW INTERIOR UNIT INSTALLATION TIME IS MINIMIZED.
- REMOVE EXISTING AIR CONDITIONING UNIT# RC7 AND ALL ASSOCIATED PIPING.
- REMOVE EXISTING AIR CONDITIONING UNIT# RC6 AND ALL ASSOCIATED PIPING.
- MOVE INTO PLACE AND INSTALL NEW AIR CONDITIONING UNIT AC-2, CONNECT TO PIPING UP TO CU-2, CONNECT CONDENSATE DRAIN TO EXISTING DRAIN LINE UNDER RAISED FLOOR.
- START UP AC-2 AND ENSURE PROPER OPERATION.
- REMOVE EXISTING CONDENSING UNIT# RC5-CU AND ALL ASSOCIATED PIPING.
- REMOVE EXISTING AIR CONDITIONING UNIT# RC5 AND ALL ASSOCIATED PIPING.
- MOVE INTO PLACE AND INSTALL NEW AIR CONDITIONING UNIT AC-1, CONNECT TO PIPING UP TO CU-1, CONNECT CONDENSATE DRAIN TO EXISTING DRAIN LINE UNDER RAISED FLOOR.
- START UP AC-1 AND ENSURE PROPER OPERATION.

NEW DRAWING NOTES: ##

- NEW AIR CONDITIONING UNIT AC-1 IN 6TH FLOOR COMPUTER ROOM. REFER TO GENERAL NOTES & MECHANICAL SPECIFICATIONS FOR DETAILS.
- CONNECT NEW 1/2" LIQUID, 3/8" SUCTION, 1/4" C.W. AND 3/4" CONDENSATE DRAIN LINES AS SHOWN.
- NEW AIR CONDITIONING UNIT AC-2 IN 6TH FLOOR COMPUTER ROOM. REFER TO GENERAL NOTES & MECHANICAL SPECIFICATIONS FOR DETAILS.
- CONNECT NEW 1/2" LIQUID, 3/8" SUCTION, 1/4" C.W. AND 3/4" CONDENSATE DRAIN LINES AS SHOWN.
- 1/2" LIQUID, 3/8" SUCTION LINES THRU ROOF (TYPICAL).
- NEW 3/4" CONDENSATE DRAIN LINE BELOW RAISED FLOOR.

GENERAL NOTES:

- AC-1 & AC-2 LIEBERT MODEL DS035AUB0E1 AIR CONDITIONING UNIT: 120 MBH TOTAL CAPACITY, 103 MBH SENSIBLE CAPACITY, 5500 CFM C/W OPTIONAL 12" FLOOR STAND AND INFRARED HUMIDIFIER.
- CU-1 & CU-2: LEE-TEMP LOW-AMBIENT KIT
- ALL ITEMS SHOWN HIDDEN LINETYPE ON DEMO PLAN TO BE REMOVED.
- REFER TO MECHANICAL SPECIFICATIONS FOR PIPING AND EQUIPMENT MOUNTING DETAILS.

LEGEND:

—	EXISTING
—	NEW
- - - -	EXISTING TO BE REMOVED
---	FUTURE

1	ISSUED FOR TENDER	DS	6/28/05
0	ISSUED FOR CLIENT REVIEW	DS	6/3/05
No.	Revisions	By	Date

PROVINCE OF MANITOBA
REGISTERED PROFESSIONAL ENGINEER
H. J. WAEDT

APEGM
Certificate of Authorization
SMS Engineering Ltd.
No. 166 Expiry: April 30, 2006

SMS ENGINEERING
SMS Engineering Ltd. Consulting Engineers
770 Bradford Street Winnipeg MB Canada R3H 0N3
Telephone 204.775.0291 Fax 204.772.2153
sms@smseeng.mb.ca

REVIEWED AND APPROVED BY CITY OF WINNIPEG.

Project Title
**THE CITY OF WINNIPEG
COMPUTER ROOM COOLING UPGRADE
151 PRINCESS ST. WINNIPEG, MB**

Drawing Title
**151 PRINCESS ST.
SIXTH FLOOR COMPUTER ROOM
AIR CONDITIONING UPGRADE**

Drawn By RNS	Checked By DAS	Approved By HJW
Scale AS NOTED	Date JUNE 2005	File No. 04-169-01
Revision Number 1	Drawing Number M-1	OF 1