
PIPE CULVERTS

1. GENERAL

1.1 Scope of Work

- .1 This Section outlines the requirements for the Supply and Installation of culverts within the construction area.

2. EXECUTION

2.1 General

- .1 Do not perform work during inclement weather conditions or under adverse field conditions such as frozen ground or ground covered with snow, ice, or standing water.

2.2 CMP Culvert Installation

- .1 CMP Culverts will be completed in accordance with City of Winnipeg Standard Construction Specification CW 3610.
- .2 All culverts shall be 2.0 mm gauge and 65 mm x 13 mm corrugation profile.

END OF SECTION