



Note:-
 Unless noted otherwise reinforcing to be placed as follows:-
 Tank Walls - 2" Clear from face of Concrete
 Footings - Top Face 2" Clear
 Bottom Face 3" Clear or 1" clear above pile
 Floor Slab - Top Face 3" Clear from finished surface.
 Bottom Face 3" Clear.
 Piles are to be embedded 3" except where pile caps are required.
 Provide high chairs on top of piles to support reinforcing in top & bottom of floor slab.

DETAIL OF FLOOR SLAB EXPANSION JOINT

REVISIONS	DATE	DESCRIPTION
D	May 4 th 1936	Elevation Top of Centre Pier changed.
E	May 26 th 1936	Size Scum Pipe & Flanged Elbow added. Walls raised & openings added. Effluent Channel changed. Sections L-L & M-M deleted & Elevation R-R added.
F	June 10 th 36	Brass Pipe added Section O-O & Sluice Gate added Section K-K.

GREATER WINNIPEG SANITARY DISTRICT

W. B. LEE, Consulting Engineer

APPROVED

REVISION A, April 7, 1936 Plan No. changed from 137 to P.S.
 Revision B, April 22, 1936 Sludge & Effluent Channels relocated, Pile caps revised
 Revision C, April 28, 1936 See Dorr Co. Inc. Letter of April 23, 1936 & Dorr Co. Inc. Drg. 13902

FILE # NR12917 NEP-2104