
Part 1 General

1.1 REFERENCES

- .1 American Society for Testing and Materials International, (ASTM)
 - .1 ASTM A307-02, Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength.
- .2 Canadian General Standards Board (CGSB)
 - .1 CAN/CGSB-1.40-97, Anti-corrosive Structural Steel Alkyd Primer.
 - .2 CAN/CGSB-1.181-92, Ready-Mixed, Organic Zinc-Rich Coating.
- .3 Canadian Standards Association (CSA International)
 - .1 CAN/CSA-G40.20/G40.21-98, General Requirements for Rolled or Welded Structural Quality Steel.
 - .2 CAN/CSA-G164-M92(R1998), Hot Dip Galvanizing of Irregularly Shaped Articles.
 - .3 CAN/CSA-S16.1-01, Limit States Design of Steel Structures.
 - .4 CSA W48-01, Filler Metals and Allied Materials for Metal Arc Welding (Developed in co-operation with the Canadian Welding Bureau).
 - .5 CSA W59-1989(R2001), Welded Steel Construction (Metal Arc Welding) (Imperial Version).

1.2 SUBMITTALS

- .1 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and data sheet in accordance with Section 01 00 00.
 - .2 Submit two copies of WHMIS MSDS - Material Safety Data Sheets in accordance with Section 01 00 00. Indicate VOC's:
 - .1 For finishes, coatings, primers and paints.
- .2 Shop Drawings
 - .1 Submit shop drawings in accordance with Section 01 00 00.
 - .2 Indicate materials, core thicknesses, finishes, connections, joints, method of anchorage, number of anchors, supports, reinforcement, details, and accessories.

1.3 QUALITY ASSURANCE

- .1 Certificates: Upon request provide product certificates signed by manufacturer certifying materials comply with specified performance characteristics and criteria and physical requirements.
- .2 Pre-installation Meetings: Conduct pre-installation meeting to verify project requirements, manufacturer's installation instructions and manufacturer's warranty requirements.

1.4 DELIVERY, STORAGE, AND HANDLING

- .1 Deliver, store, handle and protect materials in accordance with Section 01 00 00 .

Part 2 Products

2.1 MATERIALS

- .1 Steel sections and plates: to CAN/CSA-G40.20/G40.21, Grade 350W.
- .2 Welding materials: to CSA W59.
- .3 Welding electrodes: to CSA W48 Series.
- .4 Bolts and anchor bolts: to ASTM A307.
- .5 Grout: non-shrink, non-metallic, flowable, 15 MPa at 24 hours.

2.2 FABRICATION

- .1 Fabricate work square, true, straight and accurate to required size, with joints closely fitted and properly secured.
- .2 Use self-tapping shake-proof screws on items requiring assembly by screws or as indicated.
- .3 Where possible, fit and shop assemble work, ready for erection.
- .4 Ensure exposed welds are continuous for length of each joint. File or grind exposed welds smooth and flush.

2.3 FINISHES

- .1 Galvanizing: hot dipped galvanizing with zinc coating 600 g/m² to CAN/CSA-G164.
- .2 Shop coat primer: to CAN/CGSB-1.40.
- .3 Zinc primer: zinc rich, ready mix to CAN/CGSB-1.181.

2.4 SHOP PAINTING

- .1 Apply one shop coat of primer to metal items, with exception of galvanized or concrete encased items.
- .2 Use primer unadulterated, as prepared by manufacturer. Paint on dry surfaces, free from rust, scale, grease. Do not paint when temperature is lower than 7 degrees C.
- .3 Clean surfaces to be field welded; do not paint.

2.5 RAINWATER LEADER

- .1 HSS Steel: 6"x 6" prime painted or galvanized to match existing rainwater leader.

2.6 ACCESS LADDERS

- .1 Stringers: as indicated
- .2 Steel Rungs: as indicated, welded to stringers at 300 mm on centre.
- .3 Brackets: sizes and shapes as indicated, weld to stringers at 900 mm on centre, complete with fixing anchors.
- .4 Cage: as indicated.
- .5 Door: as indicated, provide for lockable by padlock supplied by The City.
- .6 Galvanize finish after fabrication.

Part 3 Execution

3.1 ERECTION

- .1 Do welding work in accordance with CSA W59 unless specified otherwise.
- .2 Erect metalwork square, plumb, straight, and true, accurately fitted, with tight joints and intersections.
- .3 Provide suitable means of anchorage acceptable to such as dowels, anchor clips, bar anchors, expansion bolts and shields, and toggles.
- .4 Exposed fastening devices to match finish and be compatible with material through which they pass.
- .5 Provide components for building by other sections in accordance with shop drawings and schedule.
- .6 Make field connections with bolts to CAN/CSA-S16.1, or weld.
- .7 Hand items over for casting into concrete or building into masonry to appropriate trades together with setting templates.
- .8 Touch-up field welds, bolts and burnt or scratched surfaces after completion of erection with primer.
- .9 Touch-up galvanized surfaces with zinc rich primer where burned by field welding.

3.2 ACCESS LADDERS

- .1 Install access ladders in locations as indicated.

- .2 Erect ladders 200 mm clear of wall on bracket supports.

3.3 CLEANING

- .1 Perform cleaning after installation to remove construction and accumulated environmental dirt.
- .2 Upon completion of installation, remove surplus materials, rubbish, tools and equipment barriers.

END OF SECTION