

EXISTING WALLS TO BE DEMOLISHED EXISTING GYPSUM BOARDS /PANELLING TO BE DEMOLISHED. EXISTING STUD FRAMING TO REMAIN. EXISTING WINDOWS AND FRAMES TO BE DEMOLISHED (FRONT ENTRANCE) EXISTING DOORS TO BE DEMOLISHED MAIN FLOOR DEMOLITION PLAN REMOVE EXISTING "ASBESTOS TILE" & OTHER FLOORING & UNDER FLOOR DOWN TO SUB-FLOOR.

NOTE: ASBESTOS TILE FLOOR REMOVAL TO FOLLOW HAZARDOUS

MATERIAL STANDARD PROCEDURES FOR REMOVAL.

NOTES :

THESE DRAWINGS SHALL NOT BE SCALED.

THE CONTRACTOR SHALL VISIT THE SITE AND SATISFY ONESELF ALL DIMENSIONS, DATUM, AND DETAILED INFORMATION SHOWN ARE CORRECT.

THE CONTRACTOR IS TO REVIEW AND COORDINATE ALL ARCHITECTURAL, MECHANICAL, ELECTRICAL AND STRUCTURAL DRAWINGS FOR ADDITIONAL OPENINGS THROUGH FLOORS, WALLS, AND CEILINGS FOR DUCT, PIPE & ELECTRICAL RISERS AND ALL OPENINGS NOT SHOWN ON DRAWINGS.

ALL PRODUCTS AND MATERIALS TO BE USED AND INSTALLED SHALL CONFORM WITH MANUFACTURER'S SPECIFICATIONS & APPLICABLE CODES.

THE CONTRACTOR SHALL BE RESPONSIBLE TO PATCH AND MAKE GOOD ALL EXISTING CONSTRUCTION AFFECTED BY THE REMOVAL OF ALL ITEMS FORMING THE PART OF THE RENOVATION WORK.

EXISTING SECURITY SYSTEM, MOTION SENSORS, KEYPAD, DOOR CONTACTS & SECURITY PANEL SHALL NOT BE DISCONNECTED. REHANG COMPONENTS ABOVE NEW CEILING SPACE. SECURITY SYSTEM COMPONENT SHALL BE REINSTALLED & SET-UP BY OTHERS.

FOR NEW SUB FLOOR FINISH ON MAIN FLOOR & STAIRS, SEE FLOOR FINISH DRAWING.

ORIGINAL STAMPED BY: R.K.FOK LI Arch.
DATE: 2007.10.15

NO. REVISION/DESCRIPTION BY DATE

DRAWNBYMMKCHECKEDBYAPPROVEDDATE2007.10.05USER APPROVAL



CITY OF WINNIPEG
PLANNING, PROPERTY &

DEVELOPMENT DEPARTMENT
CIVIC ACCOMMODATIONS DIVISION
300 - 65 GARRY ST. R3C 4K4

PROJECT

COMMUNITY POLICE SERVICE CENTRE

1400 HENDERSON HIGHWAY

SHEET TITLE

BASEMENT & MAIN FLOOR PLANS EAST ELEVATION

DEMOLITION

SCALE PROJECT NO. SHEET NO. AS SHOWN 2004-023

DRAWING SHEET SIZE: A1 (841mm x 594mm) PLOT 1:1