



PIPING SCHEDULE				
LINE NUMBER	MATERIAL	SIZE (mm)	REQUIRED ACTION	STATUS
A-1	C.I.	375	NO	LIVE
A-2	C.I.	100	REPLACE WITH PVC	LIVE
A-3	C.I.	100	REPLACE WITH PVC	LIVE
A-4	C.I.	100	NO	LIVE
A-5	ASBESTOS	300	REPLACE HANGERS	LIVE
A-6	STEEL PIPE	12	REMOVE & PLUG	ABANDONED
A-7	STEEL PIPE	150	NO	ABANDONED
A-8	STEEL PIPE OR/TUBING		REMOVE ALL	ABANDONED
A-9	C.I.	75/100	REPLACE WITH PVC	LIVE
A-10	C.I.	150	REPLACE WITH PVC	LIVE
A-11	STEEL PIPE	50	REMOVE & PLUG	ABANDONED
A-12	C.I.	200	REPLACE WITH S.S	LIVE
A-13	C.I.	200	REMOVE PIPE FLUSH TO WALL AND PLUG	ABANDONED
A-14	STEEL PIPE	150	REMOVE & PLUG	ABANDONED
A-15	C.I.	250	REPLACE WITH PVC	LIVE
A-16	ASBESTOS	300	REPLACE HANGERS	LIVE
A-17	C.I.	100	NO	ABANDONED
A-18	C.I.	100	REPLACE WITH PVC	LIVE
A-19	C.I.	100	REPLACE WITH PVC	LIVE

- NOTE:
- 1) FOR STAINLESS STEEL PIPING S.S 316 SCHEDULE 10 TO BE USED.
  - 2) FOR PVC PIPING USE PVC SCHEDULE 80
  - 3) PIPES TO REMAIN IN OPERATION DURING REMOVAL AND REPLACEMENT.

**A SECTION**  
1:50

**APEGM**  
Certificate of Authorization  
CH2M HILL Canada Ltd.  
No. 1441 Expiry: April 30, 2008

B.M. ELEV.		FIELD BOOK #:	
<b>CH2MHILL</b>			
DESIGNED BY	S.ARDAKANI	CHECKED BY	J.BRANDKVIST
DRAWN BY	P.KWONG	APPROVED BY	E.SHARP
HOR. SCALE	1:50	RELEASED FOR CONSTRUCTION	K. ZUREK
VERTICAL		DATE	2007/11/29
DATE	2007 06 20	DATE	2007/11/29

ENGINEER'S SEAL  
ORIGINAL SIGNED BY  
E.J. SHARP  
2007/11/28  
PROJECT No.: 358676  
PLOT DATE: 2007/11/28

**THE CITY OF WINNIPEG**  
WATER AND WASTE DEPARTMENT

**Winnipeg**

NORTH END WATER  
POLLUTION CONTROL CENTRE  
**WET WELL REHABILITATION**  
PROCESS MECHANICAL  
PIPING DEMOLITION PLANS & SECTION

SHEET 17 OF 24  
CONSULTANT DRAWING NUMBER  
P0002  
CITY DRAWING NUMBER  
1-0101M-P-  
P0001-001-00D