Template Version: C420081212 - RW

APPENDIX 'A' GEOTECHNICAL REPORT

Template Version: C420081212 - RW

APPENDIX 'A' - GEOTECHNICAL REPORT

TABLE OF CONTENTS	NO. OF PAGES
GEOTECHNICAL REPORT FOR TURNER AVENUE	16
Test Hole Locations	1
Summary of Core Samples	1
Test Hole Logs	10
Pavement Core Photos	3

The geotechnical report is provided to aid in the Contractor's evaluation of the soil conditions. The information presented is considered accurate at the locations shown on the Drawings and at the time of drilling. However, variations in soil conditions may exist between test holes and fluctuations in groundwater levels can be expected seasonally and may occur as a result of construction activities. The nature and extent of variations may not become evident until construction commences.



CITY OF WINNIPEG 2009 STREET RENEWAL PROGRAM TURNER AVENUE MOUNT ROYAL ROAD TO MOUNT ROYAL ROAD

Prepared for AECOM 99 COMMERCE DRIVE WINNIPEG, MANITOBA R3P 0Y7

Prepared by
THE NATIONAL TESTING LABORATORIES LIMITED
199 HENLOW BAY
WINNIPEG, MANITOBA
R3Y 1G4





Project No.:EAR-811	Drawn by: KK	Figure: 1
Date: Jan. 26. 2009	Reviewed by: DF	Scale: NTS

Testhole Location Plan
City of Winnipeg2009 Street Renewal Program
Turner Avenue
Mount Royal Road to Mount Royal Road

City of Winnipeg 2009 Street Renewal Program Turner Avenue Mount Royal Road to Mount Royal Road

T 11 - 1 -		Paveme	nt Surface	Pavement :	Structure Material	0	Sample	Moisture	Pai	ticle Size	e Analys	sis	А	tterberg L	imits
Testhole ID	Testhole Location	Туре	Thickness (mm)	Туре	Thickness (mm)	Sample Description	Depth (m)	Content (%)	Gravel (%)	Sand (%)	Silt (%)	Clay (%)	Liquid Limit	Plastic Limit	Plasticity Index
TH1	Along east property line of 94 Turner Ave., east bound lane, 1 m from south curb	Asphalt / Concrete	15 /162	-	-	-	-	-	i	-	-	-	-	-	-
TH2	Along east property line of 83 Turner Ave., west bound lane, 1.5 m from north curb	Asphalt / Concrete	31 / 170	-	-	Clay	0.6	30	0	11.0	20.8	68.2	63	22	41
TH3	Along west property line of 70 Turner Ave., east bound lane, 1.5 m from south curb	Asphalt / Concrete	25 / 140	-	-	_	-	-	-	-	-	-	-	-	-
TH4	Along east property line of 63 Turner Ave., west bound lane, 1.5 m from north curb	Asphalt / Concrete	40 / 168	-	-	-	-	-	-	-	-	-	-	-	-
TH5	Along south property line of 51 Turner Ave., north bound lane, 1.5 m from east curb	Asphalt / Concrete	32 / 155	-	-	-	-	-	-	-	-	-	-	-	-
TH6	Along south property line of 43 Turner Ave., south bound lane, 1.5 m from west curb	Asphalt / Concrete	38 / 180	-	-	Clayey Silt	0.9	29	0	8.1	59.2	32.7	31	17	14
TH7	Along east property line of 35 Turner Ave., east bound lane, 1.5 m from south curb	Asphalt / Concrete	28 / 174	-	-	-	-	-	-	-	-	-	-	-	-
TH8	Along east property line of 23 Turner Ave., west bound lane, 1.5 m from north curb	Asphalt / Concrete	35 / 157	-	-	-	-	-	-	-	-	-	-	-	-
TH9	Along east property line of 11 Turner Ave., east bound lane, 1.5 m from south curb	Asphalt / Concrete	33 / 140	-	-	-	-	-	-	-	-	-	-	-	-
TH10	Along east property line of 1 Turner Ave., west bound lane, 1.5 m from north curb	Asphalt / Concrete	51 / 154	-	-	-	-	-	-	-	-	-	-	-	-

Note: No granular fill material was encountered beneath the concrete pavement



Date Drilled: January 9, 2009

Logged by: Kurtis Kulchyski

Depth of Testhole: 2.1 m

Project Name: 2009 Residential Street Renewal Program

Client: AECOM

Site: Turner Ave. Mount Royal Rd. to Mount Royal Rd.

Testhole Location: Along East Property Line of 94 Turner Ave, East Bound Lane, 1 m from south curb

		Subsurface Profile	Laboratory Testing
Depth (m)	Symbol	Description	Water Content (%) 0 20 40 60 80 100
0.0-		Ground Surface	
0.0		Asphalt	
		Concrete	
- -		Clay - grey, stiff, moist, high plasticity, trace silt - brown below 1.2 m	47
0.5- - -			4/1
1.0- - -			38
- 1.5 -			40
2.0-			40
-		 Frost present to 1.4 m. No water seepage or slough observed during or upon completion of drilling. Testhole was terminated at 2.1 m. 	
2.5-			



Date Drilled: January 9, 2009

Depth of Testhole: 2.1 m

Project Name: 2009 Residential Street Renewal Program

Client: AECOM

Site: Turner Ave. Mount Royal Rd. to Mount Royal Rd. Logged by: Kurtis Kulchyski

Testhole Location: Along East Property Line of 83 Turner Ave, West Bound Lane, 1.5 m from north curb

		Subsurface Profile			I	_abora	tory 7	Testin _s	g		
Depth (m)	Symbol	Description	PL ·	Wate	r Conte	nt (%) 75	LL 100	Gravel (%)	Sand (%)	Silt (%)	Clay (%)
0.0-	2002000	Ground Surface Asphalt	 - -	[[-					
	-	Concrete									
		Clay - brown, stiff, moist, high plasticity, with layers of silt to 0.5 m		3	88						
0.5-				30		4		0	11.0	20.8	68.2
1.0-	-			33	3						
1.5-				3	6						
2.0-					43						
	- - -	 Frost present to 1.4 m. No water seepage or slough observed during or upon completion of drilling. Testhole was terminated at 2.1 m. 									
2.5-	-		-	!	!	!	ı				



Date Drilled: January 9, 2009

Project Name: 2009 Residential Street Renewal Program

Client: AECOM

Depth of Testhole: 2.1 m Site: Turner Ave. Mount Royal Rd. to Mount Royal Rd. Logged by: Kurtis Kulchyski Testhole Location: Along West Property Line of 70Turner Ave, East Bound Lane, 1.5 m from south curb

				Laboratory Testing		
Depth (m)	Symbol	Description	0		ater Co (%) 40	ontent 60 80 10
0.0		Ground Surface		•	•	
0.0-	******	Asphalt	7[
		Concrete				
		Clay - grey, stiff, moist, high plasticity - brown below 1.4 m	l	3	30	
0.5-			U		33	
1.0-					35	
1.5-					37	
2.0-					40 42	
	- -	 Frost present to 1.4 m. No water seepage or slough observed during or upon completion of drilling. Testhole was terminated at 2.1 m. 				



Project Name: 2009 Residential Street Renewal Program

Client: AECOM
Site: Turner Ave. Mount Royal Rd. to Mount Royal Rd.

Date Drilled: January 9, 2009 Depth of Testhole: 2.1 m Logged by: Kurtis Kulchyski

Testhole Location: Along East Property Line of 63 Turner Ave, West Bound Lane, 1.5 m from north curb

Depth (m)	Symbol	Description		W	ater Co	mtont
0.0			o	20	(%)	
0.0		Ground Surface	+			
-		Asphalt	∄ †'			
		Concrete				
0.5		Clay - grey, stiff, moist, high plasticity			377	
1.0-		Clayey Silt - grey, firm, moist, low to intermediate plasticity		29	5	
1.5		Clay - brown, stiff, moist, high plasticity		3	35	
2.0					42	
-		 Frost present to 1.4 m. No water seepage or slough observed during or upon completion of drilling. Testhole was terminated at 2.1 m. 				



Project Name: 2009 Residential Street Renewal Program

Client: AECOM

Site: Turner Ave. Mount Royal Rd. to Mount Royal Rd.

Depth of Testhole: 2.1 m Logged by: Kurtis Kulchyski

Date Drilled: January 9, 2009

Testhole Location: Along South Property Line of 51 Turner Ave, North Bound Lane, 1.5 m from east curb

	,	Subsurface Profile		Laboratory Testing			
Depth (m)	Symbol	Description	0	W 20	ater Con (%)	tent 80 100	
			Ŭ,		10 00		
0.0	25277253	Ground Surface Asphalt	┧┝				
-		Concrete					
-			_				
-		Clay - grey, stiff, moist, high plasticity - with layers of silt below 0.8 m - brown below 1.4 m			35		
0.5-					40		
-				25			
1.0-				R			
-					38		
- 1.5-					44		
-							
-					37		
2.0-					41		
- - -		 Frost present to 1.4 m. No water seepage or slough observed during or upon completion of drilling. Testhole was terminated at 2.1 m. 					
2.5-				-			



Project Name: 2009 Residential Street Renewal Program

Client: AECOM

Site: Turner Ave. Mount Royal Rd. to Mount Royal Rd.

Date Drilled: January 9, 2009 Depth of Testhole: 2.1 m Logged by: Kurtis Kulchyski

Testhole Location: Along South Property Line of 43 Turner Ave, South Bound Lane, 1.5 m from west curb

Depth		Subsurface Profile				Laboratory Testing					
(m)	Symbol	Description	PL - 0	Water	Conte	ent (%) 75	LL 100	Gravel (%)	Sand (%)	Silt (%)	Clay (%)
0.0-		Ground Surface									
0.0-		Asphalt	7["								
-		Concrete									
-		Clay - brown, stiff, moist, high plasticity, with layers of silt below 0.6 m			5b						
0.5-				33							
1.0- - -	-	Clayey Silt - tan, firm, moist, low to intermediate plasticity		29				0	8.1	59.2	32.7
1.5- -		Clay - brown, stiff, moist, high plasticity		33							
2.0- -		• Frost present to 1.2 m.		3	41						
- - 2.5	-	 No water seepage or slough observed during or upon completion of drilling. Testhole was terminated at 2.1 m. 									



Date Drilled: January 9, 2009

Depth of Testhole: 2.1 m

Project Name: 2009 Residential Street Renewal Program

Client: AECOM

Site: Turner Ave. Mount Royal Rd. to Mount Royal Rd.

Logged by: Kurtis Kulchyski Testhole Location: Along East Property Line of 35 Turner Ave, East Bound Lane, 1.5 m from south curb

	, ,	Subsurface Profile	Laboratory Testing			
Depth (m)	Symbol	Description	Q	W 20	(%) 40 60	tent 80 100
0.0-		Ground Surface				
0.0	******	Asphalt	7			
-		Concrete		i		
- - -		Clay - grey, stiff, moist, high plasticity - brown below 1.2 m			34	
0.5-					35	
-					39	
1.0-				1	37	
- - 1.5 -					43	
- - 2.0-					41	
- - -		 Frost present to 1.4 m. No water seepage or slough observed during or upon completion of drilling. Testhole was terminated at 2.1 m. 				
2.5-						



Date Drilled: January 9, 2009

Depth of Testhole: 2.1 m

Project Name: 2009 Residential Street Renewal Program

Client: AECOM

Site: Turner Ave. Mount Royal Rd. to Mount Royal Rd. Logged by: Kurtis Kulchyski Testhole Location: Along East Property Line of 23 Turner Ave, West Bound Lane, 1.5 m from north curb

		Subsurface Profile	Laboratory Testing
Depth (m)	Symbol	Description	Water Content (%) 0 20 40 60 80 100
0.0-		Ground Surface	
_	no a suno a	Asphalt	
		Concrete	
-		Clay Fill - brown, stiff, moist, high plasticity with some silt inclusions	27
0.5-		Clayey Silt - tan/light brown, firm, moist, intermediate plasticity - with layers of clay below 1.2 m	25 25 28
2.0-		Clay - brown, stiff, moist, high plasticity, with layers of silt to 2.0 m	40
-		 Frost present to 1.4 m. No water seepage or slough observed during or upon completion of drilling. Testhole was terminated at 2.1 m. 	
2.5-	1		



Date Drilled: January 9, 2009

Logged by: Kurtis Kulchyski

Depth of Testhole: 2.1 m

Project Name: 2009 Residential Street Renewal Program

Client: AECOM

Site: Turner Ave. Mount Royal Rd. to Mount Royal Rd.

Testhole Location: Along East Property Line of 11 Turner Ave, East Bound Lane, 1.5 m from south curb

Clay - grey, firm to stiff, moist, high plasticity - brown below 1.5 m 1.5- 2.0- **Frost present to 1.2 m.** Ground Surface Ground Surface Asphalt Concrete 1.5- 38 41 41 46 **Frost present to 1.2 m.**	Testing	Laboratory Te	Lab	Subsurface Profile	,	
Asphalt Concrete Clay - grey, firm to stiff, moist, high plasticity - brown below 1.5 m 1.0- 1.5- 35 41 2.0- • Frost present to 1.2 m.	ontent) 60 80 100	Water Cont (%) 20 40 60		Description	Symbol	Depth (m)
Asphalt Concrete Clay - grey, firm to stiff, moist, high plasticity - brown below 1.5 m 1.5- 1.5- 38 41 46 • Frost present to 1.2 m.				Ground Surface		0.0-
Clay - grey, firm to stiff, moist, high plasticity - brown below 1.5 m 1.0- 1.5- 1.5- *Frost present to 1.2 m.			11	(4/8)		0.0
- grey, firm to stiff, moist, high plasticity - brown below 1.5 m 1.0- 1.5- 35 42 42 41 46 • Frost present to 1.2 m.] }	Concrete		
1.0- 1.5- 2.0- • Frost present to 1.2 m.	58 	58		- grey, firm to stiff, moist, high plasticity		- -
1.5- 2.0- • Frost present to 1.2 m.		42				0.5- - - -
2.0- • Frost present to 1.2 m.		35 35				1.0- -
• Frost present to 1.2 m.		38				- 1.5- -
Frost present to 1.2 m. No water seepage or slough observed during or upon completion.		41				2.0-
of drilling. • Testhole was terminated at 2.1 m.				 No water seepage or slough observed during or upon completion of drilling. 		- -



Project Name: 2009 Residential Street Renewal Program

Client: AECOM

Site: Turner Ave. Mount Royal Rd. to Mount Royal Rd.

Depth of Testhole: 2.1 m Logged by: Kurtis Kulchyski

Date Drilled: January 9, 2009

Testhole Location: Along East Property Line of 1 Turner Ave, West Bound Lane, 1.5 m from north curb

Subsurface Profile				Laboratory Testing			
Depth (m)	Symbol	Description	o O	W	ater Conte (%) 40 60	ent 80 100	
0.0-		Ground Surface					
	75663756	Asphalt	$-\parallel$				
		Concrete					
-		Clay - grey, firm to stiff, moist, high plasticity - brown below 1.7 m			55		
0.5- - -					400		
1.0-					41		
- - 1.5-			l l		42		
- - 2.0-					38		
- - -		 Frost present to 1.1 m. No water seepage or slough observed during or upon completion of drilling. Testhole was terminated at 2.1 m. 					
2.5-	-			<u> </u>		-	





Pavement core from Testhole TH 1



Pavement core from Testhole TH 2



Pavement core from Testhole TH 3



Pavement core from Testhole TH 4





Pavement core from Testhole TH 5



Pavement core from Testhole TH 6



Pavement core from Testhole TH 7



Pavement core from Testhole TH 8





Pavement core from Testhole TH 9



Pavement core from Testhole TH 10