

Part 1 General

1.1 SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Shop drawings to show:
 - .1 Mounting arrangements.
 - .2 Operating and maintenance clearances.
- .3 Shop drawings and product data accompanied by:
 - .1 Detailed drawings of bases, supports, and anchor bolts.
 - .2 Acoustical sound power data, where applicable.
 - .3 Points of operation on performance curves.
 - .4 Manufacturer to certify current model production.
 - .5 Certification of compliance to applicable codes.
- .4 Closeout Submittals:
 - .1 Provide operation and maintenance data for incorporation into manual specified in Section 01 77 00 – Closeout Procedures.
 - .2 Operation and maintenance manual approved by, and final copies deposited with, Contract Administrator before final inspection.
 - .3 Operation data to include:
 - .1 Control schematics for systems including environmental controls.
 - .2 Description of systems and their controls.
 - .3 Description of operation of systems at various loads together with reset schedules and seasonal variances.
 - .4 Operation instruction for systems and component.
 - .5 Description of actions to be taken in event of equipment failure.
 - .6 Valves schedule and flow diagram.
 - .7 Colour coding chart.
 - .4 Maintenance data to include: Servicing, maintenance, operation and trouble-shooting instructions for each item of equipment.
 - .1 Data to include schedules of tasks, frequency, tools required and task time.
 - .5 Performance data to include:
 - .1 Equipment manufacturer's performance datasheets with point of operation as left after commissioning is complete.
 - .2 Equipment performance verification test results.
 - .3 Special performance data as specified.
 - .4 Testing, adjusting and balancing reports as specified in Section 23 05 93 - Testing, Adjusting and Balancing for HVAC.
 - .6 Approvals:

- .1 Submit 2 copies of draft Operation and Maintenance Manual to Contract Administrator for approval. Submission of individual data will not be accepted unless directed by Contract Administrator.
- .2 Make changes as required and re-submit as directed by Contract Administrator.
- .7 Additional data:
 - .1 Prepare and insert into operation and maintenance manual additional data when need for it becomes apparent during specified demonstrations and instructions.
- .8 Site records:
 - .1 Contract Administrator will provide 1 set of reproducible mechanical drawings. Provide sets of white prints as required for each phase of work. Mark changes as work progresses and as changes occur.
 - .2 Transfer information weekly to reproducibles, revising reproducibles to show work as actually installed.
 - .3 Use different colour waterproof ink for each service.
 - .4 Make available for reference purposes and inspection.
- .9 As-built drawings:
 - .1 Prior to start of Testing, Adjusting and Balancing for HVAC, finalize production of as-built drawings.
 - .2 Identify each drawing in lower right hand corner in letters at least 12 mm high as follows: - "AS BUILT DRAWINGS: THIS DRAWING HAS BEEN REVISED TO SHOW MECHANICAL SYSTEMS AS INSTALLED" (Signature of Contractor) (Date).
 - .3 Submit to Contract Administrator for approval and make corrections as directed.
 - .4 Perform testing, adjusting and balancing for HVAC using as-built drawings.
 - .5 Submit completed reproducible as-built drawings with Operating and Maintenance Manuals.
- .10 Submit copies of as-built drawings for inclusion in final TAB report.

1.2 SCREWS, BOLTS AND FASTENERS

- .1 Use standard commercial sizes and patterns with material and finish suitable for service.
- .2 Use heavy hex heads, semi-finished unless otherwise specified. Use non-ferrous material throughout for plumbing services. Use type 304 stainless steel for exterior areas.
- .3 Bolts used on fan equipment for access to motors, bearings, filters and the like shall be heavy-duty.
- .4 Bolts shall not project more than one diameter beyond nuts.
- .5 Washers
 - .1 Use plain-type washers on equipment, sheet metal and soft gaskets, lock-type washers where vibration occurs, and resilient washers with stainless steel.

1.3 DYNAMIC EQUIPMENT BALANCING

- .1 All rotating equipment supplied shall be dynamically balanced at the factory.
- .2 All rotating equipment shall be checked for vibration after installation. Excessive vibration shall be remedied under warranty, or the equipment shall be replaced with new one.

1.4 MAINTENANCE

- .1 Furnish spare parts in accordance with Section 01 77 00 - Closeout Procedures as follows:
 - .1 One set of packing for each pump.
 - .2 One casing joint gasket for each size pump.
 - .3 One glass for each gauge glass.
 - .4 One filter cartridge or set of filter media for each filter or filter bank in addition to final operating set.
- .2 Provide one set of special tools required to service equipment as recommended by manufacturers and in accordance with Section 01 77 00 - Closeout Procedures.
- .3 Furnish one commercial quality grease gun, grease and adapters to suit different types of grease and grease fittings.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 CLEANING

- .1 Clean interior and exterior of all systems including strainers. Vacuum interior of ductwork and air handling units.

3.2 DEMONSTRATION

- .1 Supply tools, equipment and personnel to demonstrate and instruct operating and maintenance personnel in operating, controlling, adjusting, trouble-shooting and servicing of all systems and equipment during regular work hours, prior to acceptance.
- .2 Use operation and maintenance manual, as-built drawings, and audio visual aids as part of instruction materials.
- .3 Instruction duration time requirements as specified in appropriate sections.
- .4 Contractor will record these demonstrations on video tape for future reference.

3.3 PROTECTION

- .1 Protect equipment and systems openings from dirt, dust, and other foreign materials with materials appropriate to system.

END OF SECTION

Part 1 General

1.1 GENERAL

- .1 Following Appendix of Manufacturers lists manufacturers of equipment and materials acceptable to Contract Administrator, subject to individual clauses under the various sub-sections of Mechanical Work Specifications. See item 'Materials' under this section of specification.
- .2 Product noted in individual specification clauses is an item that meets specification in all respects regarding performance, quality of material and workmanship, and is acceptable to Contract Administrator without qualification. Equipment proposed from other manufacturers listed as 'Approved Manufacturers' and alternates shall meet same standards.
- .3 Contractor to submit within forty-eight hours of notification from Contract Administrator, one (1) copy of fully and properly completed Appendix of Manufacturers listing thereon names of manufacturers of products which shall be used to execute work of Contract. If list is not submitted within 48 hours, Contractor must use product named in each individual clause.
- .4 Submit shop drawings for all items marked with asterisk(*)
- .5 **All steel piping, all welding fittings, all malleable iron fittings shall be of North American manufacture.**

1.2 EQUIPMENT OR MATERIAL & APPROVED MANUFACTURERS

- .1 **ELECTRIC MOTORS**
 - .1 G.E.; Siemens; Tamper; Reliance; Leland; Lincoln; U.S. Electric; Century; Baldor; WEG; Toshiba
- .2 **INSULATION**
 - .1 External Duct Insulation Manville; Fibreglas; Knauf
 - .2 Lagging Adhesive/Coating Bakor; Childers; Fosters
- .3 **AIR DISTRIBUTION**
 - .1 Ducturns, damper hardware, fan connections* Duro-Dyne
 - .2 Duct Sealer Duro-Dyne; 3M; Flexa-Duct; United; Bakelite
 - .3 Roof Exhaust* Penn; Greenheck; Ventex
- .4 **H.V.A.C. BALANCE AND TESTING**
 - .1 H.V.A.C. Balance & Testing Agency Airdronics Inc.; DFC; AHS; Air Movement

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Concrete housekeeping pads, hangers and supports for mechanical piping, ducting and equipment.

1.2 REFERENCES

- .1 American National Standards Institute/American Society of Mechanical Engineers (ANSI/ASME)
 - .1 ANSI/ASME B31.1-04, Power Piping.
- .2 American Society for Testing and Materials International (ASTM)
 - .1 ASTM A125-1996(R2001), Specification for Steel Springs, Helical, Heat-Treated.
 - .2 ASTM A307-04, Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength.
 - .3 ASTM A563-04a, Specification for Carbon and Alloy Steel Nuts.
- .3 Factory Mutual (FM)
- .4 Health Canada/Workplace Hazardous Materials Information System (WHMIS)
 - .1 Material Safety Data Sheets (MSDS).
- .5 Manufacturer's Standardization Society of the Valves and Fittings Industry (MSS)
 - .1 MSS SP58-2002, Pipe Hangers and Supports - Materials, Design and Manufacture.
 - .2 ANSI/MSS SP69-2003, Pipe Hangers and Supports - Selection and Application.
 - .3 MSS SP89-2003, Pipe Hangers and Supports - Fabrication and Installation Practices.
- .6 Underwriter's Laboratories of Canada (ULC)

1.3 SYSTEM DESCRIPTION

- .1 Design Requirements:
 - .1 Construct pipe hanger and support to manufacturer's recommendations utilizing manufacturer's regular production components, parts and assemblies.
 - .2 Base maximum load ratings on allowable stresses prescribed by MSS SP58.ASME B31.1 or
 - .3 Ensure that supports, guides, anchors do not transmit excessive quantities of heat to building structure.
 - .4 Design hangers and supports to support systems under conditions of operation, allow free expansion and contraction, prevent excessive stresses from being introduced into pipework or connected equipment.
 - .5 Provide for vertical adjustments after erection and during commissioning. Amount of adjustment in accordance with MSS SP58.

1.4 SUBMITTALS

- .1 Submittals: in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit shop drawings and product data for following items:
 - .1 Bases, hangers and supports.
 - .2 Connections to equipment and structure.
 - .3 Structural assemblies.
- .3 Quality assurance submittals: submit following in accordance with Section 01 33 00 - Submittal Procedures.
 - .1 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performance characteristics and physical properties.
 - .2 Instructions: submit manufacturer's installation instructions.

Part 2 Products

2.1 GENERAL

- .1 Fabricate hangers, supports and sway braces in accordance with ANSI B31.1 and MSS SP58.
- .2 Use components for intended design purpose only. Do not use for rigging or erection purposes.

2.2 VARIABLE SUPPORT SPRING HANGERS

- .1 Vertical movement: 13 mm minimum, 50 mm maximum, use single spring pre-compressed variable spring hangers.
- .2 Steel alloy springs: to ASTM A125, shot peened, magnetic particle inspected, with +/-5 % spring rate tolerance, tested for free height, spring rate, loaded height and provided with CMTR.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 Install in accordance with:
 - .1 manufacturer's instructions and recommendations.
- .2 Provide supplementary structural steelwork where structural bearings do not exist or where concrete inserts are not in correct locations.

- .3 Use variable support spring hangers where:
 - .1 transfer of load to adjacent piping or to connected equipment is not critical.
 - .2 variation in supporting effect does not exceed 25 % of total load.

3.3 HANGER SPACING

- .1 Plumbing piping: to Provincial Code.
- .2 Fire protection: to applicable fire code.
- .3 Gas and fuel oil piping: up to NPS 1/2: every 1.8 m.
- .4 Copper piping: up to NPS 1/2: every 1.5 m.
- .5 Flexible joint roll groove pipe: in accordance with table below, but not less than one hanger at joints.
- .6 Within 300 mm of each elbow.

Maximum Pipe Size : NPS	Maximum Spacing Steel	Maximum Spacing Copper
up to 1-1/4	2.1 m	1.8 m
1-1/2	2.7 m	2.4 m
2	3.0 m	2.7 m
2-1/2	3.6 m	3.0 m
3	3.6 m	3.0 m
3-1/2	3.9 m	3.3 m
4	4.2 m	3.6 m
5	4.8 m	
6	5.1 m	
8	5.7 m	
10	6.6 m	
12	6.9 m	

- .7 Pipework greater than NPS 12: to MSS SP69.

3.4 HANGER INSTALLATION

- .1 Install hanger so that rod is vertical under operating conditions.
- .2 Adjust hangers to equalize load.
- .3 Support from structural members. Where structural bearing does not exist or inserts are not in suitable locations, provide supplementary structural steel members.

3.5 HORIZONTAL MOVEMENT

- .1 Angularity of rod hanger resulting from horizontal movement of pipework from cold to hot position not to exceed 4 degrees from vertical.
- .2 Where horizontal pipe movement is less than 13 mm, offset pipe hanger and support so that rod hanger is vertical in the hot position.

3.6 FINAL ADJUSTMENT

- .1 Adjust hangers and supports:
 - .1 Ensure that rod is vertical under operating conditions.
 - .2 Equalize loads.
- .2 Adjustable clevis:
 - .1 Tighten hanger load nut securely to ensure proper hanger performance.
 - .2 Tighten upper nut after adjustment.
- .3 C-clamps:
 - .1 Follow manufacturer's recommended written instructions and torque values when tightening C-clamps to bottom flange of beam.
- .4 Beam clamps:
 - .1 Hammer jaw firmly against underside of beam.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 TAB is used throughout this Section to describe the process, methods and requirements of testing, adjusting and balancing for HVAC.
- .2 TAB means to test, adjust and balance to perform in accordance with requirements of Contract documents and to do other work as specified in this section.

1.2 QUALIFICATIONS OF TAB PERSONNEL

- .1 Submit names of personnel to perform TAB to Contract Administrator within 90 days of award of contract.
- .2 Provide documentation confirming qualifications, successful experience.
- .3 TAB: performed in accordance with the requirements of standard under which TAB Firm's qualifications are approved:
 - .1 Associated Air Balance Council, (AABC) National Standards for Total System Balance, MN-1-2002.
 - .2 National Environmental Balancing Bureau (NEBB) TABES, Procedural Standards for Testing, Adjusting, Balancing of Environmental Systems-1998.
 - .3 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA), HVAC TAB HVAC Systems - Testing, Adjusting and Balancing-2002.
- .4 Recommendations and suggested practices contained in the TAB Standard: mandatory.
- .5 Use TAB Standard provisions, including checklists, and report forms to satisfy Contract requirements.
- .6 Use TAB Standard for TAB, including qualifications for TAB Firm and Specialist and calibration of TAB instruments.
- .7 Where instrument manufacturer calibration recommendations are more stringent than those listed in TAB Standard, use manufacturer's recommendations.
- .8 TAB Standard quality assurance provisions such as performance guarantees form part of this contract.
 - .1 For systems or system components not covered in TAB Standard, use TAB procedures developed by TAB Specialist.
 - .2 Where new procedures, and requirements, are applicable to Contract requirements have been published or adopted by body responsible for TAB Standard used (AABC), requirements and recommendations contained in these procedures and requirements are mandatory.

1.3 PURPOSE OF TAB

- .1 Test to verify proper and safe operation, determine actual point of performance, evaluate qualitative and quantitative performance of equipment, systems and controls at design, average and low loads using actual or simulated loads
- .2 Adjust and regulate equipment and systems to meet specified performance requirements and to achieve specified interaction with other related systems under normal and emergency loads and operating conditions.
- .3 Balance systems and equipment to regulate flow rates to match load requirements over full operating ranges.

1.4 EXCEPTIONS

- .1 TAB of systems and equipment regulated by codes, standards to satisfaction of authority having jurisdiction.

1.5 CO-ORDINATION

- .1 Schedule time required for TAB including repairs, re-testing into project construction and completion schedule to ensure completion before acceptance of project.
- .2 Do TAB of each system independently and subsequently, where interlocked with other systems, in unison with those systems.

1.6 PRE-TAB REVIEW

- .1 Review contract documents before project construction is started and confirm in writing to Contract Administrator adequacy of provisions for TAB and other aspects of design and installation pertinent to success of TAB.
- .2 Review specified standards and report to the Contract Administrator in writing proposed procedures which vary from standard.
- .3 During construction, co-ordinate location and installation of TAB devices, equipment, accessories, measurement ports and fittings.

1.7 START-UP

- .1 Follow start-up procedures as recommended by equipment manufacturer unless specified otherwise.
- .2 Follow special start-up procedures specified elsewhere in Division 23.

1.8 OPERATION OF SYSTEMS DURING TAB

- .1 Operate systems for length of time required for TAB and as required by Contract Administrator for verification of TAB reports.

1.9 START OF TAB

- .1 Notify The City's Representative, Contract Administrator 7 days prior to start of TAB.

- .2 Start TAB when building is essentially completed, including:
- .3 Installation of ceilings, doors, windows, other construction affecting TAB.
- .4 Application of weatherstripping, sealing, and caulking.
- .5 Pressure, leakage, other tests specified elsewhere Division 23.
- .6 Provisions for TAB installed and operational.
- .7 Start-up, verification for proper, normal and safe operation of mechanical and associated electrical and control systems affecting TAB including but not limited to:
 - .1 Proper thermal overload protection in place for electrical equipment.
 - .2 Air systems:
 - .1 Filters in place, clean.
 - .2 Duct systems clean.
 - .3 Ducts, air shafts, ceiling plenums are airtight to within specified tolerances.
 - .4 Correct fan rotation.
 - .5 Fire, smoke, volume control dampers installed and open.
 - .6 Coil fins combed, clean.
 - .7 Access doors, installed, closed.
 - .8 Outlets installed, volume control dampers open.

1.10 APPLICATION TOLERANCES

- .1 Do TAB to following tolerances of design values:
 - .1 HVAC systems: plus 5 %, minus 5 %.

1.11 ACCURACY TOLERANCES

- .1 Measured values accurate to within plus or minus 2 % of actual values.

1.12 INSTRUMENTS

- .1 Calibrate in accordance with requirements of most stringent of referenced standard for either applicable system or HVAC system.

1.13 SUBMITTALS

- .1 Submit, prior to commencement of TAB:
- .2 Proposed methodology and procedures for performing TAB if different from referenced standard.

1.14 PRELIMINARY TAB REPORT

- .1 Submit for checking and approval of The City's Representative Contract Administrator, prior to submission of formal TAB report, sample of rough TAB sheets. Include:
 - .1 Details of instruments used.

- .2 Details of TAB procedures employed.
- .3 Calculations procedures.
- .4 Summaries.

1.15 TAB REPORT

- .1 TAB report to show results in SI units and to include:
 - .1 Project record drawings.
 - .2 System schematics.
- .2 Submit two copies of tab report to Contract Administrator for initial review. Do changes and comments thru resubmit. 6 copies of TAB Report to Contract Administrator for verification and approval, in English in D-ring binders, complete with index tabs.

1.16 VERIFICATION

- .1 Reported results subject to verification by The City's Representative Contract Administrator.
- .2 Number and location of verified results as directed by Contract Administrator.
- .3 Pay costs to repeat TAB as required to satisfaction of Contract Administrator.

1.17 SETTINGS

- .1 After TAB is completed to satisfaction of Contract Administrator, replace drive guards, close access doors, lock devices in set positions, ensure sensors are at required settings.
- .2 Permanently mark settings to allow restoration at any time during life of facility. Do not eradicate or cover markings.

1.18 COMPLETION OF TAB

- .1 TAB considered complete when final TAB Report received and approved by Contract Administrator.

1.19 AIR SYSTEMS

- .1 Standard: TAB to most stringent of TAB standards of AABC.
- .2 Do TAB of all exhaust, supply air and return air systems, equipment, components, controls specified in Division 23. Include new and modified systems in the existing High School Building.
- .3 Qualifications: personnel performing TAB current member in good standing of AABC.
- .4 Measurements: to include as appropriate for systems, equipment, components, controls: air velocity, static pressure, flow rate, pressure drop (or loss), temperatures (dry bulb, wet bulb, dewpoint), duct cross-sectional area, RPM, electrical power, voltage, noise, vibration.
- .5 Locations of equipment measurements: to include as appropriate:

- .1 Inlet and outlet of dampers, filter, coil, humidifier, fan, other equipment causing changes in conditions.
- .2 At controllers, controlled device.
- .6 Locations of systems measurements to include as appropriate: main ducts, main branch, sub-branch, run-out (or grille, register or diffuser).

Part 2 Products

2.1 NOT USED

- .1 Not used.

Part 3 Execution

3.1 NOT USED

- .1 Not used.

END OF SECTION

Part 1 General

1.1 RELATED SECTIONS

- .1 Section 01 33 00 - Submittal Procedures.
- .2 Section 01 74 11 - Cleaning.
- .3 Section 23 05 29 - Hangers and Supports for HVAC Piping and Equipment.

1.2 REFERENCES

- .1 American Society of Heating, Refrigeration and Air Conditioning Engineers (ASHRAE)
 - .1 ANSI/ASHRAE/IESNA 90.1-01, SI; Energy Standard for Buildings Except Low-Rise Residential Buildings.
- .2 American Society for Testing and Materials International, (ASTM)
 - .1 ASTM B209M-02, Specification for Aluminum and Aluminum Alloy Sheet and Plate (Metric).
 - .2 ASTM C335-95, Test Method for Steady State Heat Transfer Properties of Horizontal Pipe Insulation.
 - .3 ASTM C411-97, Test Method for Hot-Surface Performance of High-Temperature Thermal Insulation.
 - .4 ASTM C449/C449M-00, Standard Specification for Mineral Fiber-Hydraulic-Setting Thermal Insulating and Finishing Cement.
 - .5 ASTM C547-00, Specification for Mineral Fiber Pipe Insulation.
 - .6 ASTM C553-00, Specification for Mineral Fiber Blanket Thermal Insulation for Commercial and Industrial Applications.
 - .7 ASTM C612-00a, Specification for Mineral Fiber Block and Board Thermal Insulation.
 - .8 ASTM C795-92, Specification for Thermal Insulation for Use with Austenitic Stainless Steel.
 - .9 ASTM C921-92(1998)e1, Standard Specification for Thermal Insulation for Use in Contact with Austenitic Stainless Steel.
- .3 Canadian General Standards Board (CGSB)
 - .1 CGSB 51-GP-52Ma-89, Vapour Barrier, Jacket and Facing Material for Pipe, Duct and Equipment Thermal Insulation.
- .4 Thermal Insulation Association of Canada (TIAC): National Insulation Standards (R1999).
- .5 Underwriters Laboratories of Canada (ULC)
 - .1 CAN/ULC-S102-M88(R2000), Surface Burning Characteristics of Building Materials and Assemblies.
 - .2 CAN/ULC-S701-01, Thermal Insulation Polyotrene, Boards and Pipe Covering.

1.3 DEFINITIONS

- .1 For purposes of this section:

- .1 "CONCEALED" - insulated mechanical services and equipment in suspended ceilings and non-accessible chases and furred-in spaces.
- .2 "EXPOSED" - will mean "not concealed" as defined herein.
- .3 Insulation systems - insulation material, fasteners, jackets, and other accessories.

.2 TIAC Codes:

- .1 CRD: Code Round Ductwork,
- .2 CRF: Code Rectangular Finish.

1.4 SHOP DRAWINGS

- .1 Submit shop drawings in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Submit for approval manufacturer's catalogue literature related to installation, fabrication for duct jointing recommendations.

1.5 MANUFACTURERS' INSTRUCTIONS

- .1 Submit manufacturer's installation instructions in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Installation instructions to include procedures used, and installation standards achieved.

1.6 QUALIFICATIONS

- .1 Installer: specialist in performing work of this section, and have at least 5 years successful experience in this size and type of project, qualified to standards.

1.7 DELIVERY, STORAGE AND HANDLING

- .1 Deliver materials to site in original factory packaging, labelled with manufacturer's name, address.
- .2 Protect from weather and construction traffic.
- .3 Protect against damage from any source.
- .4 Store at temperatures and conditions recommended by manufacturer.

1.8 WASTE MANAGEMENT AND DISPOSAL

- .1 Separate and recycle waste materials in accordance with Section 01 74 11 - Cleaning.

Part 2 Products

2.1 FIRE AND SMOKE RATING

- .1 In accordance with CAN/ULC-S102:
 - .1 Maximum flame spread rating: 25.
 - .2 Maximum smoke developed rating: 50.

2.2 INSULATION

- .1 Mineral fibre: as specified includes glass fibre, rock wool, slag wool.
- .2 Thermal conductivity ("k" factor) not to exceed specified values at mean temperature when tested in accordance with ASTM C335.
- .3 TIAC Code C-1: Rigid mineral fibre board to ASTM C612, with factory applied vapour retarder jacket to CGSB 51-GP-52Ma (as scheduled in PART 3 of this Section).
- .4 TIAC Code C-2: Mineral fibre blanket to ASTM C553 faced with factory applied vapour retarder jacket to CGSB 51-GP-52Ma (as scheduled in PART 3 of this section).
 - .1 Mineral fibre: to ASTM C553.
 - .2 Jacket: to CGSB 51-GP-52Ma.
 - .3 Maximum "k" factor: to ASTM C553.

2.3 JACKETS

- .1 Canvas:
 - .1 220 gm/ cotton, plain weave, treated with dilute fire retardant lagging adhesive to ASTM C921.
- .2 Lagging adhesive: Compatible with insulation.

2.4 ACCESSORIES

- .1 Vapour retarder lap adhesive:
 - .1 Water based, fire retardant type, compatible with insulation.
- .2 Indoor Vapour Retarder Finish:
 - .1 Vinyl emulsion type acrylic, compatible with insulation.
- .3 Insulating Cement: hydraulic setting on mineral wool, to ASTM C449.
- .4 ULC Listed Canvas Jacket:
 - .1 220 gm/ cotton, plain weave, treated with dilute fire retardant lagging adhesive to ASTM C921.
- .5 Outdoor Vapour Retarder Mastic:
 - .1 Vinyl emulsion type acrylic, compatible with insulation.
 - .2 Reinforcing fabric: Fibrous glass, untreated 305 g/.
- .6 Tape: self-adhesive, aluminum, reinforced, 50 mm wide minimum.
- .7 Contact adhesive: quick-setting
- .8 Canvas adhesive: washable.
- .9 Tie wire: 1.5 mm stainless steel.
- .10 Banding: 12 mm wide, 0.5 mm thick stainless steel.

- .11 Facing: 25 mm galvanized steel hexagonal wire mesh stitched on one face of insulation one face of insulation with expanded metal lath on other face.
- .12 Fasteners: 2 mm diameter pins with 35 mm diameter clips, length to suit thickness of insulation.

Part 3 Execution

3.1 PRE-INSTALLATION REQUIREMENTS

- .1 Pressure testing of ductwork systems complete, witnessed and certified.
- .2 Surfaces clean, dry, free from foreign material.

3.2 INSTALLATION

- .1 Install in accordance with TIAC National Standards.
- .2 Apply materials in accordance with manufacturers instructions and as indicated.
- .3 Use two layers with staggered joints when required nominal thickness exceeds 75 mm.
- .4 Maintain uninterrupted continuity and integrity of vapour retarder jacket and finishes.
 - .1 Hangers, supports to be outside vapour retarder jacket.
- .5 Supports, Hangers in accordance with Section 23 05 29 - Hangers and Supports for HVAC Piping and Equipment.
 - .1 Apply high compressive strength insulation where insulation may be compressed by weight of ductwork.
- .6 Fasteners: At 300 mm oc in horizontal and vertical directions, minimum two rows each side.

3.3 DUCTWORK INSULATION SCHEDULE

- .1 Insulation types and thicknesses: Conform to following table:

	<u>TIAC Code</u>	<u>Vapour Retarder</u>	<u>Thickness (mm)</u>
Supply, return and exhaust ducts exposed in space being served			none
Exhaust duct between dampers and louvres	C-2	no	25

3.4 ADDITIONAL REQUIREMENTS

- .1 All ducts penetrating building envelope shall be externally insulated with vapour barrier insulations from roof or wall back for a length of 1.85m or back to damper whichever is greater.

END OF SECTION

Part 1 General

1.1 SUMMARY

.1 Section Includes:

.1 Materials and installation of low-pressure metallic ductwork, joints and accessories.

.2 Related Sections:

.1 Section 01 33 00 - Submittal Procedures.

.2 Section 01 74 11 – Cleaning

1.2 REFERENCES

.1 American Society of Heating, Refrigerating and Air-Conditioning Engineers, Inc. (ASHRAE).

.2 American Society for Testing and Materials International, (ASTM).

.1 ASTM A480/A480M-03c, Standard Specification for General Requirements for Flat-Rolled Stainless and Heat-Resisting Steel Plate, Sheet and Strip.

.2 ASTM A635/A635M-02, Standard Specification for Steel, Sheet and Strip, Heavy-Thickness Coils, Carbon, Hot Rolled.

.3 ASTM A653/A653M-03, Standard Specification for Steel Sheet, Zinc Coated (Galvanized) or Zinc-Iron Alloy Coated (Galvannealed) by the Hot-Dip Process.

.3 National Fire Protection Association (NFPA).

.1 NFPA 90A-02, Standard for the Installation of Air-Conditioning and Ventilating Systems.

.2 NFPA 96-01, Standard for Ventilation Control and Fire Protection of Commercial Cooking Operations.

.4 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA).

.1 SMACNA HVAC Duct Construction Standards - Metal and Flexible, 2nd Edition 1995 and Addendum No. 1, 1997.

.2 SMACNA HVAC Air Duct Leakage Test Manual, 1985, 1st Edition.

.3 IAQ Guideline for Occupied Buildings Under Construction 1995, 1st Edition.

1.3 SUBMITTALS

.1 Submit shop drawings and product data in accordance with Section 01 33 00 - Submittal Procedures.

1.4 DELIVERY, STORAGE AND HANDLING

.1 Protect on site stored or installed absorptive material from moisture damage.

.2 Waste Management and Disposal:

- .1 Separate waste materials for recycling in accordance with Section 01 47 19 - Construction Waste Management and Disposal.

Part 2 Products

2.1 SEAL CLASSIFICATION

- .1 Classification as follows:

Maximum Pressure Pa	SMACNA Seal Class
500	C
250	C
125	C
125	Unsealed

- .2 Seal classification:

- .1 Class A: longitudinal seams, transverse joints, duct wall penetrations and connections made airtight with sealant and tape.
- .2 Class B: longitudinal seams, transverse joints and connections made airtight with sealant.
- .3 Class C: transverse joints and connections made air tight with gaskets sealant. Longitudinal seams unsealed.
- .4 Unsealed seams and joints.

2.2 SEALANT

- .1 Sealant: oil resistant, water borne , polymer type flame resistant duct sealant. Temperature range of minus 30 degrees C to plus 93 degrees C.

2.3 TAPE

- .1 Tape: polyvinyl treated, open weave fiberglass tape, 50 mm wide.

2.4 DUCT LEAKAGE

- .1 In accordance with SMACNA HVAC Air Duct Leakage Test Manual.

2.5 FITTINGS

- .1 Fabrication: to SMACNA.
- .2 Radiused elbows.
 - .1 Rectangular: standard radius short radius with single thickness turning vanes
Centreline radius: 1.5 times width of duct.
 - .2 Round: smooth radius five piece . Centreline radius: 1.5 times diameter.
- .3 Mitred elbows, rectangular:
 - .1 To 400 mm: with single thickness turning vanes.
 - .2 Over 400 mm: with double thickness turning vanes.
- .4 Branches:

- .1 Rectangular main and branch: with radius on branch 1.5 times width of duct 45 degrees entry on branch .
- .2 Round main and branch: enter main duct at 45 degrees with conical connection.
- .3 Provide volume control damper in branch duct near connection to main duct.
- .4 Main duct branches: with splitter damper.
- .5 Transitions:
 - .1 Diverging: 20 degrees maximum included angle.
 - .2 Converging: 30 degrees maximum included angle.
- .6 Offsets:
 - .1 Full short radiused elbows as indicated.
- .7 Obstruction deflectors: maintain full cross-sectional area.
 - .1 Maximum included angles: as for transitions.

2.6 GALVANIZED STEEL

- .1 Lock forming quality: to ASTM A653/A653M, Z90 zinc coating.
- .2 Thickness, fabrication and reinforcement: to SMACNA.
- .3 Joints: to SMACNA.

2.7 HANGERS AND SUPPORTS

- .1 Hangers and Supports: in accordance with Section 23 05 29 - Hangers and Supports for HVAC Piping and Equipment.
 - .1 Strap hangers: of same material as duct but next sheet metal thickness heavier than duct.
 - .1 Maximum size duct supported by strap hanger: 500.
 - .2 Hanger configuration: to ASHRAE and SMACNA.
 - .3 Hangers: black galvanized steel angle with black galvanized steel rods to ASHRAE and SMACNA following table :

Duct Size (mm)	Angle Size (mm)	Rod Size (mm)
up to 750	25 x 25 x 3	6
751 to 1050	40 x 40 x 3	6
1051 to 1500	40 x 40 x 3	10
1501 to 2100	50 x 50 x 3	10
2101 to 2400	50 x 50 x 5	10
2401 and over	50 x 50 x 6	10
 - .4 Upper hanger attachments:
 - .1 For concrete: manufactured concrete inserts.
 - .2 For steel joist: manufactured joist clamp.
 - .3 For steel beams: manufactured beam clamps:

Part 3 Execution

3.1 GENERAL

- .1 Do work in accordance with NFPA 90A NFPA 90B ASHRAE, SMACNA.
- .2 Do not break continuity of insulation vapour barrier with hangers or rods.
 - .1 Insulate strap hangers 100 mm beyond insulated duct Ensure diffuser is fully seated.
- .3 Support risers in accordance with SMACNA as indicated.
- .4 Install breakaway joints in ductwork on sides of fire separation.
- .5 Install proprietary manufactured flanged duct joints in accordance with manufacturer's instructions.
- .6 Manufacture duct in lengths and diameter to accommodate installation of acoustic duct lining.

3.2 HANGERS

- .1 Strap hangers: install in accordance with SMACNA.
- .2 Angle hangers: complete with locking nuts and washers.
- .3 Hanger spacing: in accordance with SMACNA and as follows:

Duct Size (mm)	Spacing (mm)
to 1500	3000
1501 and over	2500

3.3 SEALING AND TAPING

- .1 Apply sealant to outside of joint to manufacturer's recommendations.
- .2 Bed tape in sealant and recoat with minimum of one coat of sealant to manufacturers recommendations.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Materials and installation for duct accessories including flexible connections, access doors, vanes and collars.
- .2 Related Sections:
 - .1 Section 01 33 00 - Submittal Procedures.

1.2 REFERENCES

- .1 Sheet Metal and Air Conditioning Contractors' National Association (SMACNA).
 - .1 SMACNA - HVAC Duct Construction Standards - Metal and Flexible, 95.

1.3 SUBMITTALS

- .1 Submittals in accordance with Section 01 33 00 - Submittal Procedures.
- .2 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and data sheet. Indicate the following:
 - .1 Flexible connections.
 - .2 Duct access doors.
 - .3 Turning vanes.
 - .4 Instrument test ports.
- .3 Instructions: submit manufacturer's installation instructions.

Part 2 Products

2.1 GENERAL

- .1 Manufacture in accordance with SMACNA - HVAC Duct Construction Standards.

2.2 FLEXIBLE CONNECTIONS

- .1 Frame: galvanized sheet metal frame mm thick with fabric clenched by means of double locked seams.
- .2 Material:
 - .1 Fire resistant, self extinguishing, neoprene coated glass fabric, temperature rated at minus 40 degrees C to plus 90 degrees C, density of 1.3 kg/.

2.3 ACCESS DOORS IN DUCTS

- .1 Non-Insulated Ducts: sandwich construction of same material as duct, one sheet metal thickness heavier, minimum 0.6 mm thick complete with sheet metal angle frame.
- .2 Insulated Ducts: sandwich construction of same material as duct, one sheet metal thickness heavier, minimum 0.6 mm thick complete with sheet metal angle frame and 25 mm thick rigid glass fibre insulation.
- .3 Gaskets: neoprene.
- .4 Hardware:
 - .1 Up to 300 x 300 mm: two sash locks.
 - .2 301 to 450 mm: four sash locks.
 - .3 451 to 1000 mm: piano hinge and minimum two sash locks.
 - .4 Doors over 1000 mm: piano hinge and two handles operable from both sides.
 - .5 Hold open devices.

2.4 TURNING VANES

- .1 Factory or shop fabricated single thickness double thickness with trailing edge , to recommendations of SMACNA and as indicated.

2.5 INSTRUMENT TEST

- .1 1.6 mm thick steel zinc plated after manufacture.
- .2 Cam lock handles with neoprene expansion plug and handle chain.
- .3 28 mm minimum inside diameter. Length to suit insulation thickness.
- .4 Neoprene mounting gasket.

2.6 SPIN-IN COLLARS

- .1 Conical galvanized sheet metal spin-in collars with lockable butterfly damper.
- .2 Sheet metal thickness to co-responding round duct standards.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and data sheet.

3.2 INSTALLATION

- .1 Flexible Connections:

- .1 Install in following locations:
 - .1 Inlets and outlets to supply air units and fans.
 - .2 Inlets and outlets of exhaust and return air fans.
 - .3 As indicated.
- .2 Length of connection: 100 mm.
- .3 Minimum distance between metal parts when system in operation: 75 mm.
- .4 Install in accordance with recommendations of SMACNA.
- .5 When fan is running:
 - .1 Ducting on sides of flexible connection to be in alignment.
 - .2 Ensure slack material in flexible connection.
- .2 Access Doors and Viewing Panels:
 - .1 Size:
 - .1 600 x 600 mm for person size entry.
 - .2 600 x 600 mm for servicing entry.
 - .3 300 x 300 mm for viewing.
 - .4 As indicated.
 - .5 Keep doors out of residents rooms.
 - .2 Locations:
 - .1 Fire and smoke dampers.
 - .2 Control dampers.
 - .3 Devices requiring maintenance.
 - .4 Required by code.
 - .5 Reheat coils.
 - .6 Manual dampers and elsewhere as indicated.
 - .7 Variable air volume valves.
- .3 Instrument Test Ports:
 - .1 General:
 - .1 Install in accordance with recommendations of SMACNA and in accordance with manufacturer's instructions.
 - .2 Locate to permit easy manipulation of instruments.
 - .3 Install insulation port extensions as required.
 - .4 Locations:
 - .1 For traverse readings:
 - .1 Ducted inlets to roof and wall exhausters.
 - .2 Inlets and outlets of other fan systems.
 - .3 Main and sub-main ducts.
 - .4 And as indicated.
 - .2 For temperature readings:
 - .1 At outside air intakes.
 - .2 In mixed air applications in locations as approved by Contract Administrator .
 - .3 At inlet and outlet of coils.

- .4 Downstream of junctions of two converging air streams of different temperatures.
- .5 And as indicated.
- .4 Turning vanes:
 - .1 Install in accordance with recommendations of SMACNA and as indicated.

3.3 CLEANING

- .1 Perform cleaning operations as specified in Section and in accordance with manufacturer's recommendations.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 SUMMARY

- .1 Section Includes:
 - .1 Balancing dampers for mechanical forced air ventilation and air conditioning systems.

1.2 REFERENCES

- .1 Sheet Metal and Air Conditioning National Association (SMACNA)
 - .1 SMACNA HVAC Duct Construction Standards, Metal and Flexible-1985.

1.3 SUBMITTALS

- .1 Product Data:
 - .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures . Include product characteristics, performance criteria, and limitations.

1.4 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
- .2 Waste Management and Disposal:
 - .1 Construction Waste Management and Disposal: separate waste materials for recycling in accordance with Section 01 74 11 – Cleaning.

Part 2 Products

2.1 GENERAL

- .1 Manufacture to SMACNA standards.

2.2 SINGLE BLADE DAMPERS

- .1 Fabricate from same material as duct, but one sheet metal thickness heavier. V-groove stiffened.
- .2 Size and configuration to recommendations of SMACNA, except maximum height 100 mm.
- .3 Locking quadrant with shaft extension to accommodate insulation thickness .
- .4 Inside and outside nylon end bearings.
- .5 Channel frame of same material as adjacent duct, complete with angle stop.

2.3 MULTI-BLADED DAMPERS

- .1 Factory manufactured of material compatible with duct.
- .2 Opposed blade: configuration, metal thickness and construction to recommendations of SMACNA.
- .3 Maximum blade height: 100 mm.
- .4 Bearings: pin in bronze bushings self-lubricating nylon.
- .5 Linkage: shaft extension with locking quadrant.
- .6 Channel frame of same material as adjacent duct, complete with angle stop.

Part 3 Execution

3.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

3.2 INSTALLATION

- .1 Install where indicated.
- .2 Install in accordance with recommendations of SMACNA and in accordance with manufacturer's instructions.
- .3 Locate balancing dampers in each branch duct, for supply, return and exhaust systems. Keep dampers out of residence rooms.
- .4 Runouts to registers and diffusers: install single blade damper located as close as possible to main ductwork take offs. Keep dampers out of residence rooms.
- .5 Dampers: vibration free.
- .6 Ensure damper operators are observable and accessible. Keep dampers out of residence rooms.
- .7 Corrections and adjustments conducted by Engineer.

3.3 FIELD QUALITY CONTROL

- .1 Tests:
 - .1 Tests to cover period of not less than days and demonstrate that system is functioning as specified.

3.4 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning .

-
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION

Part 1 General

1.1 SUMMARY

.1 Section Includes:

- .1 Fans, motors, accessories and hardware for commercial use.

1.2 REFERENCES

.1 Air Conditioning and Mechanical Contractors (AMCA)

- .1 AMCA Publication 99-2003, Standards Handbook.
- .2 AMCA 300-1996, Reverberant Room Method for Sound Testing of Fans.
- .3 AMCA 301-1990, Methods for Calculating Fan Sound Ratings from Laboratory Test Data.

.2 American National Standards Institute (ANSI)/American Society of Mechanical Engineers (ASME)

- .1 ANSI/AMCA 210-1999, Laboratory Methods of Testing Fans for Aerodynamic Performance Rating.

.3 Canadian General Standards Board (CGSB)

- .1 CAN/CGSB 1.181-99, Ready-Mixed Organic Zinc-Rich Coating.

1.3 SYSTEM DESCRIPTION

.1 Performance Requirements:

- .1 Catalogued or published ratings for manufactured items: obtained from tests carried out by manufacturer or those ordered by manufacturer from independent testing agency signifying adherence to codes and standards in force.
- .2 Capacity: flow rate, total static pressure, bhp W, efficiency, revolutions per minute, power, model, size, sound power data and as indicated on schedule.
- .3 Fans: statically and dynamically balanced, constructed in conformity with AMCA 99.
- .4 Sound ratings: comply with AMCA 301, tested to AMCA 300. Supply unit with AMCA certified sound rating seal.
- .5 Performance ratings: based on tests performed in accordance with ANSI/AMCA 210. Supply unit with AMCA certified rating seal, except for propeller fans smaller than 300 mm diameter.

1.4 SUBMITTALS

.1 Product Data:

- .1 Submit manufacturer's printed product literature, specifications and datasheet in accordance with Section 01 33 00 - Submittal Procedures. Include product characteristics, performance criteria, and limitations.

.2 Shop Drawings:

- .1 Submit shop drawings and product data in accordance with Section 01 33 00 - Submittal Procedures.
- .3 Provide :
 - .1 Fan performance curves showing point of operation, BHP kW and efficiency.
 - .2 Sound rating data at point of operation.
- .4 Indicate:
 - .1 Motors, sheaves, bearings, shaft details .
 - .2 Minimum performance achievable with variable speed controllers and variable inlet vanes as appropriate.
- .5 Closeout Submittals:
 - .1 Provide operation and maintenance data for incorporation into manual specified in Section 01 77 00 – Closeout Procedures.

1.5 MAINTENANCE

- .1 Extra Materials:
 - .1 Provide maintenance materials in accordance with Section 01 77 00 - Closeout Procedures.
 - .1 Spare parts to include:
 - .1 Matched sets of belts.
 - .2 Furnish list of individual manufacturer's recommended spare parts for equipment, include:
 - .1 Bearings and seals.
 - .2 Addresses of suppliers.
 - .3 List of specialized tools necessary for adjusting, repairing or replacing.

1.6 DELIVERY, STORAGE, AND HANDLING

- .1 Packing, shipping, handling and unloading:
 - .1 Deliver, store and handle in accordance with Section 01 61 00 - Common Product Requirements.
 - .2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Waste Management and Disposal:
 - .1 Construction Waste Management and Disposal: separate waste materials for recycling in accordance with Section 01 74 11 – Cleaning.

1.7 FANS GENERAL

- .1 Motors:
 - .1 In accordance with Section 23 05 13 - Common Motors Requirements for HVAC Equipment supplemented as specified herein.
 - .2 For use with variable speed controllers.
 - .3 Sizes as indicated.
 - .4 Two speed with two windings and speeds of approximately as indicated.

- .5 Two speed with split winding, constant horsepower constant or variable torque and speeds of r/min.
- .2 Accessories and hardware: matched sets of V-belt drives, adjustable motor bases, belt guards, coupling guards fan inlet safety screens as indicated and as specified in Section 23 05 13 - Common Motor Requirements for HVAC Equipment . inlet outlet dampers and vanes and as indicated.
- .3 Factory primed before assembly in colour standard to manufacturer.
- .4 Scroll casing drains: as indicated.
- .5 Bearing lubrication systems plus extension lubrication tubes where bearings are not easily accessible.
- .6 Flexible connections: to Section 23 33 00 - Air Duct Accessories.
- .7 Refer to Fan Schedule on the drawings.

1.8 CENTRIFUGAL FANS

- .1 Fan wheels:
 - .1 Welded steel aluminum construction.
 - .2 Maximum operating speed of centrifugal fans not more than 50 % of first critical speed.
 - .3 Air foil forward curved backward inclined blades, as indicated.
- .2 Bearings: heavy duty split pillow-block flange mounted grease lubricated ball or roller self aligning type with oil retaining, dust excluding seals and a certified minimum rated life of 100,000 hours.
- .3 Shaft seals on exhaust fans:
 - .1 Single disc seals.
- .4 Housings:
 - .1 Volute with inlet cones: fabricated steel for wheels 300 mm or greater, cast iron, steel, aluminum, for smaller wheels, braced, and with welded supports.
 - .2 For horizontally and vertically split housings provide flanges on each section for bolting together, with gaskets of non-oxidizing non-flammable material.
 - .3 Provide bolted latched airtight access doors with handles.

Part 2 Execution

2.1 MANUFACTURER'S INSTRUCTIONS

- .1 Compliance: comply with manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheet.

2.2 FAN INSTALLATION

- .1 Install fans as indicated, complete with resilient mountings specified in Section 23 05 48 - Vibration Controls for HVAC Piping and Equipment, flexible electrical leads and flexible connections in accordance with Section 23 33 00 - Air Duct Accessories.
- .2 Provide sheaves and belts required for final air balance.
- .3 Bearings and extension tubes to be easily accessible.
- .4 Access doors and access panels to be easily accessible.

2.3 ANCHOR BOLTS AND TEMPLATES

- .1 Size anchor bolts to withstand acceleration and velocity forces as specified.

2.4 CLEANING

- .1 Proceed in accordance with Section 01 74 11 - Cleaning.
- .2 Upon completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

END OF SECTION