

	Lamacoid Schedule		Document Code	113368-0000-47EL-0003
			Revision	0
Client City of Winnipeg				
Project Marion Wastewater Lift Station				
Package / Area Electrical and Automation				
Prepared By	Name	Signature	Date	
	B. Cleven		2010-09-30	
Checked By	Name	Signature	Date	
	C. Reimer		2010-09-30	
Approved By	Name	Signature	Date	
	C. Reimer		2010-09-30	
Notes / Comments				

Revisions					
Rev	Description	Date	By	Checked	Approved
0	Issued for Tender	2010-09-30	B. Cleven	C. Reimer	C. Reimer

ID No.	Line 1	Line 2	Size (mm)	Note
1	CB-PNL-L1	WASTEWATER LIFT STATION	5	
2	CB-HCE-L1	ELECTRIC HEATING COIL	3	
3	CB-MS-SF-L1	SUPPLY FAN SF-L1 STARTER	3	
4	CB-VFD-P-L1	P-L1 VFD	3	
5	CB-VFD-P-L2	P-L2 VFD	3	
6	CB-XFMR-L10	XFMR-L10	3	
7	HCE-L1		5	
8	L100-LIT-A		5	
9	L101-HS-1	P-L1 E-STOP	5	
10	L101-HS-2	P-L1 E-STOP	5	
11	L102-HS-1	P-L2 E-STOP	5	
12	L102-HS-2	P-L2 E-STOP	5	
13	L105-LSH		5	
14	L110-FE		5	
15	L110-FIT		5	
16	L601-FV-1		5	
17	L601-FV-2		5	
18	L601-FV-3		5	
19	L602-TT		5	
20	L603-FSL		5	
21	L604-TT		5	
22	MAIN	FLOOR	3	6
23	MCS-PNL-L1	MAIN DISCONNECT	3	
24	MOTOR AND	PUMP ROOMS	3	6
25	MS-SF-L1	SF-L1 SUPPLY FAN	5	
26	MS-SF-L2	SF-L2 SUPPLY FAN	5	
27	MTR-P-L1		5	
28	MTR-P-L2		5	
29	P-L1		5	
30	P-L2		5	
31	PNL-L1		5	
32	PNL-L10	120/240V	5	
33	SF-L1	SUPPLY FAN	5	
34	SF-L2	SUPPLY FAN	5	
35	INLET VALVE	CHAMBER	3	6
36	VFD-P-L1		5	
37	VFD-P-L2		5	
38	XFMR-L10	15 kVA 600-120/240V	5	

Notes:

1. This schedule includes lamacoids for electrical and automation equipment only. Identification requirements for other divisions are not shown.
2. This schedule is provided for reference only and the potential omission of any lamacoids on this schedule does not reduce the contractor's responsibility in providing lamacoids as specified.
3. Cable tags are not shown. Lighting and receptacle labels are not shown.
4. Lamacoids required for control panels and junction boxes specified to be manufactured by a panel shop are not shown.
5. Lamacoids sizes in accordance with specification section 26 05 01 - Common Work Results.
6. Lamacoid to be applied above light switch on main floor.