

## **1.0 COORDINATION**

- 1.1 Coordinate all Work in each area and Work on which subsequent Work depends to facilitate mutual progress, and to prevent conflict between part of the Work.
- 1.2 Ensure that each Section makes known, for the information of the Contractor and other Sections, the environmental and surface conditions required for the execution of this Work: and that each Section makes known the sequence of others' Work required for installation of its Work.
- 1.3 Ensure that each Section before commencing Work, knows requirements for subsequent Work and that each Section is assisted in the execution of its preparatory Work by Sections whose work depends upon it.
- 1.4 Ensure that setting drawings, templates and all other information necessary for the location and installation of materials, holes, sleeves, inserts, anchors, accessories, fastenings, connections, and access panels are provided by each Section whose Work requires cooperative location and installation by other Sections and that such information is communicated to the applicable installer.
- 1.5 Deliver materials supplied by one Section to be installed by another well before the installation begins.
- 1.6 Remove Work installed in error which is unsatisfactory for subsequent work.

## **2.0 CUTTING AND PATCHING**

- 2.1 Before cutting, drilling, or sleeving structural load bearing elements, obtain approval of location and methods.
- 2.2 Do not endanger Work or property by cutting, digging, or similar activities. No Section shall cut or alter Work of another Section who has installed it unless approved by that Section.
- 2.3 Cut and drill with true smooth edge to minimum suitable tolerances.
- 2.4 Replace, and otherwise make good, damaged Work or bank equipment.

- 2.5 This Section shall be responsible for all cutting and patching in addition to that specified for mechanical and electrical Work.
- 2.6 Patching or replacement of damaged work shall be supplied and installed by the Sub-Contractor under whose Work it was originally executed, and at the expense of the Subcontractor who caused the damage.
- 2.7 Make patches invisible in final assembly.

END OF SECTION