

1.0 FIRES

1.1 Fires and burning of rubbish on Site is not permitted.

2.0 DISPOSAL OF WASTES

2.1 Burying of rubbish and waste materials on Site is not permitted.

2.2 Disposal of waste or volatile materials, such as mineral spirits oil or paint thinner into storm or sanitary sewers are prohibited.

3.0 POLLUTION CONTROL

3.1 Prevent extraneous materials from contaminating air beyond application areas, by providing temporary enclosures.

3.2 Cover or wet down dry materials and rubbish to prevent blowing dust and debris.

4.0 DRAINAGE

4.1 Provide temporary drainage and pumping as necessary to keep excavations and Site free from water.

4.2 Dispose of water containing silt in suspension in accordance with local authority requirements.

4.3 Take full responsibility for maintenance of existing drainage above ground and underground, adjacent to the Work or affected by the Work.

4.4 Before commencing any Work likely to affect the drainage of water from the existing building or Site, provide necessary alternative drainage systems to ensure that water will be conducted to alternative outlets. Do not block or impeded any drain, roof outlet or rainwater leader until such safety precautions have been made.

5.0 NOISE

5.1 Comply with regulations and requirements of Authorities having jurisdiction.

END OF SECTION