



## 379-2011 ADDENDUM 1

### ELEVATOR MODERNIZATION – CITY HALL ADMINISTRATION BUILDING – 510 MAIN STREET

#### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE BID  
OPPORTUNITY**

ISSUED: July 26, 2011  
BY: Stan Russell  
TELEPHONE NO. (204) 794-7311

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID OPPORTUNITY AND SHALL  
FORM A PART OF THE CONTRACT  
DOCUMENTS**

Template Version: A20070419

---

**Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.**

---

#### **PART B – BIDDING PROCEDURES**

Revise: B2.1 to read:

B2.1 The Submission Deadline is 4:00 p.m. Winnipeg time, **August 5, 2011**.

#### **PART E – SPECIFICATIONS**

Revise specification reference to “mirror finish brass” where ever it appears in the Bid Opportunity document and drawings to read “Alloy 280, number 8 finish, lacquered”.

Revise: E52.1 to read:

E52.1 Clad the existing hoistway door panels and transoms (including light soffit) at the Main and 2nd floors (a total of 4 entrances) in mirror finish brass. Chemically etch the door panels with the City of Winnipeg Coat of Arms, approximately 24” wide by 24” high. Artwork in electronic format will be supplied by the City. Centre the Coat of Arms on the centre of the door opening. Obtain approval of the etching shop drawing before proceeding with the etching process

Delete: E57.4

Add: E57.11

E57.11 Remove and dispose of the existing wood finish on the front returns, side walls and rear wall of the cabs.

Add: E57.12

E57.12 Provide raised panels on all four walls. The rear wall to have a single raised panel running from side to side and above the handrail, finished and self-edged in plastic laminate of the Owners choice of colour and pattern. On this raised panel, mount a bronze-tinted mirror consisting of tempered or laminated glass mounted in a frame of mirror finish brass to match the other brass in the car.

Add: E57.13

E57.13 Provide similar raised plastic laminate panels below the handrail on the rear wall, above the handrails on the two side walls and below the handrails on the two side walls. Line of the panels to run from the top of the car door frame to 4 inches above the car floor.

Add: E57.14

E57.14 Provide a similar raised plastic laminate panel on each front return, suitable for mounting the new car stations. Provide a single panel on each front return running vertically from the line of the top of the wall panels to the bottom of the wall panels.

Add: E57.15

E57.15 Arrange the rear and side wall panels to be removable from inside the car.

Add: E57.16

E57.16 Provide reveals between panels on all four sides, including the radiused corners, and behind the handrail on three sides of contrasting colour plastic laminate. Provide matching reveals for the front return raised panels.

Revise: E108.1 to read:

E108.1 Clad the existing hoistway front door panels and transoms (including light soffit) at the Main and 2nd floors (a total of 2 entrance doors) in mirror finish brass. Chemically etch the door panels with the City of Winnipeg Coat of Arms, approximately 24" wide by 24" high. Artwork in electronic format will be supplied by the City. Centre the Coat of Arms on the centre of the door opening. Obtain approval of the etching shop drawing before proceeding with the etching process.

Revise: E113.6

E113.6 Insert blocking into the space currently occupied by the Car Position Indicator above the car doors and skin the existing front and rear headers and car door jambs in new mirror finish brass. **Provide new Alloy 280, number 8 finish, lacquered strips to the front and rear car door jambs, similar to the existing.**