



Supply & Install New Park Signage (By Others)

Existing Spring Toy

Supply & Install New Metal Slat W.R.

Supply & Install New 2-Tier Timber Edging w/ Pedra Cap

Supply & Install New Accessible Picnic Table

Supply & Install New 2-Bay, 2 Baby, 2 Belt Swingset

Proposed Play Area (304 SM)

Supply & Install Soil & Sod (TYP.)

Supply & Install New Bench in Accessibility Node

Existing Tree (TYP.)

F.H.

C.B.

L.S.

BACK LANE

Supply & Install Wood Fibre Safety Surfacing including subsurface drainage

Supply & Install New Granular Path

0 2 5 8 11 m

Supply & Install New Bench

Supply & Install New Sandbox

5'-10 5/8"m

CONTRACTOR TO CONFIRM ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION. LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.



THE CITY OF WINNIPEG
 Planning, Property and Development Department
 Planning and Land Use Division
 Unit 15 - 30 Fort Street, Winnipeg, MB, (R3C 4X5)

DESIGNED BY	HF	CHECKED BY	
DRAWN BY	HF	APPROVED BY	
HORIZ. SCALE	1:200		
VERT. SCALE			
DATE	DEC/10		

MANAGER, PARK AND OPEN SPACES	DATE
MANAGER, PLANNING AND LAND USE DIVISION	DATE

DRAWING TITLE BEAUMONT BAY PARK PLAYGROUND REDEVELOPMENT PROPOSED PLAN
SITE ADDRESS 21 BEAUMONT BAY

DRAWING NO. B.76-D
BID OPPORTUNITY NO. 41-2011