ARCHIBALD ST.

CUSSON ST.
300 WWS
150 WM

COTE ST.

MATCH EXIST.
CONC. APRON

MATCH EXIST.
CONC. APRON

100 GAS
100 GAS
250 LDS

A

MTS

SCALE
0   10   20   30   40   50 METRES

PROPERTY
LINE

PROPERTY
LINE

VARIES | VARIES
5.00

100 BASE COURSE
200 RECYCLED CONCRETE
SEPARATION
GEOTEXTILE

LANE ℄

BOULEVARD
GRADING
(TYP.)

EXIST. GROUND

A   LIMESTONE SECTION WITH RECYCLED CONCRETE
    SCALE 1:25

CONSTRUCTION NOTES:

1. LANES ARE TO BE GRADED AS DIRECTED BY THE CONTRACT ADMINISTRATOR
2. CONFIRM LOCATION OF ALL EXISTING UTILITIES PRIOR TO CONSTRUCTION.
3. NOTIFY ALL RESIDENTS AND BUSINESSES 24 HOURS IN ADVANCE OF ANY DISRUPTION OF UTILITY SERVICE.
4. ENSURE ALL THE UPPER EDGES OF THE GEOTEXTILE AND ENVIROGRID HAVE A MINIMUM OF 100mm BURIED DEPTH OVER ALL PORTIONS.
5. CONTRACTOR TO TAKE PRECAUTIONARY STEPS TO AVOID DAMAGE FROM CONSTRUCTION ACTIVITIES TO TREES
6. LOCATION OF EXISTING SERVICES AND UTILITIES TO BE CONFIRMED IN THE FIELD BY THE CONTRACTOR

METRIC

WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

WARNING

IF POWER EQUIPMENT OR EXPLOSIVES ARE TO BE USED FOR EXCAVATION ON THIS PROJECT THE CONTRACTOR MUST:

1. NOTIFY THE GAS COMPANY OF THE PROPOSED LOCATION OF EXCAVATION.
2. TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY INSTALLATIONS SEE PROVINCIAL REGULATION 210/72 FOR DETAILS.
3. OBTAIN EXCAVATION PERMITS PRIOR TO CONSTRUCTION.

LEGEND–PLAN EXISTING		LEGEND–PLAN PROPOSED		LEGEND–PROFILE EXISTING	LEGEND–PROFILE PROPOSED
150 WM	WATERMAIN	150 WM	HYDRO	HYDRO	150 mm W.M.
	HYDRANT		M.T.S.	MTS	HYDRANT
	VALVE		CONCRETE		VALVE
300 LDS	LAND DRAINAGE SEWER	300 LDS	ASPHALT	300 mm L.D.S.	LAND DRAINAGE SEWER
250 WWS	WASTE WATER SEWER	250 WWS	PLANING	250 mm W.W.S.	WASTE WATER SEWER
	MANHOLE		SIDEWALK		℄ PROFILE
	CATCH BASIN		PAVING STONES		NORTH/WEST GUTTER
	CURB INLET		PARTIAL DEPTH REPAIR		SOUTH/EAST GUTTER
	JUNCTIONS		PROPERTY LINE		NORTH/WEST T/LANE
	CULVERT		SURVEY BAR		SOUTH/EAST T/LANE
100 GAS	GAS	100 GAS	CURB RAMP		

UNDERGROUND STRUCTURES

SUPV. U/G STRUCTURES   DATE
COMMITTEE

NOTE:
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE, BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

B.M. ELEV.					DESIGNED BY	BPN
					DRAWN BY	PMW
					CHECKED BY	DBW
					APPROVED BY	DPK
					HOR. SCALE	1:125
1	ISSUED FOR TENDER	2011/09/01	BPN		VERTICAL	—
NO.	REVISIONS	DATE	BY		DATE	2011 / 09 / 01

DILLON CONSULTING

ENGINEER'S SEAL
PROVINCE OF MANITOBA
ORIGINAL STAMPED BY
W.P. NAIRN
2011/09/01
Member
34277
REGISTERED PROFESSIONAL ENGINEER

RELEASED FOR CONSTRUCTION

DATE

CONSULTANT PROJECT NUMBER
11-5329

Winnipeg
THE CITY OF WINNIPEG
PUBLIC WORKS DEPARTMENT

2011 GRANULAR LANE IMPROVEMENT PROGRAM

LANE G

CITY DRAWING NUMBER

SHEET 7 OF 14

CONSULTANT DRAWING NUMBER

G:\CAD\115329\Contract\Current\Paving_&_Grading.dwg