



787-2011 ADDENDUM 2

REQUEST FOR PROPOSAL FOR PROFESSIONAL CONSULTING SERVICES FOR THE MACLEAN PUMPING STATION MCC REPLACEMENT DETAILED DESIGN AND CONTRACT ADMINISTRATION

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
REQUEST FOR PROPOSAL**

ISSUED: October 3, 2011
BY: Linda McCusker, P.Eng.
TELEPHONE NO. (204) 986-6669

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE REQUEST FOR PROPOSAL AND
SHALL FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: Ar20070420

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Request for Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph ^ of Form A: Proposal may render your Proposal non-responsive.

PART D – SUPPLEMENTAL CONDITIONS

- Add: D4.3 (k) Rerouting, if required, of the cabling and cable trays. The current cable trays are quite full and the area where they are currently run is congested with ducting and piping. In addition, asbestos may be present in some of the piping insulation. The City will provide a document detailing the location of the asbestos containing materials within the facility. The Consultant must review the document and identify in a detailed document any areas where asbestos remediation is required. The City will then abate the asbestos prior to the commencement of construction.
- Add: D4.3 (l) Replacement of the cables dependant on their condition. Note that many of the cables are of 1960's vintage and will require replacement.
- Add: D4.3 (m) Lengthening of the cables as required. Lengthening will only be permitted based on specific approval from the City.
- Add: D4.3 (n) Replication of any existing connections to the PLC Monitoring points. Some of the existing starters have connections to the existing Station PLC. These IO connections must be replicated. Include in the design additional monitoring and control points to allow to future monitoring and control.