



289-2013 ADDENDUM 1

CITY OF WINNIPEG 2013 LOCAL STREET PACKAGE: GARWOOD AVENUE, LAIDLAW BOULEVARD, WAVELL AVENUE AND VARIOUS OTHER LOCATIONS

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: May 14, 2013
BY: Ron Bruce, P.Eng.
TELEPHONE NO. (204) 977-8370

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20070419

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 289-2013 Bid Submission with 289-2013 Addendum 1- Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): Revise Item No. B.18 i) a)

Revise Item No. C.21

PART E – SPECIFICATIONS

Revise: E19.1 to read:

The Work shall consist of the supply of all supervision, labour, materials (except as indicated in **E19.12**) insurance, tools, backfill and equipment (and their maintenance), transportation, fuel, oil, meals and lodging, mobilization and de-mobilization, and warranty of workmanship as required to remove existing street light poles and install new street light poles and associated underground cables/conduits, all in accordance with the requirements specified in the tender documents.

Revise: E19.18.2 to read:

Rocky Road Recycling, 4154 McGillvary Blvd, Winnipeg, Manitoba:
concrete (precast, poured in place)

Revise: E19.39.2 to read:

The Contractor shall determine the location of all buried obstructions and shall notify the appropriate authorities and obtain all necessary permits prior to excavation, trenching and directional drilling near or across such obstructions. All buried obstructions where the buried cable route crosses gas, water, sewer, telephone and hydro lines, etc., shall be hand exposed by the Contractor, including the use of Pressurized Water/Vacuum Equipment (PW/VE) where necessary. Should any damage occur to such lines during the course of the Work, the Contractor shall be responsible for the damage and the costs of repairs to buried obstructions caused by its operations and shall fully indemnify the City of Winnipeg and Manitoba Hydro from and against all claims arising out of such damage. The requirements of the Directional Boring Guidelines included in **Appendix D** shall be followed when crossing natural gas pipelines and electrical cables by the directional boring method.

Add: E20: Refer to Appendix E for Manitoba Hydro (Gas) for parameters for working in proximity to all natural gas mains

Add: Appendix E – Manitoba Hydro (Gas) Requirements

Page numbering on some forms may be changed as a result.