


APEGIN Certificate of Authorization KGS Group

No. 245

DATE BY

DATE

13/08/30



CHECKED PAT

DATE 14/06/16

CONSTRUCTION: K. ZUREK

APPROVED

**METRIC** WHOLE NUMBERS INDICATE MILLIMETRES DECIMALIZED NUMBERS INDICATE METRES

## WARNING

1. NOTIFY THE GAS COMPANY OF THE PROPOSED LOCATION OF EXCAVATION. 2. TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY INSTALLATIONS.

**GENERAL NOTES:** 

1. ALL WORKS TO BE IN ACCORDANCE WITH THE LATEST REVISION OF THE CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS.

REQUIRED IN ACCORDANCE WITH THE LATEST REVISION OF THE "CONSTRUCTION SAFETY ACT" OF THE PROVINCE OF MANITOBA DEPARTMENT OF LABOR AND IN ACCORDANCE WITH THE PROVINCE OF MANITOBA 'W210 WORKPLACE SAFETY & HEALTH ACT" AND "GUIDELINES FOR EXCAVATION WORK". IF SHORING REQUIRED, CONTRACTOR TO SUPPLY STAMPED ENGINEERING SHORING DESIGN

BY ENGINEER REGISTERED IN THE PROVINCE OF MANITOBA.

3. ALL ELEVATIONS SHOWN ON DRAWINGS TAKEN FROM CITY OF

4. ADDITIONAL ELEVATIONS SHOWN ON AUBREY FPS ISOMETRIC INCLUDED IN APPENDIX B OF TENDER DOCUMENTS.

5. FORCEMAIN SHALL BE PRESSURE TESTED IN ACCORDANCE WITH

6. PROTECT WATER SERVICE FROM FREEZING DURING CONSTRUCTION.

8. BACKFILL EXCAVATION WITH CEMENT STABILIZED FILL. PROVIDE SAND BEDDING AROUND WATER SERVICES AND VENT PIPE.

11. CONTRACTOR TO PROVIDE TEMPORARY BY-PASS PUMPING AS PER

TEMPORARY PUMPING PLAN TO BE APPROVED BY THE

CHAMBER AND WEIR. DISCHARGE FLOW TO MH-B.

LOW MH RIM ELEV. = 230.43± (LOCATED AT WOLSLEY &

ALLOWABLE SHUT DOWN TIME: 6 HOURS (APPROXIMATE).

CRITICAL BASEMENT FLOODING EL. = 227.381

PROTECT TEMPORARY PUMPING FROM FREEZING.

CONTRACT ADMINISTRATOR PRIOR TO COMMENCEMENT OF

PUMPS MAY BE INSTALLED IN MH—A OR UPSTREAM OF GATE

7. RESTORE SITE TO PRE-CONSTRUCTION CONDITIONS.

9. NO STOCKPILING OF EXCAVATED MATERIAL ON SITE.

10. PROTECT EXISTING TREES DURING CONSTRUCTION.

WINNIPEG RECORD DRAWINGS.

FORCEMAIN REPLACEMENT NOTES:

AWWA STANDARDS.

TEMPORARY PUMPING:

THE SPECIFICATIONS.

CONSTRUCTION.

2. CONTRACTOR SHALL PROVIDE TEMPORARY SHORING WHERE

3. SEE PROVINCIAL REGULATION 210/72 FOR DETAILS.

PROPERTY LIMITS DELINEATION

DELINEATION OF PROPERTY LIMITS AS SHOWN ON THIS DWG DOES NOT REPRESENT A "LEGAL SURVEY". KGS GROUP MAKES NO REPRESENTATION OR WARRANTY AS TO THE ACCURACY OF PROPERTY LIMITS DELINEATED ON THIS DWG, NOR ON THE DIMENSIONAL ACCURACY OF DWG FEATURES RELATIVE TO THOSE PROPERTY LIMITS.

300 LDS LAND DRAINAGE SEWER 300 LDS 250 WWS WASTE WATER SEWER TEST HOLE 250 WWS **④** GAS **GUY WIRE** ----LIGHT STANDARD HYDRO •---\_\_\_\_\_ \_\_\_\_\_ BACK OF CURB M.T.S. WATERMAIN CONCRETE 150 WM <u> 150 WM</u> HYDRANT +

PROPOSED

**EXISTING** 

LEGEND-PLAN

UNDERGROUND STRUCTURES SUPV. U/G STRUCTURES DATE COMMITTÉE ASPHALT SIDEWALK LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION PROPERTY LINE AVAILABLE BUT NO GUARANTEE IS GIVEN -THAT ALL EXISTING UTILITIES ARE SHOWN OR SURVEY BAR THAT THE GIVEN LOCATIONS ARE EXACT. GEODETIC BENCHMARK CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE (32.231 ELEVATION OBTAINED FROM THE INDIVIDUAL UTILITIES


LEGEND-PLAN

PROPOSED

SCALE: 1:150

LOCATION APPROVED B.M. **KGS** GROUP CONSULTING ENGINEERS DESIGNED DRAWN GEL HOR. SCALE: AS NOTED VERTICAL: N/A 14/06/16 ISSUED FOR CONSTRUCTION BEFORE PROCEEDING WITH CONSTRUCTION.

NO. REVISIONS



C01



## THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT

AUBREY WASTEWATER PUMPING STATION UPGRADE SHEET 1016 PALMERSTON AVE.

**MUNICIPAL** FORCEMAIN REPLACEMENT PLAN

CITY DRAWING NUMBER

1-0116L-C0001-001

0

 $\nabla$ 

**EXISTING** 

VALVE

MANHOLE

CATCH BASIN

CURB INLET

LEGEND-PLAN

POLES T-MTS

⊗

 $\blacksquare$ 

PROPOSED

 $\triangle$ 

231.334

**EXISTING**