

SUPPLY: 208V 3Ø 4W				NAMF	PLA	 Г F :			T	LOCATION: ELECTRICAL ROOM MCC	
MAINS AMPACITY: 100										MOUNTING: ■ SURFACE □ FLUSH	
INCOMING: ☐ BREAKER ■ LUGS										MANUFACTURER:	
MAIN BREAKER REQUIRED: ☐ YES ■ NO		PΑ	NEL	•	PNL	.–L7	2 '			MODEL NO:	
MAIN BREAKER AMPS:										BREAKER: □ PLUG-IN ■ BOLT-ON	
BUS MATERIAL: ■ COPPER ALUMINUM										SPD: ■ YES □ NO	
BUS AND BREAKER RATING: 10kA										SERVICE ENTRANCE RATED: YES	■ NO
REV CCT	VA	Р	BKR	Α	ВС	BKF	R P	VA	4		CCT RE\
0 1 SCADA CONTROL PANEL	1000	1	20	•		20	1	600		PUMP ROOM RECEPTACLES	2 0
0 3 DAMPER MOTORS FV-L611-1, FV-L611-2,AND FV-L611-3	250	1	20		•	20	1	250	0	SUMP PUMP RECEPTACLE	4 0
0 5 INTERIOR & EXTERIOR LIGHTING AND EMERGENCY LIGHTING	960	1	20		•	20	1	600	0	MOTOR ROOM RECEPTACLES	6 0
0 7 MAGNETIC FLOW TRANSMITTER FIT-L011	20	1	15	•		20	1	600	0	ELECTRICAL ROOM AND LOWER LEVEL RECEPTACLES	8 0
0 9 MAGNETIC FLOW TRANSMITTER FIT-L021	20	1	15		•	20	1	_		SPARE	10 0
0 11 MAGNETIC FLOW TRANSMITTER FIT-L031	20	1	15		•	20	1			SPARE	12 0
0 13 HYDROVISION TRANSMITTER	20	1	15	•		_	T -				14
15					•	_	_				16
17	_	_	_		•		_	_			18
	LOA			LOA			LOA				
	2,2	240			520		5	20			

LUMINAIRE SCHEDULE							
TYPE	DESCRIPTION	VOLTAGE	LAMPS	DESIGN BASICS			
A	FLUORESCENT FIXTURE, WET LOCATION RATED, STEEL REINFORCED POLYCARBONATE HOUSING, GASKETED POLYCARBONATE LENS, HOUSING AND LENS TO BE UV STABILIZED, METAL REFLECTOR, STAINLESS STEEL MOUNTING HARDWARE, C/W KNOCKOUTS AND PROGRAM START BALLAST	120V	2-32W T8 4100°K	AIMLITE - VP4-T8-32-AC-120-RPD BEGHELLI - BS100T8-2-HT-232W-120V			
В	COMPACT FLUORESCENT FIXTURE, WET LOCATION RATED, GRAY FIBREGLASS HOUSING, GASKETED CLEAR GLASS GLOBE, CEILING MOUNT WITH 3/4 INCH THREADED HUBS, HIGH POWER FACTOR ENCAPSULATED MAGNETIC BALLAST	120V	1-18W GX24Q-2 4100°K	CANLET - 68-01-F-C-F-11-0G-09			
w	WALL MOUNTED, VANDAL RESISTANT, WET LOCATION RATED, 24 INCH LENGTH, LED, EXTRUDED ALUMINUM HOUSING AND LENS FRAME, GASKETED UV STABILIZED POLYCARBONATE LENS, ALL MOUNTING AND LENS FRAME SCREWS TO BE CAPTIVE STAINLESS STEEL SLOTTED TYPE, L70 PROJECTED LIFE OF 75,000 HOURS, 350mA DRIVE CURRENT, LIFETIME WARRANTY ON FIXTURE DAMAGED DUE TO VANDALISM	120V	LED 3500°K	LUMINAIRE LIGHTING - AEL24-11WLED-120-DP-WOP-PC-ST/SC			

EMERGENCY LIGHTING EQUIPMENT SCHEDULE							
TYPE	DESCRIPTION	VOLTAGE	LAMPS	DESIGN BASICS			
E1	EMERGENCY BATTERY UNIT, NON-METALLIC NEMA 4X HOUSING, SOLID STATE CHARGER, TEST SWITCH, LED INDICATING LIGHTS, MINIMUM 90W CAPACITY LONG LIFE BATTERY, 12VDC OUTPUT, AUTO TEST AND SELF DIAGNOSTICS, 5 MINUTE TIME DELAY, CABTIRE WITH TWIST-LOCK PLUG, CSA C22.2 NO. 141 CERTIFIED, C/W 2 LIGHTING HEADS	120V 12VDC	2-LED 5W MR16	AIMLITE - EBWP12100-2MW-5.7L-GRY-ATD-LNC-TDL-TLP120 BEGHELLI - BRV-12-90-LEDMR16-AT			
E2	REMOTE EMERGENCY LIGHTING HEAD, SURFACE MOUNT, WET LOCATION RATED, NON-METALLIC NEMA 4X HOUSING, GASKETED, DOUBLE HEAD, ADJUSTABLE AIM POSITION	12VDC	2-LED 5W MR16	AIMLITE - RMWP2-12-5.7L/GRY BEGHELLI - WR2-12V-5WLED			







E16



THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT

AUBREY WASTEWATER PUMPING STATION UPGRADE SHEET X OF X 1016 PALMERSTON AVE ELECTRICAL

SCHEDULES

CITY DRAWING NUMBER

1-0116L-E0013-001