



788-2014 ADDENDUM 1

POINTE HEBERT PARK UPGRADES – PHASE I

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: August 27, 2014
BY: Matthew Derksen
TELEPHONE NO. (204) 956-0396

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20131129

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph ^ of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 788-2014 Bid Submission with 788-2014 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): Add Item No. 33.

Page numbering on some forms may be changed as a result.

PART E – SPECIFICATIONS

Delete: E21.1(c) Remove and dispose of dead trees

Add: E31 Temporary Gravel Approach

E31.1 Work of this section comprises the furnishing of all labour, equipment and materials incidental and required to complete the temporary gravel approach to existing parking lot and related Work as shown on the drawings and as hereinafter specified. The Work includes, but not necessarily confined to, the following:

- (a) Supply and installation of a compacted gravel approach with CSP culvert to an existing parking lot prior to construction of roadwork in Whittier Park.
- (b) Removal of compacted gravel approach and CSP culvert following completion of roadwork in Whittier Park.

Materials

All materials as per CW 3110

Work Included

E31.2 Prior to roadwork in Whittier Park:

- (a) Install compacted gravel approach with culvert at bottom of existing swale as shown on the Drawings to maintain existing drainage pattern and provide smooth, level surface over existing swale to parking lot.

E31.3 Following roadwork completion in Whittier Park:

- (a) Remove culvert and gravel approach.
- (b) Repair damage to sod caused by installation and/or removal of gravel approach and ensure drainage pattern is maintained.

Measurement and payment

E31.4 Temporary Gravel Approach will be paid for at the contract lump sum price for “Supply, install and remove compacted gravel approach to parking lot” as specified herein, which price shall be payment in full for performing all operations herein and all other items incidental to the Work included in this Specification

DRAWINGS

Add: 788-2014 _Drawing_ L1.2-R1