

| INFORMATION AVAILABLE BUT NO | |
|---------------------------------------|--|
| GUARANTEE IS GIVEN THAT ALL EXISTING | |
| UTILITIES ARE SHOWN OR THAT THE GIVEN | |
| LOCATIONS ARE EXACT. CONFIRMATION OF | |
| EXISTENCE AND EXACT LOCATION OF ALL | |
| SERVICES MUST BE OBTAINED FROM THE | |
| | |

| s | MORRISON HERSHFIELD | | | | | | | |
|-------------|---------------------------|----------------|----------|----------------|-----|----------|-------------------------|-----|
| D. – APE | SAL | CHECKED BY | DAN | DESIGNED BY | | | | |
| MA | BE | APPROVED BY | DML | DRAWN BY | | | | |
| | RELEASED FOR CONSTRUCTION | | AS SHOWN | HOR. SCALE | DAN | 15/03/31 | ISSUED FOR TENDER | С |
| CONSU | | | AS SHOWN | VERT. SCALE | DAN | 15/03/13 | ISSUED FOR 99% PROGRESS | В |
| | | | AS SHOWN | VERT. SCALE | DAN | 15/02/27 | ISSUED FOR 50% PROGRESS | А |
| W14 | | DATE | 15/02/27 | DATE | BY | YY/MM/DD | REVISIONS | No. |
| | | | | | | | | |

JLTANT DRAWING No. 40009-PL-01.dwg

SITE NOTES:

- SITE ACCESS SHALL BE VIA COLE AVENUE (PIER #3) OR COSMO PLACE (PIER #8).
- THE CONTRACTOR'S FORCES SHALL AT NO TIME ENTER CP RAIL PROPERTY OR INHIBIT ACCESS TO CP RAIL PROPERTY. THE WEST PROPERTY LIMIT IS PHYSICALLY DELINEATED BY A CHAIN LINK FENCE. THE EAST PROPERTY LIMIT IS NOT PHYSICALLY DELINEATED.
- LAYDOWN AREAS SHALL BE WITHIN THE FOLLOWING BOUNDARIES:
- O PIER #3 WORK SITE:
- EAST OF PIER #4
- SOUTH OF THE NORTH EDGE OF THE EXISTING BRIDGE
- NORTH OF COLE AVENUE
- WEST OF THE EAST ABUTMENT
- O PIER #8 WORK SITE:
- MINIMUM 5 m EAST OF THE EXISTING SIDEWALK
- MAXIMUM 25 m NORTH OF THE BRIDGE DECK LIMITS
- NORTH AND WEST OF THE CP RAIL ROW
- PEDESTRIAN ACCESS TO THE SIDEWALK BETWEEN PIER #9 AND PIER #10 SHALL BE MAINTAINED AT ALL TIMES.

CHAIN LINK FENCE NOTES:

- CHAIN LINK FENCE AND GATES SHALL CONFORM TO CITY OF WINNIPEG STANDARD SPECIFICATION CW 3550-R3.
- ALL POSTS SHALL BE FOUNDED ON 300 mm DIAMETER CONCRETE PILES. PILE CONCRETE SHALL CONFORM TO STANDARD SPECIFICATIONS CW 3550-R3 AND CW 2160. PILES SHALL BE THE STANDARD LENGTH OF 1800 mm, WITH THE EXCEPTION OF PILES ABOVE THE EXISTING PIER COLUMN PILE CAP, WHICH SHALL BE NOMINALLY 750 mm IN DEPTH. CONTRACTOR TO FIELD LOCATE FENCEPOSTS SUCH THAT FENCE PERIMETER FULLY ENCLOSES EXISTING CONCRETE SETTLEMENT PONDS AND SUCH THAT PILES DO
- POSITION POSTS NOMINALLY AS SHOWN. MAX POST SPACING IS 3050mm.
- CHAIN LINK FENCE SHALL BE FITTED WITH TOP AND BOTTOM RAILS.

NOT CONFLICT WITH EXISTING UNDERGROUND INFRASTRUCTURE.

• THE SUPPLIER SHALL PROVIDE SHOP DRAWINGS OF GATES FOR REVIEW AND ACCEPTANCE BY THE CONTRACT ADMINISTRATOR PRIOR TO FABRICATION.

| BID OP | PORTUNITY No. 202 | -2015 | | | | | | | |
|--|-------------------------------------|-------|--|--|--|--|--|--|--|
| Winnipeg THE CITY OF WINNIPEG Winnipeg PUBLIC WORKS DEPARTMENT ENGINEERING DIVISION | | | | | | | | | |
| NAIRN AVENUE OVERPASS | CITY DRAWING NUMBER B121-2015-03 | | | | | | | | |
| CONCRETE GIRDER AND PIER REPAIRS | SHEET OF 3 7 | | | | | | | | |
| SITE PLAN | DRAWING No. | REV | | | | | | | |
| | 03 | С | | | | | | | |