



BILL OF BEARING PADS
FOR STAGE 1, AREA A (INCLUDING LINE G)

| MARK | No. | DESCRIPTION | LOCATIONS |
|------|-----|-------------------------------------|---------------------------------------|
| B1 | 6 | 200 x 425 x 25 NEOPRENE BEARING PAD | ALONG EXTERIOR WALL ON GRID LINE A |
| B2 | 2 | 200 x 300 x 25 NEOPRENE BEARING PAD | GRID LINE A5 |
| B3 | 72 | 200 x 400 x 25 NEOPRENE BEARING PAD | INTERIOR COLUMNS |
| B4 | 4 | 250 x 325 x 25 NEOPRENE BEARING PAD | GRID LINE G5 |
| B5 | 20 | 200 x 325 x 25 NEOPRENE BEARING PAD | ALONG INTERIOR COLUMNS ON GRID LINE 5 |

BEARING PAD REPLACEMENT PLAN, AREA "A"
1:200

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

APEGM
Certificate of Authorization
Dillon Consulting Limited (MB)
No. 1789 Date: 2015-11-20

LOCATION APPROVED
UNDERGROUND STRUCTURES
N/A
DATE _____
SUPV. U/G STRUCTURES COMMITTEE

NOTE:
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

| | |
|-------------------------------|------------|
| B.M. ELEV. | |
| CONSTRUCTION COMPLETION DATE: | |
| ISSUED FOR TENDER | 2015 11 20 |
| NO. | REVISIONS |

| | |
|-------------|------------|
| CHECKED BY | DRA |
| APPROVED BY | SSR |
| DESIGNED BY | FAK |
| DRAWN BY | TLK |
| SCALE: | AS NOTED |
| HORIZONTAL | |
| VERTICAL | |
| DATE | 2015 11 20 |

DILLON CONSULTING

ENGINEER'S SEAL

RELEASED FOR CONSTRUCTION

THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT
ENGINEERING DIVISION

WILKES RESERVOIR NORTH CELL REHABILITATION
STAGE 1 WEST CELL
BEARING PAD REPLACEMENT PLAN
AREA "A"

CONSULTANT DRAWING NUMBER
14-1411-S-112

SHEET 20 OF 47

CITY DRAWING NUMBER
1-0650R-S0010-001