

- 1. Spot elevations are to govern over contour information.
- 2. Confirm grades with contract administrator after initial grade staking and before proceding with grading operations. Any deviation from the stated slopes is to be approved by the landscape architect prior to
- 3. Contractor is advised that existing grades are given as information only and should be verified on site. Any discrepancies are to be reported to
- 4. All grades shown are FINISH GRADES. Rough grading operations should establish a 'mud' grade sufficiently below finish grade to allow for surface materials. Grading contractor is to establish rough grade within
- 1. Tree Protection Fence (orange safety fence) shall be established PRIOR to foundation works on site and maintained
- 2. Fence shall be established a minimum of 1.8 m (6') from the
- 3. Contractor shall ensure that there will be no storing or stockpiling of material, cross traffic by any machinery, or dumping of any deletarious materials within the tree protection
- 4. Established trees to be preserved shall be pruned by a licensed arbourist prior to construction work beginning and at the end of construction. Initial pruning shall include removal of dead or diseased branches, removal of cross branches, thining of canopy and removal of branches overhaning sufficient to
- 5. Following construction trees shall be fertilized by using root

Existing		Proposed
CB / 231.17m	Catch Basin (Rim ht.)	CB / 231.17m
– AS / 231.17m	Edge of Asphalt	\triangle AS / 231.17m
– DB / 231.17m	Ditch/Swail Bottom	\triangle DB / 231.17m
– MPT / 231.17m	Meter Pit	\triangle MPT / 231.17m
- SW / 231.17m	Edge of Sidewalk or Path	\triangle SW / 231.17m
- SF / 231.17m	Ground / Surface	\triangle SF / 231.17m
- INF / 231.17m	Edge of Infield	\triangle INF / 231.17m
TC / 231.17m	Top of Curb	\triangle TC / 231.17m
→ FH / 231.17m	Top of Fire hydrant	♦ FH / 231.17m



Dean Spearman

General Notes

- 1. All existing trees, sidewalks, curbs, catch basins, culverts, survey markers, to remain are to be protected during construction. Any damage to them is to be made good by the Contractor. Maintain positive drainage into all catch basins and curb inlets.
- 2. All work is to be warrented for a period of not less than 1 year.
- 3. Contractor is to limit operations to the area within the area of work shown on the drawing. Should areas outside of this limit be damaged during the course of construction, Contractor is to make good the damage at his own expense
- 4. Contractor is to obtain location of all utilities prior to construction. If using power equipment to excavate contractor must notify Hydro and Gas and telephone utilities and take steps to avoid damaging their installations.
- 5. All dimensions are in meters unless otherwise
- 6. Spot elevations are to govern over contour information.
- 7. Confirm grades with contract administrator after initial grade staking and before proceding with grading operations. Any deviation from the stated slopes is to be approved by the
- landscape architect prior to construction. 8. Contractor is advised that existing grades are given as information only and should be verified on site. Any discrepancies are to be reported to the Landscape Architect.
- 9. All grades shown are FINISH GRADES. Rough grading operations should establish a 'mud' grade sufficiently below finish grade to allow for surface materials. Grading contractor is to establish rough grade within +/- 2.5 cm.

- This drawing shall not be used for construction unless signed and sealed by Landscape Architect.
- Variations and modifications to the work shown will not be allowed without prior written consent of Landscape Architect.
- Drawing and Specifications, as instruments of service, are the property of the Landscape Architect. The copyright is reserved in the name of the Landscape Architect. No reproduction may be made without the prior written consent of the Landscape Architect
- Contractors/bidders are hereby granted a limited licence to reproduce these drawings for the purposes of bidding. Such

reproductions are not to be used for construction.

B 17-5-2 Issued for RFP A 17-4-17 90% Review No. Date Issue Notes

Valley Gardens Community Centre Spray Pad 218 Antrum Rd. Winnipeg, Mb

Grading Plan

12:47:29 PM Valley Gardens CC - Spray Pad [17-220].vwx