

448-2017 ADDENDUM 1

BRADY ROAD RESOURCE MANAGEMENT FACILITY (BRRMF) DISPOSAL CELL CONSTRUCTION AND LEACHATE COLLECTION AND STORAGE TANKS

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: July 11, 2017
BY: Mario Poveda
TELEPHONE NO. 204 896-1209

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20160708

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 448-2017 Bid Submission with 448-2017 Addendum 1 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R1): Revise items No. 2.2i and 2.2ii to read: Non-woven Geotextile – Cushion, Non-woven Geotextile – Filter, respectively.

Revise item No. 3.C.2.i to read: 250 mm SS Schedule 40S (Installation of drainage pipe in a trench). APPROX. QUANTITY: 10 m.

Add item No. 3.C.2.ii: 250 mm SS Schedule 40S (Installation of drainage pipe in a trench with insulation). APPROX. QUANTITY: 20 m.

Items No. 3.C.2.iv to read: Supply and Installation of 900mm Concrete Catch Basin at Truck Loading Pad, c/w Frame and Cover, SPEC. REF.: CW 2130.

PART E – SPECIFICATIONS

Revise: E7.1.6 to read:

Catch Basin

- (a) Catch basin at the track loading pad shall be in accordance with the City of Winnipeg standard detail SD-025 with H-20 Class D composite frame and cover. The catch basin shall have stainless steel trash basket.

Revise: E7.2.4 to read:

Drainage Pipe Insulation

- (a) 75mm thick rigid polystyrene insulation shall be installed around the drainage pipe from the catch basin at the truck loading pad to the manhole M03 as shown on the drawings.

Revise: E7.5.3 to read:

Supply and Installation of Catch Basin

- (a) Measurement and Payment will be on a per Unit basis. The units to be paid for shall be the total number of catch basins installed in accordance with this Specification and acceptable to the Contract Administrator as computed from measurements made by the Contract Administrator.
- (b) The Unit Price shall include all work and materials, including pipe connection, as required, to install the catch basin.

Items of Work: Supply and Installation of Catch Basin at Track Loading Pad

- a. 900mm Concrete Catch Basin c/w Frame and Cover

Division 31 Earthwork, Section 31 23 33.02:

Revise: 2.3.1 Material for Granular Drainage Blanket shall be 20 mm round clean stone, natural, manufactured, or processed clean, dry, unfrozen, sound, non-cohesive, dense granular material. Contractor shall provide the proposed material gradation to Engineer for approval. Acceptable gradation:

40 mm sieve	100% passing
25 mm sieve	50-80% passing
20 mm sieve	5-20% passing
12.5 mm sieve	0-5% passing
0.075 mm sieve	0-2% passing

DRAWINGS

Replace:

448-2017 _Drawing_ 15-0107-014_C14_R0 with 448-2017 _Addendum_1 Drawing_15-0107-014_C14_R1

448-2017 _Drawing_ 15-0107-014_C18_R0 with 448-2017 _Addendum_1 Drawing_15-0107-014_C18_R1

448-2017 _Drawing_ 15-0107-014_G01_R0 with 448-2017 _Addendum_1 Drawing_15-0107-014_G01_R1

448-2017 _Drawing_ 15-0107-014_M07_R0 with 448-2017 _Addendum_1 Drawing_15-0107-014_M07_R1