

772-2017 ADDENDUM 3

FERMOR AVENUE BRIDGE OVER SEINE RIVER – BRIDGE REHABILITATION, PEDESTRIAN UNDERPASS STRUCTURE AND ROADWORKS FROM ST. ANNE’S ROAD TO ARCHIBALD STREET

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
REQUEST FOR PROPOSAL**

ISSUED: March 2, 2018
BY: Jeffrey Crang, P.Eng., PTOE
TELEPHONE NO. 204 - 453-2301

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE REQUEST FOR PROPOSAL AND
SHALL FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: Ar20160708

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Request for Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Proposal may render your Proposal non-responsive.

PART A – BID SUBMISSION

Replace: 772-2017 Bid Submission_Addendum 2 with 772-2017 – Bid Submission_Addendum 3 . The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R2):

- Revise: E.74(i) to read: Pick up and Install Benches
Revise: E.74(ii) to read: Pick up and Install Waste Receptacles

PART E – SPECIFICATIONS

Revise E21.3.2 to read: Interlocking Paving Stones:

- (a) Concrete interlocking paving stones (unit pavers) for bus stop indicator paver squares, are as shown on the Drawings and as follows:
 - (i) Blue Holland Pavers 200 x 200 x 60 mm.
 - (ii) Concrete interlocking paving stones (unit pavers) for indicator strips shall be precast concrete pavers conforming to CAN3-A231.2, Further to CAN3-A231.2.6.1.1, where concrete pavers are shipped for installation before the pavers are 28 days old, the average compressive strength of these pavers at the time of delivery to the work site shall be not less than 40 MPA.
 - (iii) Supplied by:
 - Barkman Concrete
 - Phone: (204) 667-3310
 - www.barkmanconcrete.com
- (b) Clay brick pavers (unit pavers) for indicator strips and paving areas/fields are shown on the Drawings and as follows:
 - (i) Endicott Clay Brick Paver 194 x 92 x 57 mm (Manganese Ironspot);
 - “ **Approved Equal Product:**
 - Yankee Hill Dark Ironspot 194 x 92 x 57 mm**
 - Manufactured by: Alston Brick Supply Inc., Winnipeg, MB**
 - Phone (204) 292-2832**
 - (ii) Endicott Clay Brick Paver 194 x 92 x 57 mm (Medium Ironspot).

“ **Approved Equal Product:**
Yankee Hill Medium Ironspot 194 x 92 x 57 mm
Manufactured by: Alston Brick Supply Inc., Winnipeg, MB
Phone (204) 292-2832

(iii) Clay Brick pavers (unit pavers) for indicator strips and paving areas/fields shall conform to ASTM C902. Type 1, dimensional tolerance: 1/8”, wire cut face, solid (not cored), as manufactured by Endicott Clay Products Company and supplied by:

Alsip's Industrial Products Ltd.
Winnipeg, MB
Phone: (204) 667-3330

(c) Concrete interlocking paving stones and Clay brick pavers as described or approved equal as accepted by the Contract Administrator in accordance with B7.

- Revise: E39.1.1 to read: Provide all labour, materials, methods, equipment and accessories for the **pick up and installation of benches and waste receptacles.**
- Delete: E39.2
- Delete: E39.2.1
- Revise: E39.3.1(a) to read: **Tache Style Composite Bench with Arm Rests, galvanized, per SCD-121A, City of Winnipeg product no. 52501085GLV, or approved substitute in accordance with B7. For ordering email pwd-cps-orderdesk@winnipeg.ca.**
- Revise: E39.3.2(a) to read: **Waste Receptacle: Metal Slat Type, galvanized, per SCD-119-R2, City of Winnipeg product no. 52501063GLV, approved substitute in accordance with B7, complete with Wire Basket, City of Winnipeg product no. 52501058GLV. For ordering, email pwd-cps-orderdesk@winnipeg.ca.**
- Add: E39.4.5 All posts and supports shall be centred in the concrete footing such that there is a complete collar of concrete around each post and support. Where posts are not perfectly centered there should be a minimum of 51 mm (2”) concrete at any point around the post.
- Add: E39.4.6 All concrete footings for play equipment shall be a minimum of 914 mm (36”) depth, or in accordance with the manufacturer's written specifications, whichever is greater.
- Revise: E39.5.1 to read: The **pick up** and installation of Site Furnishings will be paid for on a unit basis each for the Items of Work listed below. Price shall be payment in full for picking up materials and for performing the Work in accordance with this Specification and accepted by the Contract Administrator. Prices include all mounting hardware.
- Revise: E39.5.2(a) to read: **Pick up** and Install Benches
- Revise: E39.5.2(b) to read: **Pick up** and Install Waste Receptacles
- Add E55.4.22 (a)(i): Approved Equal Product: POURTHANE NS, by W.R. Meadows.
- Revise E59.8.3 (a) to read: Application:
(a) 1.2 m thick 300 mm wide Bituthene 3000 shall be placed as shown in drawings prior to placement of waterproofing membrane in accordance with the Manufacturer's requirements.
- Add: E59.8.3(a)(i) Approved Equal Product: MEL-ROL, by W.R. Meadows.

DRAWINGS

Replace: 772-2017 _Drawing_LS-011-R0 with 772-2017 _Addendum_3 Drawing_LS-011-R1