



776-2017 ADDENDUM 2

2018 REGIONAL STREET RENEWAL PROGRAM: PEMBINA HIGHWAY NORTHBOUND – DUCHARME AVENUE TO CLOUTIER DRIVE

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: February 5, 2018
BY: Taran J Peters, P. Eng
TELEPHONE NO. 204 453-2301

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20160708

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 776-2017 Bid Submission with 776-2017 Addendum 2- Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B(R2): Add Line Items A.36, i), ii), A.39, i), a), A.40, A.41, A.43, A.45, A.61, A.62, i), ii)
Revise Line Items A.6, i), A.32, i), A.33, i), a), b), A.34, i), a), ii), a), iii), a), A.37, ii), iii), A.38, i), A.42, A.44

Page numbering on some forms may be changed as a result.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, February 9, 2018.

PART E – SPECIFICATIONS

- Add:
- E27. REPLACE BENCHING IN BOTTOM OF MANHOLE
 - E27.1 DESCRIPTION
 - E27.1.1 Further to CW 2130, this specification shall cover the replacement of the benching in the bottom of the manhole identified in the Drawings.
 - E27.2 MATERIALS
 - E27.2.1 All materials supplied under this specification shall comply with CW2130 and shall be subject to inspection and testing by the Contract Administrator.
 - E27.3 CONSTRUCTION METHODS
 - E27.3.1 Construction shall take place in accordance with the Drawings and CW2130.

E27.4 MEASUREMENT AND PAYMENT

E27.4.1 Manhole benching work will be measured on a unit basis and will be paid for at the Contract Unit Price per unit for "Replace Benching in Bottom of Manhole", measured as specified herein, which price shall be payment in full for performing all operations required to complete the Work and all other items incidental to the Work included in this Specification.

E28. RELOCATE BOLLARDS

E28.1 DESCRIPTION

E28.1.1 This specification shall cover the relocation of bollards as shown on the Drawings.

E28.2 MATERIALS

E28.2.1 Construction materials shall be 6 mm down limestone or as directed by Contract Administrator.

E28.3 CONSTRUCTION METHODS

E28.3.1 Relocation of the bollards shall be as per Drawings.

E28.3.2 Bollards shall be removed from existing location identified in Drawings.

E28.3.3 The Contractor shall ensure the salvaged bollards are stored safely until they are relocated.

E28.3.4 The Contractor shall confirm the proposed location of the bollards with the Contract Administrator prior to relocation.

E28.3.5 Post excavation shall accommodate bollard and required backfill as directed by Contract Administrator.

E28.3.6 The bollards shall be installed true and plumb.

E28.3.7 Tops of bollards shall match existing bollard height.

E28.3.8 Backfill post excavations with 6mm down limestone. Tamp material thoroughly.

E28.4 MEASUREMENT AND PAYMENT

E28.4.1 The relocation of the bollards will be measured on a unit basis and will be paid for at the Contract Unit Price per unit for "Relocate Bollards", measured as specified herein, which price shall be payment in full for performing all operations required to complete the Work and all other items incidental to the Work included in this Specification.

DRAWINGS

Replace: 776-2017 _Drawing_P-3493-2018_02-R0 with 776-2017 _Addendum_2 Drawing_P-3493-2018_02-R1

776-2017 _Drawing_P-3493-2018_03-R0 with 776-2017 _Addendum_2 Drawing_P-3493-2018_03-R1

776-2017 _Drawing_P-3493-2018_04-R0 with 776-2017 _Addendum_2 Drawing_P-3493-2018_04-R1

776-2017 _Drawing_P-3493-2018_05-R1 with 776-2017 _Addendum_2 Drawing_P-3493-2018_05-R2

776-2017 _Drawing_P-3493-2018_07-R0 with 776-2017 _Addendum_2 Drawing_P-3493-2018_07-R1

776-2017 _Drawing_P-3493-2018_08-R0 with 776-2017 _Addendum_2 Drawing_P-3493-2018_08-R1

776-2017 _Drawing_P-3493-2018_09-R0 with 776-2017 _Addendum_2 Drawing_P-3493-2018_09-R1