

Pick up and Install New Bench

Supply and Install New Sand Under Existing Swingset incl. Drainage to CB

public sidewalk

Supply and Install New Crushed Limestone Pathway

Hazelwood Cresc.

Pick up and Install New Bilingual Park Sign

Supply and Install New Sod

Supply and Install New Wood Fibre Surfacing and Edging incl. Drainage

public sidewalk

property line

Supply and Install New Sand Under Existing Swingset incl. Drainage to CB

Re-Grade and Sod this Area to Drain towards Swale

Supply and Install New 2-5 Yr. Old Play Equipment, Wood Fibre Surfacing and Wood Edging

+/- 90 sq.m. available

Pick up and Install New Bench

Existing Sandbox to be Re-Installed

Supply and Install New Sod


Supply and Install New Timber Edging

Supply and Install New Wood Fibre Surfacing incl. Drainage

Greenwood Ave.



LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.


THE CITY OF WINNIPEG
 Planning, Property and Development Department
 Urban Planning and Design Division
 Unit 15 - 30 Fort Street, Winnipeg, MB, (R3C 4X5)

DESIGNED BY	CH	CHECKED BY	APPROVED BY
DRAWN BY	CH	RELEASED FOR CONSTRUCTION	
HORIZ. SCALE	1 : 300		
VERT. SCALE			
DATE	JULY 2019	MANAGER, PLANNING AND LAND USE DIVISION	DATE

DRAWING TITLE	CAD DRAWING NO.
Hazelwood Cresc. Park 123 Hazelwood Cresc.	
Proposed Plan	DRAWING NO. H.49-B-R1