


DUBLIN AVENUE



NOTES:

1. ADJUST EXISTING MANHOLES AS REQUIRED.
2. ADJUST EXISTING WATER VALVES AS REQUIRED.
3. INSTALL GEOGRID OVER SILTY SUBGRADE AS DIRECTED BY THE CONTRACT ADMINISTRATOR.
4. FOR CB'S, LEADS AND UNDERGROUND INFO SEE SHEETS 37 - 39.
5. INSTALL 18m OF SUBDRAIN EACH SIDE OF LOW POINTS, AS PER SD-245 c/w CAPPED ENDS.
6. INSTALL WATER SERVICE INSULATION ON ALL LONG SIDE SERVICES AS DIRECTED BY CONTRACT ADMINISTRATOR.
7. PRIVATE APPROACHES ARE 200mm REINFORCED CONCRETE.




D — SECTION AT STA 1+440
1:200H 1:100V

## WARNING

IF POWER EQUIPMENT OR EXPLOSIVES ARE TO BE USED FOR EXCAVATION ON THIS PROJECT THE CONTRACTOR MUST:

1) NOTIFY THE GAS COMPANY OF THE PROPOSED LOCATION OF EXCAVATION.

2) TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY INSTALLATIONS.

SEE PROVINCIAL REGULATION 140/92 FOR DETAILS

## METRIC

WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

| EXISTING | LEGEND–PLAN | PROPOSED | EXISTING | LEGEND–PLAN | PROPOSED | EXISTING | LEGEND–PROFILE | PROPOSED |
|---|---|---|---|---|---|---|---|---|
| 150 WM | WATERMAIN | 150 WM | | HYDRO | | 150 WM | WATERMAIN | 150 WM |
| | HYDRANT | | | M.T.S. | | | HYDRANT, VALVE | |
| | VALVE | | | CONCRETE | | 300 LDS | LAND DRAINAGE SEWER | 300 LDS |
| 300 LDS | LAND DRAINAGE SEWER | 300 LDS | | ASPHALT | | 250 WWS | WASTE WATER SEWER | 250 WWS |
| 250 WWS | WASTE WATER SEWER | 250 WWS | | SIDEWALK | | | ℄ PROFILE | |
| | MANHOLE | | | MILL JOINT | | | NORTH OR WEST GUTTER | |
| | CATCH BASIN | | | PROPERTY LINE | | | SOUTH OR EAST GUTTER | |
| | CURB INLET/CATCH PIT | | | SURVEY BAR | | | NORTH OR WEST PL | |
| | TRANSIT STOP | | | DITCH | | | SOUTH OR EAST PL | |
| | CULVERT | | (31.334) | ELEVATION | (32.231) | | NORTH OR WEST DITCH | |
| | GAS | | | SIDEWALK RAMP | | | SOUTH OR EAST DITCH | |

LOCATION APPROVED
UNDERGROUND STRUCTURES

SUPV. U/G STRUCTURES COMMITTEE — DATE

NOTE:
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

B.M. 654528
ELEV. 234.079m

N.E. Cor. King Edward ST. & Dublin Ave., Tblt in 6.1 m Conc. pile in valve box, 31.2m N. of C.L. Pav't. of Dublin Ave. & 10 m E. of C.L. Pav't. of N. bound traffic lane King Edward St. on private property.

| NO. | REVISIONS | DATE | BY |
|---|---|---|---|
| 0 | ISSUED FOR TENDER | 19.09.18 | J.M.B. |

DATE 2019.09.18

Stantec
500 - 311 Portage Avenue, Winnipeg MB Canada
www.stantec.com

| | | | |
|---|---|---|---|
| DESIGNED BY | T.G. | CHECKED BY | S.R.S. |
| DRAWN BY | M.K. | APPROVED BY | S.R.S. |
| HOR. SCALE: | 1:250 | RELEASED FOR CONSTRUCTION: | |
| VERTICAL: | 1:10 | DATE | |

ENGINEER'S SEAL

TENDER DRAWING
NOT TO BE USED FOR CONSTRUCTION

CONSULTANT DRAWING NO.
C-204

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
Stantec Consulting Ltd.
No. 1301

Winnipeg

THE CITY OF WINNIPEG
PUBLIC WORKS DEPARTMENT
ENGINEERING DIVISION

DUBLIN AVENUE BRIDGE REPLACEMENT
DUBLIN AVENUE
STA 1+375 TO STA 1+500
ROADWORKS - RECONSTRUCTION

SHEET 24 OF 48
CAD FILE DRAWING NUMBER 33340c-201-926.dwg
CITY DRAWING NUMBER P-3503-6

U:\133233401\0300_drawing\0302_sheet_files\02_civil\33340c-201-926.dwg
2019/09/18 12:04 PM By: Kontranson, Melanie