



ENCASEMENT DETAIL
N.T.S.



SECTION A–A
N.T.S.

NOTE: CHAINAGES SHOWN ARE ALONG E ℄ OF SHERWIN ROAD



WATER SERVICE INFORMATION

ADDRESS	SIZE (mm) MATERIAL (STREET)	SIZE (mm) MATERIAL (PROP.)	SHORT & LONG MEASUREMENT	CORP. LOCATION	REMARKS
1151 SHERWIN RD COMMERCIAL	50 CU	50 CU	15.24 NSL BLDG 32.77 NNL DUBLIN AV	OPP. S.C. –	**RECONNECT SERVICE** –

* **SERVICES TO BE RENEWED TO ℄. ALL OTHERS TO BE RECONNECTED**

NOTE: ALL VALVES TO BE INSTALLED COUNTERCLOCKWISE TO CLOSE

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
MORRISON HERSHFIELD
No. 1736

METRIC

WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

HORRIZONTAL: 0.0 5.0 10.0 15.0 20.0 25.0
VERTICAL: 0.0 1.0 2.0 3.0 4.0 5.0

WARNING

IF POWER EQUIPMENT OR EXPLOSIVES ARE TO BE USED FOR EXCAVATION ON THIS PROJECT THE CONTRACTOR MUST:

1) NOTIFY THE GAS COMPANY OF THE PROPOSED LOCATION OF EXCAVATION.

2) TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY INSTALLATIONS.

SEE PROVINCIAL REGULATION 210/72 FOR DETAILS

LOCATION APPROVED

UNDERGROUND STRUCTURES

SUPV. U/G STRUCTURES COMMITTEE — DATE

NOTE:

LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

B.M. 23-018
ELEV. 235.300 m
S.E. Cor. Notre Dame Ave. & Sherwin Rd., Tblt. in W. Conc. foundation No. 2070 Notre Dame Ave., 0.8 m S. & 0.7 m below Conc. block of N.W. Cor. of bldg.

NO.	REVISIONS	DATE	BY
C	ISSUED FOR TENDER	20/07/17	HAK
B	ISSUED FOR CLIENT REVIEW	20/05/22	HAK
A	ISSUED FOR 50% REVIEW	20/04/08	HAK

MORRISON HERSHFIELD

DESIGNED BY	JKH	CHECKED BY	HAK
DRAWN BY	DML	APPROVED BY	HAK
SCALE: HORIZONTAL	1:250	RELEASED FOR CONSTRUCTION	
VERTICAL	1:50		
DATE	2020 03 09	DATE	

PLOT DATE: 2020/7/14 4:11:22 PM

ENGINEER'S SEAL

PRELIMINARY DRAWING

NOT TO BE USED FOR CONSTRUCTION

CONSULTANT DRAWING NUMBER

TENDER: 24–2020

Winnipeg

THE CITY OF WINNIPEG

WATER AND WASTE DEPARTMENT
ENGINEERING DIVISION

SHERWIN ROAD RECONSTRUCTION AND CULVERT REPLACEMENT OVER OMAND'S CREEK

SASKATCHEWAN AVE TO NOTRE DAME AVE

WATER MAIN RENEWAL – SHERWIN ROAD

9m S OF DUBLIN AVENUE TO 47m N OF DUBLIN AVENUE

SHEET 44 OF 44

CITY DRAWING NUMBER

D–15769

FILE PATH: P:\2019\190381100–Sherwin Road Reconstruction\09. CAD\07 Sheets\Watermain
FILE NAME: 1903811–Sherwin–WM–PP–01.dwg