



516-2020 ADDENDUM 1

CANORA OUTFALL CHAMBER UPGRADES

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
TENDER**

ISSUED: September 25, 2020
BY: Lunide Milius-Alphonse
TELEPHONE NO. 204 896 - 1209

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE TENDER AND SHALL FORM A PART
OF THE CONTRACT DOCUMENTS**

Template Version: A20190115

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Tender, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 516-2020 Form B-Prices with 516-2020 Addendum 1 - Form B-Prices. The following is a summary of changes incorporated in the replacement of Form B-Prices:

Form B(R1): Revise Item No. 35 to allocate \$55,000.00 for Extra Work Allowance.

Revise Item No. 38 to read: Applicable MRST (for Items 32, 33 & 34).

Page numbering on some forms may be changed as a result.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is 12:00 noon Winnipeg time, **October 1st, 2020**.

PART E – SPECIFICATIONS

Revise: E15.2.2 (b) to read: Slightly brackish water is expected in this area. Therefore, discharge of excavation depressurization water may not be directed to the Assiniboine River and must be directed to the City sanitary sewer.

APPENDICES

Add: Appendix _E Record Drawing SC15581 – Details, Canora Street Gate Chamber and Outfall

QUESTIONS AND ANSWERS

Q1: Under Section E15.2.2.b, it is stated that the water cannot be directly discharged to the Assiniboine River but to the Land Drainage Sewer (LDS). Can the water be disposed of into the wastewater sewer?

A1: Water from dewatering should go to the sanitary system as groundwater can be brackish. A permit to discharge must be provided by the City for discharging any flows into the wastewater system.

Q2: On the record drawing provided in Appendix E, should the unshrinkable fill shown from the bottom of the chamber to the hardpan be removed?

A2: Yes, remove any interfering unshrinkable fill, as and where required.

Q3: Is a clay cofferdam required or has to be provided?

A3: As per clause E8.5 in the Tender, the cofferdam shall be constructed in accordance with 'Sandbag Dike Construction Instruction' as published by the Government of Manitoba Emergency Measures Organization.