

CONSTRUCTION NOTES

1. MILL EXISTING ASPHALT
2. REMOVE EXISTING PAVEMENT AND CONSTRUCT NEW 150mm REINFORCED CONCRETE PAVEMENT
3. CONSTRUCT NEW ASPHALT OVERLAY (+/- 80mm)
4. REMOVE EXISTING SIDEWALK AND CONSTRUCT NEW 100mm CONCRETE SIDEWALK (SD-228A)
5. REMOVE AND REPLACE EXISTING CATCH BASIN WITH NEW 1800mm CATCH BASIN WITH CURB AND GUTTER INLET FRAME (SD-024), AND CONNECT TO EXISTING CB LEAD AS PER CW 2130
6. INSTALL NEW 1800mm CATCH BASIN WITH CURB AND GUTTER INLET FRAME (SD-024), AND CONNECT TO EXISTING SEWER WITH 250mm PVC PIPE AS PER CW 2130
7. REMOVE AND REPLACE CATCH PIT WITH GRATED COVER (AP-008) AND CONNECT TO EXISTING CATCH BASIN AS PER CW 2130
8. INSTALL NEW SQUARE OPENING REDUCER AND NEW CURB AND GUTTER INLET FRAME (AP-011) AND COVER (AP-012)
9. INSTALL NEW FRAME AND SOLID COVER (AP-006, AP-007)
10. INSTALL LIFTER RING AND MATCH TO GRADE
11. ADJUST CURB AND GUTTER INLET FRAME TO GRADE
12. REMOVE EXISTING CURB INLET FRAME AND CUT OFF AND ABANDON CURB INLET LEAD AS PER CW 2130
13. REMOVE EXISTING CURB AND CONSTRUCT NEW BARRIER CURB (SD-205)
14. REGRADE EXISTING PATIO BLOCKS
15. INSTALL NEW SOLID COVER (AP-007)
16. REPLACE CONCRETE CURB AND GUTTER (SD-200)
17. INSTALL NEW STANDARD PRECAST CONCRETE MANHOLE (SD-010) WITH NEW SOLID COVER (AP-007) AS PER CW 2130

GENERAL NOTES

A. PAVEMENT DIMENSIONS ARE TO BACK OF CURB
B. ALL CURB RADII UNDER 15.0m SHALL BE MODIFIED
C. CURB REPLACEMENT AS DIRECTED BY CONTRACT ADMINISTRATOR
D. ASPHALT TIE-IN LIMITS ON APPROACHES TO BE DETERMINED IN FIELD BY CONTRACT ADMINISTRATOR
E. PAVEMENT REPAIRS SHOWN ARE A REPRESENTATIVE SAMPLE OF THE TENDERED QUANTITIES
F. INSTALL DETECTABLE WARNING TILES AS DIRECTED BY CONTRACT ADMINISTRATOR (CW 3326)
G. ADJUST WATER VALVES AND WATER SERVICE SHUT-OFF VALVES TO GRADE IF REQUIRED

PRELIMINARY
NOT TO BE USED FOR CONSTRUCTION

METRIC
WHOLE NUMBERS INDICATE MILLIMETERS
DECIMALIZED NUMBERS INDICATE METERS

BID OPPORTUNITY NO. 1-2021

EXISTING	LEGEND - PLAN	PROPOSED	EXISTING	LEGEND - PLAN	PROPOSED	EXISTING	LEGEND - PROFILE	PROPOSED
	HYDRANT			LDS/WWS		231.000	ELEVATIONS	31.000
	VALVE			WATERMAIN			TREE	
	CURB STOP			GAS			CONCRETE	
	MANHOLE			TRAFFIC SIGNALS			CONCRETE SIDEWALK	
	CATCH BASIN			HYDRO/STREET LIGHT			ASPHALT	
	CURB INLET / CATCH PIT			MTS/SHAW		EXISTING	LEGEND - PLAN	PROPOSED
	HYDRO POLE			CURB RENEWAL			NORTH GUTTER	
	LIGHT STANDARD			PROPERTY LINE			CENTER LINE	
	TRAFFIC SIGNAL POLE			WOOD FENCE			SOUTH GUTTER	
	SURVEY BAR			CONCRETE FENCE			NORTH SIDEWALK	
	GEODETIC BENCH MARK			RAMP CURB			SOUTH SIDEWALK	

LOCATION APPROVED
UNDERGROUND STRUCTURES

SUPR. U/G STRUCTURES COMMITTEE — DATE

NOTE:
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE. BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

B.M. IB @ SW CORNER OF CECIL ST & ELGIN AVE
ELEV. 232.381

NO.	REVISIONS	DATE	BY
2.	ISSUE FOR TENDER	21/03/24	T.G.
1.	SUBMIT FOR PLAN APPROVAL	21/01/06	T.G.

ENGINEERING DIVISION
TECHNOLOGY SERVICES BRANCH
106 - 1155 PACIFIC AVE

DESIGNED BY T.G & M.S
CHECKED BY E.H , M.S , M.L
DRAWN BY T.G
APPROVED BY M.L
HOR. SCALE: 1 : 250
VERTICAL: 1 : 10
DATE 2021/03/19

ENGINEER'S SEAL

Winnipeg

THE CITY OF WINNIPEG
PUBLIC WORKS DEPARTMENT

CECIL ST
FROM NOTRE DAME AVE TO ALEXANDER AVE
ASPHALT OVERLAY AND ASSOCIATED WORKS
FROM STA. 5+35 TO STA. 6+50

CITY DRAWING NUMBER SE-21-14
SHEET 5 OF 18

5