

NOTE: CHAINAGES SHOWN ARE ALONG E. ℙ OF PARK BOULEVARD N

PARK BOULEVARD NORTH

WATER SERVICE INFORMATION

ADDRESS	SIZE (mm) MATERIAL (STREET)	SIZE (mm) MATERIAL (PROP)	SHORT & LONG MEASUREMENT	CORP. LOCATION	REMARKS
229 PARK BLVD N	20.0	20.0	5.2 M SNHL	–	RECONNECT SERVICE
RESIDENTIAL	COPPER	COPPER	46.9 M S HYD OPP 229 PARK BLVD N		
221 PARK BLVD N	38.0	38.0	5.4 M SNHL	2.2 M S SC	RECONNECT SERVICE
RESIDENTIAL	COPPER	COPPER	187.7 M N HYD OPP 235 PARK BLVD N		
215 PARK BLVD N	20.0	20.0	1.7 M SNHL	OPP SC	RECONNECT SERVICE
RESIDENTIAL	COPPER	COPPER	118.2 M S HYD OPP SL NANTON AVE		
211 PARK BLVD N	–	–	–	–	RECONNECT SERVICE
RESIDENTIAL	–	–	–		

*SERVICES TO BE RENEWED TO ℙ. ALL OTHERS TO BE RECONNECTED



ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
KGS Group
No. 245

NOTE: ALL VALVES TO BE INSTALLED COUNTER-CLOCKWISE TO CLOSE

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

0.0 5.0 10.0 15.0 20.0 25.0

WARNING

IF POWER EQUIPMENT OR EXPLOSIVES ARE TO BE USED FOR EXCAVATION ON THIS PROJECT THE CONTRACTOR MUST:

1) NOTIFY THE GAS COMPANY OF THE PROPOSED LOCATION OF EXCAVATION.

2) TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY INSTALLATIONS.

SEE PROVINCIAL REGULATION 210/72 FOR DETAILS

LOCATION APPROVED
UNDERGROUND STRUCTURES

SUPV. U/G STRUCTURES COMMITTEE — DATE

NOTE:

LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

B.M.
ELEV.

NO.	REVISIONS	DATE	BY
0	ISSUED FOR TENDER	2021 04 01	MAT

DESIGNED BY	TLE	CHECKED BY	MAT
DRAWN BY	IT	APPROVED BY	
SCALE: HORIZONTAL	1:250	RELEASED FOR CONSTRUCTION	
VERTICAL	1:50		
DATE	2021 03 31	DATE	

PLOT DATE: 2021 03 31

ENGINEER'S SEAL

PROVINCE OF MANITOBA
M.A. TURKO
Licence No. 30633
REGISTERED ENGINEERING LICENSEE

CONSULTANT DRAWING NUMBER
C103

Winnipeg

THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT
ENGINEERING DIVISION

2021 WATER MAIN RENEWALS
CONTRACT 11

PARK BOULEVARD NORTH
CORYDON AVENUE TO NANTON BOULEVARD
STA 2+25 TO 3+75

SHEET 5 OF 18

CITY DRAWING NUMBER
D-15942

BID OPPORTUNITY: 183-2021
CONTRACT NUMBER:

FILE PATH: P:\Projects\2021\21-0107-002\Design\Mun\
FILE NAME: 21-0107-002_DESIGN.dwg