



KEY PLAN
SCALE: NTS

GENERAL NOTES

- A. ALL EQUIPMENT, DEVICES, FIXTURES REMOVED UNDER DEMOLITION SCOPE WILL BE FIRST OFFERED TO THE CITY FOR REFUSAL FOLLOWED BY CONTRACTOR AND FINALLY TO BE LEGALLY DISPOSED OF.
- B. FOR ALL EXISTING ELECTRICAL DEVICES, EQUIPMENT, ETC. THAT ARE REMOVED, REMOVE EXISTING CONDUIT, WIRING, ETC. BACK TO SOURCE UNLESS OTHERWISE NOTED.
- C. CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING EXACT LAYOUT, ROUTING, ETC. VERIFY EXISTING SERVICES ON SITE.
- D. VERIFY ALL EXISTING EQUIPMENT BEING RE-USED IS WORKING PRIOR TO INSTALLATION. SUPPLY NEW EQUIPMENT AS NECESSARY.
- E. CONTRACTOR TO DETERMINE EXACT CABLE ROUTES ON SITE, WHERE POSSIBLE FOLLOW EXISTING CABLE ROUTES THROUGH BUILDING, RE-USE EXISTING OPENINGS AND PENETRATIONS TO ROUTE CABLES. PROVIDE NEW PENETRATIONS WHERE EXISTING CANNOT BE RE-USED. SEAL ALL PENETRATIONS.
- F. SEAL ALL PENETRATIONS THROUGH FIRE RATED WALLS WITH FIRE STOP MATERIAL AS REQUIRED TO MAINTAIN ASSEMBLY RATING.
- G. COORDINATE FULLY WITH MECHANICAL FOR THE SEQUENCE OF DEMOLITION AND CONSTRUCTION.
- H. COORDINATE WITH THE CITY PRIOR TO SHUT DOWN OF EQUIPMENT.
- I. CONTRACTOR SHALL ENSURE COORDINATION BETWEEN ALL SUBCONTRACTORS AND CONTRACT ADMINISTRATOR, ON AND OFF SITE, AS REQUIRED FOR INSTALLATION OF ELECTRICAL EQUIPMENT.
- J. CONTRACTOR TO VISIT SITE DURING BID AND VERIFY ALL EXISTING SERVICES ON SITE PRIOR TO SUBMITTING BID. REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR DURING BID PERIOD.

4		
3		
2		
1		
0	ISSUED FOR CONSTRUCTION	AS 07/06/22
NO.	Description	BY DDMMYY

ENGINEERS GEOSCIENTISTS
MANITOBA
Certificate of Authorization
SMS Engineering Ltd.
No. 166

PROVINCE OF MANITOBA
A.J. SCHINKEL
Member
35672
REGISTERED PROFESSIONAL ENGINEER

SMS Engineering
770 Bradford Street Winnipeg, Canada (204) 775-0291
20-349-01

Winnipeg Transit

Project Title
TRANSIT MAINTENANCE AND REPAIR BUILDING MECHANICAL UPGRADE - WEST HIGH BAY
WINNIPEG MANITOBA

Drawing Title
PARTIAL MAIN FLOOR PLAN - ELECTRICAL - DEMOLITION

Drawn By	WPD	Checked By	CRM	Approved By	AS
Scale	1/16"=1'-0"	Date	JUNE 2022	Project No.	20-349-01
Revision Number	0	Drawing Number	E1.1	Sheet Order	1 OF 6

1 PARTIAL MAIN FLOOR PLAN - ELECTRICAL - DEMOLITION
SCALE: 1/16" = 1'-0"

DEMOLITION KEY NOTES

- 1. DISCONNECT AND REMOVE WIRE, CONDUIT, ETC. ASSOCIATED WITH EXISTING MAKE UP AIR UNIT AND ASSOCIATED CONTROLLER BACK TO EXISTING DISTRIBUTION. COORDINATE REMOVAL WITH MECHANICAL CONTRACTOR.
- 2. DISCONNECT EXISTING WIRE, CONDUIT, ETC. ASSOCIATED WITH EXISTING GAS FIRED INFRARED HEATER. INFRARED HEATER TO BE REPLACED WITH NEW IN SAME LOCATION. RE-USE CIRCUIT IN NEW CONSTRUCTION. REFER TO DRAWING E2.1 FOR FURTHER INFORMATION. COORDINATE REMOVAL WITH MECHANICAL CONTRACTOR.
- 3. DISCONNECT AND REMOVE EXISTING WIRE, CONDUIT, ETC. ASSOCIATED WITH EXISTING EXHAUST FAN BACK TO EXISTING DISTRIBUTION. COORDINATE REMOVAL WITH MECHANICAL CONTRACTOR.
- 4. EXISTING CABLE TRAYS (TWO TRAYS STACKED AT HIGH LEVEL) TO REMAIN AS IS. NEW TRAY TO BE PROVIDED ABOVE/BELOW EXISTING. REFER TO DRAWING E2.1 FOR FURTHER INFORMATION.
- 5. EXISTING EXHAUST FAN TO BE RELOCATED. REFER TO DRAWING E2.2 FOR FURTHER INFORMATION. COORDINATE RELOCATION WITH MECHANICAL CONTRACTOR.
- 6. EXISTING GAS DETECTION PANEL TO BE INTERCONNECTED TO FIRE ALARM. REFER TO NEW CONSTRUCTION FOR FURTHER INFORMATION.
- 7. EXISTING EXHAUST FAN TO REMAIN.

FILE NAME AND PATH: C:\PROJECTS\2020\20-349 Transit Maintenance Building\03 Civil\Revit\4 E1.dwg; 120919_11_1_GWA_U.dwg
LAYOUT: E1.1
LAST SAVED BY: jgimour
DATE PLT PLOTTED: Monday, April 25, 2023 10:02:23 AM